

11

11

8.5

8.5

11

17

11

11

8.5

8.5

11

17

10X

I certify that the image contained on this frame was made in the normal and regular course of business, on the date stated below and that it is an accurate reproduction of the document submitted to reprographics.

EXCEPTIONS LIST

SUPPORT No.	TYPICAL SUPPORT	CONDUIT (s)	APPROX. LOCATION	EXCEPTION (s)
1084	12	1BE082 1BE084	AUX. BLDG EL. 668' 12' W (34) 3' S (7)	ATTACH TO ADDITIONAL STEEL MEMBER T.S. 6x6x1/2 (WHICH ATTACHES TO EXISTING STEEL WITH DETAIL 56 SH. 356). VERTICAL T.S. IS 3x3x1/2. MAX. LOAD = 150 LB.
1085		15E028 18F083 1BE085	20' W (34) 3' S (7)	
1086	11-4A	2AH002 2AJ008 2AJ011	AUX. BLDG EL. 656' 6' E (72) N SIDE KC	HORIZONTAL 2" DISTANCE ON EAST SIDE OF R2 IS 2" IN LIEU OF 4"
1087		1BPO17	S.W. 3 EL. 634' N/E OF S.W. WALL 70' S.E. OF N.W. WALL	MAX. LOAD ON SUPPORT = 77 LB. PIGGO SHIM EXTENDS 2" ON EITHER SIDE OF T.S. WITH CONDUIT ATTACHED AT C OF T.S.
1088	12-5	2BSA016	27' N.E. OF S.W. WALL	
1089		2ASA015	55' N.E. OF S.W. WALL	
1090		1APO19	62' N.E. OF S.W. WALL	

This drawing and the design it covers are the property of BECHTEL. They are hereby loaned and on the basis of particular agreement that they will not be reproduced, copied, loaned, exhibited, or used except in the limited way and areas permitted by any written consent given by the lender to the borrower.

6-2-82	INCORP FCN-E-5530	S10	HT	RS	RS	RS	RS	RS	RS
1-28-79	ISSUED FOR CONST PER DCN #59	RS	RS	RS	RS	RS	RS	RS	RS
SCALE	W/A	DESIGNED	MIDLAND PLANT UNITS 1 & 2 CONSUMERS POWER COMPANY CONDUIT AND TRAY NOTES, SYMBOLS AND DETAILS	DRAWN	SCHALLMAN	JOB No.	7220	DRAWING No.	E-429(Q) Sh. 1013
REV.									1

PRC APERTURE CARD

8302020497

RIDS

