

11

11

8.5

8.5

11

17

11

11

8.5

8.5

11

17

EXCEPTIONS LIST

This drawing and the design it covers are the property of BECHTEL. They are hereby loaned and used in the borrower's express agreement that they will not be reproduced, copied, loaned, exhibited, or used except in the limited way and periods as permitted by any written agreement given by the lender to the borrower.

SUPPORT NO.	TYPICAL SUPPORT	CONDUIT(S)	APPROX. LOCATION	EXCEPTION(S)
1417	12A	2BJE029	AUX BLDG. EL. 621'-0" EL. 624'-0" COL. (J) & (B)	WELD 1/8" x 2 1/8" x 5 3/8" R TO END OF P1001 OF TYPE 12A SUPPORT.
1414	1	1AE035(4)	AUX BLDG. EL. 644'-6" EL. 647'-6" 4'-3" W 3'-0" S	REDUCED C/C SPACING OF 3/8" B ANCHOR BOLTS ON TWO TYPE 1 SUPPORTS ALLOWS MAX. CAR 430# EA.
1416	24A	2ZE031(4) 1AE033(4) 1AE101(2) 2NE926(4)	AUX BLDG. 1'-8" W 1'-9" S EL. 677'-0"	PREHEAT 1/8" RIGID CRANE GUSSET PLATE AND WELD TYPE 24A CONDUIT SUPPORT TO IT. MAX. WGT. ON SUPPORT 290#.
1417	BOX UNISCHL. 16x12x6	2BC025 (2) 2BC051 (2) 2BC052 (2)	REACTOR BLDG. @ LINE	SUPPORT UNSCHEDULED 16x12x6 BOX FROM EXISTING TYPE 12 SUPPORT BY MEANS OF 2-PIGGIN 3 CASTLEVEES. MAX. LOAD ON TYPE 12 SUPPORT 160#.
1418	12B	2BJA017 2BJA018	AREA 3 AUX BLDG. 10'-0" E 6'-0" S EL. 620'-0"	SUPPORT SHALL BE ATTACHED TO A W18x35. MAX. LOAD SHALL BE 10#. FCR-E-2753
1419	20	2AV002 2AG004 2AG005 2AG007	R BLDG. #2 EL. 635'-0" 5'-0" E	INSTALL TYPE 20 SUPPORTS ON BEAMS THAT ARE NOT PARALLEL. SUPPORT CONDUIT 2AV002 FROM SUPT. TYPE 12A ATTACHED TO IS A 44 MEM. OF THE TYPE 20 SUPT. FCR-E-2897 - MAX. WGT. 160#.
1420	20	2AG007 2BYA009 2BYD00(1) 2AG007	R BLDG. #2 EL. 638'-0" 3'-0" S 2'-0" W	INSTALL TYPE 20 SUPPORT ON BEAMS THAT ARE NOT PARALLEL.
1421	20	2AG028 2AG032	R BLDG. #2 EL. 684'-0" 12'-0" W 17 5'-0" N 17	INSTALL TYPE 20 SUPPORT ON BEAMS THAT ARE NOT PARALLEL.

11-2-82	UNCORP. FCR-E-2897	SID	BM	AD	JA	AD	LINE	OR
11-12-82	UNCORP. FCR-E-753	SID	WT	WAB	AD	JA	AD	LINE
2-10-88	REVISIONS FOR CONDUIT BEAM BEAMS E-1141	CLD	PP	YUN	WAB	AD	LINE	OR
No.	DATE	REVISIONS	BY	CHKD	GROUP	PRJL	CHIEF	ENGR
SCALE	A3/A	DESIGNED		DRAWN	C. L. DeWitt			
ORIGIN								
MIDLAND PLANT UNITS 1 AND 2 CONSUMERS POWER COMPANY CONDUIT AND TRAY NOTES, SYMBOLS, AND DETAILS				JOB No.	7290			
				DRAWING No.		REV.		
				E-4286A	SHT. 1072	2		

16X

I certify that the image contained on this frame was made in the normal and regular course of business, on the date stated below and that it is an accurate reproduction of the document submitted to reprographics.

11-16-82
DATE
OPERATOR
REPROGRAPHICS
G-1249

PRC
APERTURE
CARD

8302020505

RIDS

