

17"

11"

8.5"

8.5"

11"

17"

17"

11"

8.5"

8.5"

11"

17"

This drawing and the design it covers are the property of BECHTEL. They are hereby loaned to the borrower for the purpose of carrying out the work shown hereon. They are not to be reproduced, copied, loaned, exhibited, or used, except in the manner and for the purposes intended, without the written consent of BECHTEL.

EXCEPTIONS LIST				
SUPPORT No.	TYPICAL SUPPORT	CONDUIT(s)	APPROX. LOCATION	EXCEPTION(S)
1622		BLOCK (1) 1/2" PLUS 2DTA018 2BTB014 2BTB009 1BJA022 2BJB030 2BKA023 2BTB009	AUX. BLDG. ELEV 61' COL LINES (7) AND (8)	2 HORIZONTAL MEMBERS, ONE HORIZONTAL IS 4"X 1/4" TS, COLUMN AND 5X5X 1/4" TS. USED AS VERTICALS MAX. LOAD = 900# FCR E-2288
1623	20	BLOCK (1) SUPP 1/2" PLUS 2DTA018 2BTB014 2BTB009 1BJA022 2BJB030 2BTB009 2SIP011	COL. LINE (7) AND 1'-9" N. OF (8)	VERTICALS ARE 4'-9" LONG, 2 HORIZONTAL MEMBERS. MAXIMUM LOAD = 924 LBS. 2 ATTACHMENTS TO ONE VERTICALS HAS TYPE 12A SUPT AND SHIMS ON TS. FCR-E-2622 FCR E-2288
1624		BLOCK (1) SUPP 1/2" PLUS 2DTA018 2DTA003 2BTB009	COL. LINE (7) AND 3'-3" N. OF (8)	2 HORIZONTAL MEMBERS, MAX. LOAD = 871 LBS. VERTICALS ARE 4'-9" LONG HAS TYPE 12A SUPT. ON TS. FCR-E-2622 FCR-E-2288
1625	TYPE 6 WIREWAY SUPPORT	2NFG002 2NFG025	AUX. BLDG. 5'E/6.8' 1' N (8) EL. 677' 675'	2-TYPE 6 WIREWAY SUPPORTS SPACED AT 13" IN LIEU OF 2'-0" MIN. 2-BOLT STRAPS REQUIRED MAX. 180#/SUPPORT FCR E 2892
1626				

AD	6-2-82	INCORP FCR-E-2622	BY	10	AT	DR	SR	1/24/82
AD	5-15-81	FCR E-2288, FCR E-2892	BY	30	AT	DR	SR	1/24/82
AD		ISSUED FOR CONSTRUCTION	BY	30	AT	DR	SR	1/24/82
No.	DATE	REVISIONS	BY	CHK'D	GROUP LEAD	GROUP SUPV	PROJ ENGR	CHIEF SCKR
SCALE	N/A	DESIGNED	P.R.G. L.C.B.	DRAWN	P.R. GALLAGHER	JOB No.	7220	
ORIGIN		MIDLAND PLANT UNITS 1 & 2 CONSUMERS POWER COMPANY CONDUIT AND TRAY NOTES, SYMBOLES AND DETAILS		DRAWING No.		REV.		
				E-42(Q) Sh. 1112		1		

PRC APERTURE CARD

I certify that the image contained on this frame was made in the normal and regular course of business, on the date stated below and that it is an accurate reproduction of the document submitted to reprographics.

8302020509

RIDS

