



TABLE A
EMBEDDED CONDUIT FOR LIGHTING & COMMUNICATION ITEMS

ITEM	DESCRIPTION	QUANTITY	UNIT
1	DESK TEL. OUTLET CONDUIT	418-6	424'-0"
2	MIG-134D	429-6	436'-10"
3	MIS-59D	421-6	426'-0"
4	MIS-59H	432-6	436'-10"
5	VOL. CONTROL OUTLET	423-6	426'-0"
6	MIG-72 DMC	434-4	434'-0"
7	WALL TEL. OUTLET	422'-0	424'-0"
8	JACK STA. OUTLET-2 GANG	432'-6	436'-10"
9	MIS-49 EC	424'-3	426'-0"
10	DESK TEL. OUTLET-DOUBLE GANG	418'-6	SEE PLAN
11		429'-6	SEE PLAN

NOTES:
 1. FOR INSTALLATION DETAILS SEE DWG. A-50204 DWG. G-5421 (L) DETAIL 'A'.
 2. FOR INSTALLATION DETAILS SEE DWG. G-50900 & G-50902.
 3. FOR CONDUIT THROUGH FLOOR SEE DETAIL 'A' DWG. G-5357.
 4. CONDUITS THAT RUN IN SLAB & TURN OUT OF BOTTOM OF SLAB SHALL BE TERMINATED SIMILAR TO DETAIL 'A' DWG. G-5357 (L).
 5. ALL BOXES IN FLOORS SHALL BE MOUNTED FLUSH WITH BOTTOM OF METAL DECK UNLESS OTHERWISE NOTED.
 6. FOR TYP. TERMINATION OF CNDS STUBBING UP TO PEN. BOXES SEE DETAIL 'A' (N).
 THIS DWG. CONTAINS:
 CONSTRUCTION CONTRACT NO. 225
 CONSTRUCTION CONTRACT NO. 223
 CONSTRUCTION CONTRACT NO. 221
 THE SCOPE OF THE 223 CONTRACT INCLUDES ALL EMBEDDED ELECTRICAL WORK IN WALLS & FLOORS ABOVE EL. 390.00.
 THE SCOPE OF THE 225 CONTRACT INCLUDES INSTALLATION OF ELECTRICAL EQUIPMENT & EXPOSED EQUIPMENT GROUNDING TERMINATIONS WITHIN SCOPE OF CONTRACT, & CABLE TRAYS.
 THE SCOPE OF THE 221 CONTRACT INCLUDES ALL EXPOSED GROUNDING TERMINATIONS NOT COVERED BY THE 223 CONTRACT, AND ALL EXPOSED CNDS & BOXES WITHIN SCOPE OF THIS CONTRACT.
 FOR FURTHER DETAILS SEE CONSTRUCTION SPECIFICATIONS.
 PCP-354-0003 & 0053 WAS INCORPORATED IN REV. 4.



INCORPORATED: PCP-354-03, 249, 259, 347, 483, 717 & 903.
 ADDED: (18) NOTE.
 5 112-61
 4 430-41
 3 430-41
 2 430-41
 1 430-41
 APPROVED FOR CONSTRUCTION
 CONFIRMATION REQUIRED:
 1. CONDUIT TERMINATION AT PEN. BOX

RIDS

8303300540

