



ESSENTIAL COMPONENT
THIS ITEM IS OR CONTAINS A
SAFETY RELATED COMPONENT

TABLE I

PART NO	DESCRIPTION	MP ITEM NO	CHAR SIZE
1000	(1) 480V BUS IN (2) SUPPLEMENTARY	170	.12
1001	(1) 480V BUS IN (2) OUT OF SERVICE INDICATOR	159	
1002	(1) 480V BUS IN (2) SUPPLEMENTARY	156	
1003	(1) 480V BUS IN (2) SUPPLEMENTARY	156	
1004	(1) 480V BUS IN (2) SUPPLEMENTARY	156	
1005 A	(1) 480V BUS IN (2) CURRENT	157	
1005 B	(1) 480V BUS IN (2) CURRENT	157	
1005 C	(1) 480V BUS IN (2) CURRENT	157	
1006 A	(1) DC 1A OUTPUT (2) WATTS	158	
1006 B	(1) DC 1A OUTPUT (2) WATTS	158	
1006 C	(1) DC 1A OUTPUT (2) CURRENT	158	
1007 A	(1) DC 1A OUTPUT (2) VOLTAGE	157	
1007 B	(1) DC 1A OUTPUT (2) FREQUENCY	157	
1008 A	(1) 480V BUS A (2) CURRENT	158	
1008 B	(1) 480V BUS A (2) CURRENT	158	
1008 C	(1) 480V BUS A (2) VOLTAGE	158	
1009 A	(1) DC 1A OUTPUT (2) VOLTAGE	157	
1009 B	(1) BATTERY IN (2) CURRENT	157	
1010	(1) 480V BUS IN (2) LEVEL	156	
1011	(1) 480V BUS IN (2) LEVEL	156	.12

**NUCLEAR
SAFETY
RELATED**

SARGENT & LUNDY
ENGINEERS
CLAYTON POWER STATION
ILLINOIS POWER COMPANY
UNIT 1
STATUS 4
FOR IDENTIFICATION ONLY
FOR ASSEMBLY IDENTIFICATION
SPEC. NO. K-2801 PROJ. NO. 4834-D
DEPT. ED & D (WIRING)
RET'D DATE 30 SEPT 80

T-1290

GENERAL NOTES

11202114

INSERT

CLAYTON I

1977-1980

REVISIONS

NO.	DATE	DESCRIPTION	BY	CHKD
1				

- NOTES:**
- FOR ITEMS 2 THRU 150 SEE ELECTRICAL DEVICE LIST 4427450600, ITEM 1.
 - FOR ITEMS 151 THRU 999 SEE INSERT PARTS LIST 112021140001.
 - FOR ITEMS 500 THRU 999 SEE HARDWARE LIST 44274506001, ITEM 135.
 - FOR ITEMS 1000 AND UP SEE MARKING, TABLE I, THIS DRAWING. MARK PER PHOTO PROCESS SPEC 272A7123, ITEM 154.
 - THIS INSERT IS PART OF PGCC PANEL ASBY N13-677.
 - FOR WIRING INFORMATION SEE CONNECTION DIAGRAM SHEET 160, ITEM 152.
 - MARK REF DESIGNATIONS (REAR SIDE) ADJACENT TO DEVICES USING .12 HIGH CHARACTERS.
- ⚠ REF NO'S (1), (2), (3), (4), (5) ARE LINE NO'S PERTAINING TO MARKING SPEC.
 - ⚠ LENGTH AND ROUTING OF CONDUIT AND WIRING TO BE DETERMINED BY MFG.
 - ⚠ REMOVE PAINT IN ALL AREAS WHICH ARE IN CONTACT WITH CONDUIT FITTINGS.
 - ⚠ FOR LEGEND INSERTS, MATCH REF. DESIGNATIONS FOR ITEM 14, TO LEGEND INSERT DWG. 2184242, ITEM 171.
 - ⚠ ON ALL JUV-EL SWITCHES ITEM 13 DISCARD TWO #387 LAMPS SUPPLIED AND REPLACE WITH TWO LAMPS 2K24250000, ITEM 172.

TERA
APERTURE
CARD

NO.	DATE	DESCRIPTION	BY	CHKD
2	11/20/80	REVISED	SCERRA	DW
1	11/20/80	REVISED	SCERRA	DW
1	11/20/80	REVISED	SCERRA	DW
1	11/20/80	REVISED	SCERRA	DW

DALLAS
COPY #
AUG 18 1981

FOR REFERENCE ONLY
Not To Be Used For Construction

16X

R 105

8111120469

