

22"

22"

17"

17"

11"

11"

8.5"

8.5"

8.5"

8.5"

11"

11"

17"

17"

22"

22"

7.1.3 A digit suffix is added to the wire identification number, where required, as follows:

1. Even suffix numbers are added in P.T. circuits after a switch, fuse or contact.
2. Odd suffix numbers are added in C.T. circuits after a coil, switch or contact.
3. Suffix numbers are added in numerical order in circuits other than P.T. and C.T. circuits, after a fuse, switch, coil or contact.

NOTES: 1. These functions have prefixes as follows:

| Function | Prefix |
|----------|--------|
| X-C | 3 |
| Y-H | 1 |
| Z-F | 2 |
| U-C | 2 |

2. These functions have prefixes as follows:

| Functions | Prefix |
|-----------|--------|
| X-H | 1 |
| U-K | 2 |

3. These functions may have different prefix numbers depending on the type of scheme.

7.1.4 Wire identification for interlocks will disregard the color code of paragraph 7.1.1, provided that the wire identification is not in conflict with paragraphs 7.1.2 and 7.1.3. △

| | | | | | |
|---|---------|-------------------------------|----------|--------|-----|
| APPROVED | DATE | BY | REVISION | DATE | BY |
| | | | | | |
| REVISIONS: 1. <i>Revised to paragraph 7.1.4</i> 2. <i>Revised to paragraph 7.1.4</i> | | | | | |
| SCALE | DRAWING | TITLE | DATE | BY | CHK |
| | | MICHAEL PLATE SYSTEMS 1 & 2 | | | |
| | | CONSIGNED POWER COMPANY | | | |
| | | STANBOL AND GENERAL BONES | | | |
| | | FOR SINGLE LINE AND SCHEMATIC | | | |
| | | | 7220 | | |
| | | | 10-28 | Sh. 18 | |

TERA APERTURE CARD

16X

I certify that the image contained on this frame was made in the normal and regular course of business, on the date stated below and that it is an accurate reproduction of the document submitted to reprographics.

10-23-81 *Fred S. [Signature]*

RIDS

811120868

