



GENERAL NOTES:

THE CONSTRUCTION SUBCONTRACTOR'S REMEDIAL ACTION MOBILIZATION ACTIVITIES SHALL BEGIN NO EARLIER THAN 6 P.M. AND END DEMOBILIZATION NO LATER THAN 7 A.M. IT SHALL BE HIS RESPONSIBILITY TO ARRANGE WITH SUPPLIERS TO DELIVER ALL RECONSTRUCTION MATERIALS (I.E., BACKFILL AND CONCRETE) DURING THESE HOURS, UNLESS PRIOR ARRANGEMENTS HAVE BEEN MADE IN WRITING AND APPROVED BY THE UNC CONSTRUCTION INSPECTOR AND THE CITY OF GRAND JUNCTION.

THE CONSTRUCTION SUBCONTRACTOR SHALL PROVIDE ALL NECESSARY TRAFFIC CONTROL MEASURES AS APPROVED BY THE CITY OF GRAND JUNCTION AND UNC HEALTH AND SAFETY. HE SHALL SUBMIT TO THE UNC CONSTRUCTION INSPECTOR A TRAFFIC CONTROL PLAN APPROVED BY THE CITY OF GRAND JUNCTION PRIOR TO THE START OF REMEDIAL ACTION.

THE CONSTRUCTION SUBCONTRACTOR SHALL MAINTAIN SAFE ACCESS TO ALL BUSINESSES. BUSINESSES THAT REMAIN OPEN DURING THE APPROVED REMEDIAL ACTION WORK HOURS (I.E., BARS, THEATERS, AND RESTAURANTS) SHALL HAVE REMEDIAL ACTION PERFORMED AFTER THEIR CLOSE OF BUSINESS AND WITHIN THE APPROVED WORK HOURS.

AT THE END OF EACH SHIFT'S REMEDIAL CONSTRUCTION ACTIVITIES, THE CONSTRUCTION SUBCONTRACTOR SHALL: 1) PROVIDE TEMPORARY PROTECTIVE FENCING AROUND ALL REMEDIAL CONSTRUCTION AREAS. 2) PROVIDE SAFE ACCESS TO BUSINESSES ACROSS REMEDIAL CONSTRUCTION AREAS BY MEANS OF A WOOD-FRAMED WALKWAY OR OTHER APPROVED METHOD. 3) COVER ALL REMEDIAL CONSTRUCTION AREAS WITH A 6 MIL PLASTIC MEMBRANE FOR DUST CONTROL DURING THE DAY. AND 4) REMOVE ALL CONSTRUCTION EQUIPMENT AND MATERIALS FROM PUBLIC AREAS. PUBLIC AREAS SHALL BE SWEEPED CLEAN.

THE CONSTRUCTION SUBCONTRACTOR SHALL NOT PERFORM REMEDIAL ACTION ON MORE THAN 1/2 A CITY BLOCK AT ANY ONE TIME WITHOUT PRIOR WRITTEN APPROVAL BY UNC CONSTRUCTION. A CONSTRUCTION SEQUENCE PLAN SHALL BE SUBMITTED FOR APPROVAL TO UNC CONSTRUCTION PRIOR TO START OF REMEDIAL ACTION.

THE CONSTRUCTION SUBCONTRACTOR SHALL CALL UTILITIES LOCATE SERVICE FOR LOCATIONS OF UNDERGROUND UTILITIES, A MINIMUM OF 2 WORKING DAYS PRIOR TO ANY EXCAVATION.

THE CONSTRUCTION SUBCONTRACTOR IS RESPONSIBLE FOR PROTECTING ALL ART SCULPTURES FROM DUST AND DAMAGE. HOWEVER, IF IT IS DETERMINED THAT A ART SCULPTURE MUST BE REMOVED IN ORDER TO PERFORM REMEDIAL ACTION, HE SHALL NOT REMOVE IT UNTIL HE RECEIVES WRITTEN INSTRUCTIONS FROM UNC CONSTRUCTION.

- DESIGN NOTES
- 1 REMOVE CONCRETE SIDEWALK AS SHOWN ON DRAWINGS. EXCAVATE TAILINGS TO DEPTHS INDICATED. BACKFILL WITH CONTRACTED ROADBASE AND PLACE NEW 4" CONCRETE SIDEWALK AND HANDICAPPED RAMPS PER CITY OF GRAND JUNCTION SPECIFICATIONS.
 - 2 REMOVE STREET SIGNS, STORE AND PROTECT FROM DAMAGE. REINSTALL TO ORIGINAL LOCATIONS PER CITY OF GRAND JUNCTION SPECIFICATIONS.
 - 3 REMOVE CONCRETE TRASH RECEPTACLE, STORE AND PROTECT FROM DAMAGE. REPLACE TO ORIGINAL LOCATION AFTER COMPLETION OF REMEDIAL ACTION CONSTRUCTION.
 - 4 REMOVE CONCRETE STEP. DO NOT REPLACE.
 - 5 DISCONNECT ELECTRICAL AND REMOVE STREET LIGHT PULLBOX. REINSTALL AND RECONNECT ELECTRICAL AS REQUIRED TO COMPLETE REMEDIAL ACTION.
 - 6 EXTERIOR AREA E (RED COLORED BRICK PATTERN STAMPED CONCRETE UTILITY STRIP AND LANDSCAPE PLANTING AREAS) IS EXCLUDED FROM REMEDIAL ACTION.

SITE PLAN

NORTH

SCALE IN FEET

30 15 0 30 60

This drawing, prepared for the Uranium Mill Tailings Remedial Action Project, is for the sole use of the U.S. Department of Energy and its contractors. It is not a land survey plot or an improvement survey plot and is not to be relied upon for the establishment of fence, building, or other future improvement lines.

ANISTEC
APERTURE
CARD

9707020334

NO.	DATE	REVISIONS	BY	CK	A.E.	APP.	NO.	DATE	REVISIONS	BY	CK	A.E.	APP.
RESIDENCE - NO. OF OCCUPANTS													
NON-RESIDENCE - NAME, HRS./WK.													
DESIGNED: <i>1/85</i> <i>6/85</i>													
DRAWN: <i>CK</i> <i>6/85</i>													
CHECKED: <i>1/85</i> <i>6/85</i>													
PROJ. ENG: <i>1/85</i> <i>6/85</i>													
APPROVED: <i>1/85</i> <i>6/85</i>													
SURVEY DATE													
TIME													
VERIFICATION DATE													
U.S. DEPARTMENT OF ENERGY GRAND JUNCTION PROJECTS OFFICE, COLORADO													
400 BLOCK OF MAIN ST. GRAND JUNCTION, CO.													
UNC Geotech													
DOR ID NO. GJ-97003-OT													
BWC NO. 3-C97003-F1 SHT. 1 OF 1													

70 72 74

9707020334

9707020334

* 8807210067

PDR RIDS / U12 FO

9707020334

