



SYM	REVISION	DATE	BY

- NOTES: 1) MAXIMUM AMBIENT TEMPERATURE IS 140 °F (60 °C)  
2) DETECTOR IS APPROVED FOR CLASS I, DIV. 1, GROUP A, B, C, & D HAZARDOUS CONDITIONS  
3) MAXIMUM WEIGHT OF UNIT IS 335 LBS (147.4 KG)  
4) GAGE IS DESIGNED FOR MAXIMUM PIPE PLUS INSULATION O.D. OF 14" (355.6 mm)

**CAUTION**  
**RADIOACTIVE MATERIAL**  
SO [ ]  
MODEL [ ] P/L [ ]  
ISOTOPE [ ] mCi [ ]  
SERIAL NO. [ ] DATE [ ]  
REMOVAL OF THIS LABEL IS PROHIBITED  
THE OHMART CORP., CINCINNATI, OHIO, U.S.A.  
MADE IN U. S. A.  
PT. NO. 38-8422

RADIOACTIVE MATERIAL LABEL  
PT. NO. 38-8422  
S.S. LABEL MAGENTA/YELLOW  
FASTENER/WIRE/DRIVE SCREWS

DIMENSIONS IN INCHES AND INCLUDE PLATING BUT NOT PAINTING	
TOLERANCES:	
UNLESS OTHERWISE SPECIFIED:	
ANGLE TOLERANCES	± 1/2°
CAST OR WELD DIM.	± 1/16"
MACHINED FRACTIONAL	± 1/64"
MACHINED DECIMAL	± .005"
BREAK ALL SHARP CORNERS	

THE OHMART CORPORATION CINCINNATI, OHIO			
OUTLINE: PIPE DENSITY GAGE WITH EXTERNAL MOUNTING TABS			
P.O. NO.	CUSTOMER	DATE	MODEL
		3-15-77	SERIES 3000
DRAWN BY	CHECKED BY	DATE	SCALE
L.H.			1/4"
APPROVED BY	DATE		
			C-30586

C-30586



PDR RIDS

8606090100

