

**APPENDIX F - AGENCY CORRESPONDENCE**

May 6, 2016

Ms. Hillary Young  
Chief Environmental Engineer  
Oklahoma Department of Environmental Quality  
707 North Robinson  
Oklahoma City, OK 73102

Re: Cimarron Environmental Response Trust  
Approval to Inject Treated Water Under Oklahoma's UIC Program

Dear Ms. Young:

Environmental Properties Management LLC (EPM) is the Trustee for the Cimarron Environmental Response Trust, which owns the former nuclear fuel production facility located in Logan County, OK. In December 2015, EPM submitted a decommissioning plan to complete the radiological decommissioning of the site to obtain termination of the Special Nuclear Materials license issued by the US Nuclear Regulatory Commission (NRC). Remediation of impacted groundwater at the site is the last remaining phase of remediation; this effort is jointly regulated by NRC and DEQ.

Groundwater remediation will consist of extracting impacted groundwater from the Cimarron River floodplain and treating the groundwater to remove uranium (the radiological contaminant) and/or nitrate (the non-radiological contaminant). The treated groundwater will comply with the drinking water standards of 30 micrograms per liter (ug/L) uranium and 10 milligrams per liter (mg/L) nitrate. Our plan is to discharge a portion of the treated water to the Cimarron River in accordance with an Oklahoma Pollution Discharge Elimination System (OPDES) permit.

The rest of the treated water will be injected into the shallow sandstones south of the floodplain to flush contaminants to recovery wells located in the floodplain, where it will be recovered for treatment. In the uppermost sandstone, treated water will be injected via shallow wells installed in injection trenches. Trenches will be excavated and backfilled with gravel to provide adequate hydraulic connection with the fractures and bedding planes within the sandstone. All trenches will be installed in an unconfined water-bearing zone, extending below the existing water table. In one area, treated water will be injected into a deeper (approximately 70 feet below ground surface) sandstone via injection wells.

Treated water will not be injected under significant pressure to prevent hydraulic fracturing of the receiving bedrock formations. Shut-off switches will be installed in injection wells to cut off flow when the water reaches a point approximately 3 feet below grade, and to restore flow when the water reaches a point approximately 5 feet below grade. Consequently, injection will be gravity flow, with the pressure head being the difference between the potentiometric head in the well and the water table.



Ms. Hillary Young  
Oklahoma Department of Environmental Quality  
May 6, 2016  
Page 2

Enclosed are two “Inventory of Injection Wells” forms, one for each of the quarter sections in which groundwater remediation will be performed. Also enclosed are four drawings from the Decommissioning Plan. Figure 2-1 provides an aerial image of the site, showing the property boundaries. Drawing BMCD-GWREMEDI-C002 provides an aerial image of most of the site, showing the locations of the groundwater remediation infrastructure.

Injection of treated water will occur within the areas identified on BMCD-GWREMEDI-C002 as “C004” and “C005”. All of the injection infrastructure located in C004 lies within the northwest quarter of Section 12, T16N, R4W. All the injection infrastructure located in C005 lies within the northeast quarter of Section 12, T16N, R4W. The level of detail on this drawing is not sufficient to locate each injection trench and well. Drawings BMCD-GWREMEDI-C004 and BMCD-GWREMEDI-C005 are also enclosed to provide a more detailed picture of the groundwater remediation infrastructure in these two areas. For your convenience, I have annotated the locations of injection wells by placing a red dot on each one.

It is our understanding that these injection trenches and wells are Class 5 injection wells, and that no permit is required, as DEQ regulates Class 5 injection wells through “permit by rule”. It is also our understanding that DEQ must be provided an inventory of wells and monthly reports of injection during operations. Due to the nature of the inventory, EPM attached a table to the “Inventory of Wells” form that describes the depth and length of each injection trench, as well as the depth, screened interval, and proposed maximum flow rate for each injection well.

DEQ approval to inject treated water during this remediation effort is requested herein. Please contact me at 405-642-5152 or via e-mail at [jlux@envpm.com](mailto:jlux@envpm.com) should you have questions or desire clarification.


Sincerely,



Jeff Lux, PE  
Project Manager

Attachments

cc: Paul Davis, Oklahoma Department of Environmental Quality  
Ken Kalman, US Nuclear Regulatory Commission



# United States Department of the Interior

## FISH AND WILDLIFE SERVICE

Division of Ecological Services  
9014 East 21<sup>st</sup> Street  
Tulsa, Oklahoma 74129  
918/581-7458 / (FAX) 918/581-7467



August 25, 2015

### Online Project Review Concurrence Letter

To: Bryan R. Gasper  
Burns & McDonnell Engineering Company, Inc.  
9400 Ward Parkway  
Kansas City, Missouri 64114

Project Name: Cimarron Environmental Response Trust Site in Logan County, Oklahoma  
Burns & McDonnell Project No. 72454  
USFWS Consultation Code: 02EKOK00-2015-SLI-1367

Dear Applicant:

Thank you for using the U.S. Fish and Wildlife Service (Service) Oklahoma Ecological Services Field Office online project review process. By providing this letter in conjunction with your project review package, you are certifying that you have accurately completed the online project review process for the referenced project in accordance with all instructions provided, using the best available information to reach your conclusions. Concurrence with “not likely to adversely affect” determinations does not provide any exemption for violations of section 9 of the ESA or “take” of federally-listed species. The Federal action agency is ultimately responsible for ensuring compliance with the ESA and any take that occurs due to your proposed action would be considered a violation under section 9 of the ESA.

This letter and the enclosed project review package complete the review of your project in accordance with the Endangered Species Act of 1973 (16 U.S.C. 1531-1544, 87 Stat. 884), as amended (ESA). This letter also provides information for your project review under the National Environmental Policy Act (National Environmental Policy Act of 1969 (P.L. 91-190, 42 U.S.C. 4321-4347, 83 Stat. 852), as amended. A copy of this letter and the project review package must be emailed to [okprojectreview@fws.gov](mailto:okprojectreview@fws.gov) for this certification to be valid. This letter and the project review package will be maintained in Service records. **Please allow the OKESFO 60 days to review your information. If the OKESFO determines that the package is not complete, or that additional coordination is necessary, we will contact your office. If after 60 days from the time you emailed your project review package the OKESFO has not contacted your office, consider your section 7 consultation complete.**



The proposed action consists of

Burns & McDonnell Engineering Company, Inc. (Burns & McDonnell) is providing environmental support services for the Cimarron Environmental Response Trust (CERT) at a site formerly owned and operated by Kerr-McGee Nuclear Corporation (KMNC) in Logan County, Oklahoma (Project) (Appendix A). For the purpose of informal consultation with the U.S. Fish and Wildlife Service (USFWS), Burns & McDonnell conducted desktop analyses to evaluate threats to species protected by the Endangered Species Act (ESA) (16 U.S.C. 1531 et seq.), Bald and Golden Eagle Protection Act (BGEPA) (16 U.S.C. 668), and the Migratory Bird Treaty Act (MBTA) (16 U.S.C. 703).

Burns & McDonnell and CERT are requesting a concurrence with the findings of this desktop habitat assessment that the proposed Project has no effect or is not likely to adversely affect species protected under the jurisdiction of the USFWS.

The Project is located at a site that was formerly owned and operated by Kerr-McGee Nuclear Corporation. The onsite facilities were utilized for the production of mixed oxide fuel and uranium fuel, including enriched uranium reactor fuel pellets and eventually fuel rods from 1966 to 1975. During this time, exposure of process water and material to the environment resulted in the contamination of the site groundwater. The site is now owned by the CERT. The concentration of uranium, nitrates, and fluorides in the groundwater must be reduced to achieve unrestricted release of the site and license termination from the Nuclear Regulatory Commission (NRC). Additionally, other mitigation and compliance efforts will be completed to obtain a No Further Remediation Required notice from the Oklahoma Department of Environmental Quality (ODEQ). Mitigation of these constituents will be achieved through the extraction, treatment, and discharge of affected groundwater. These processes will require the construction of groundwater extraction wells, groundwater extraction trenches, groundwater injection wells, groundwater injection trenches, process piping, two outfalls to the Cimarron River, and groundwater treatment facilities. All best management practices (BMPs) will be implemented in compliance with associated erosion and sedimentation regulations for disturbance; thereby minimizing those associated impacts.



The project is expected to be completed:

July 2018

This project review is needed for:

The concentration of uranium, nitrates, and fluorides in the groundwater must be reduced to achieve unrestricted release of the site and license termination from the NRC. License termination from the NRC, in addition to other mitigation and compliance efforts, is needed for a No Further Remediation Required determination from the ODEQ.

The species conclusions table in the enclosed project review package summarizes your ESA conclusions. These conclusions resulted in “not likely to adversely affect/modify” determinations for listed species and critical habitat in relation to potential effects of your proposed project. We certify that the use of the online project review process in strict accordance with the instructions provided as documented in the enclosed project review package results in reaching the appropriate determinations. Therefore, we concur with determinations of “not likely to adversely affect” for listed species and critical habitat reached by proper use of this process. For projects where this particular determination is reached, additional coordination with this office is not needed.

Candidate species are not legally protected pursuant to the ESA. However, the Service encourages efforts to avoid or minimize adverse impacts to them from project effects. Some federal agencies have standing policies that grant limited protections to candidate species. Conservation of candidate species now may preclude future needs to federally list them as endangered or threatened, at which point their legal protection would become required. Please contact this office for additional coordination if your project action area contains candidate species.

Should project plans change or if additional information on the distribution of listed species or critical habitat becomes available, this determination may be reconsidered. You should re-visit the Service's Information, Planning, and Conservation (IPaC) website at <http://ecos/fws.gov/ipac/> within 90 days of project initiation to ensure species information is correct. If new species or critical habitat is identified, this letter is no longer valid and a new project package should be submitted to the OKESFO.

Information about the online project review process including instructions and use, species information, and other information regarding project reviews within Oklahoma is available at our website: <<http://www.fws.gov/southwest/es/oklahoma/>>. If you have any questions, please call 918-581-7458 or send an email message to [OKProjectReview@fws.gov](mailto:OKProjectReview@fws.gov).

Sincerely,  
/s/ Jontie Aldrich  
Acting Field Supervisor  
Oklahoma Ecological Services Field Office

Enclosures:

- 1) ENTIRE PROJECT REVIEW PACKAGE:
  - Species Conclusion Table
  - IPaC Species List and Action Area map
  - This letter (Online Concurrence Letter)
  - (Optional) Additional maps
- 2) Other relevant project data/documents

ODWC state list of protected species by county - Logan County, OK.



**Weis, Brian**

---

**From:** Ok Project Review, FW2 <okprojectreview@fws.gov>  
**Sent:** Monday, August 31, 2015 11:25 AM  
**To:** Gasper, Bryan R.  
**Subject:** Email received by FWS Re: USFWS-OK Kerr-McGee Cimarron project review

Thank you for submitting your project through the U.S. Fish and Wildlife Service's Oklahoma Ecological Service Field Office project review website. This email serves as verification of your submission to [OKprojectreview@fws.gov](mailto:OKprojectreview@fws.gov).

For future requests, please note the following Issues and Updates with the Project Review Webpage:

**Recent Updates**

8/19/2015	Please note that response times described in Steps 7a and 7b have changed from 60 days (65 for hardcopy submissions) to <b>45 days (50 for hard copy submissions)</b> .
8/19/2015	The <b>Online Concurrence Letter</b> (from Step 7a) and the <b>Online Project Review Request Form</b> (Step 7b) have been updated. Please use these new documents with your project request.
3/25/2015	The range of the American burying beetle in Oklahoma has been updated, as a result of positive survey findings along the western edge of the ABB's range in 2014. This change results in a range expansion by 3% in Oklahoma, or an additional 576,738 acres.

**Project Review Website Known Issues**

6/24/2014	Our email return receipt for <a href="mailto:okprojectreview@fws.gov">okprojectreview@fws.gov</a> can provide only one response per email address every four hours. If you submit multiple requests within a four hour window, you may use the return receipt email from your initial project request as proof of additional project submittals.
-----------	--



September 8, 2015

Division Chief  
U.S. Army Corps of Engineers  
CESWT-RO  
1645 South 101st East Ave  
Tulsa, OK 74128

Re: Cimarron Remediation Project

Dear Sir/Madam:

Burns & McDonnell Engineering Company, Inc. (Burns & McDonnell) was retained by the Cimarron Environmental Response Trust (Trust) to provide wetland delineation and permitting services for the proposed Cimarron Remediation Project (Project). These actions are part of a larger effort to remediate groundwater contaminated by a former uranium enrichment facility.

## **INTRODUCTION**

The Project is located at a site that was formerly owned and operated by Kerr-McGee Nuclear Corporation (KMNC) (Figure A-1 in Appendix A). From 1966 to 1975, the onsite facilities were utilized for the production of mixed oxide fuel and uranium fuel including enriched uranium reactor fuel pellets and eventually fuel rods. During this time, exposure of process water and material to the environment resulted in the contamination of site groundwater. The site is now owned by the Trust. The concentration of uranium, nitrates, and fluorides in the groundwater must be reduced to achieve unrestricted release of the site and license termination from the U.S. Nuclear Regulatory Commission (NRC) and the Oklahoma Department of Environmental Quality (DEQ). Mitigation of these constituents will be achieved through the extraction, treatment, and discharge of affected groundwater. These processes will require the construction of groundwater extraction wells, groundwater extraction trenches, groundwater injection wells, groundwater injection trenches, process piping, two outfalls to the Cimarron River, and groundwater treatment facilities.

The Project has the potential to impact wetlands or other waters of the U.S. that may be under the jurisdiction of the U.S. Army Corps of Engineers (USACE) as designated by Section 404 of the Clean Water Act. Burns & McDonnell conducted a wetland delineation for the Project to evaluate for the presence of waters of the U.S., including streams, creeks, and ponds. This report has been prepared to identify and assess potential impacts to these waters.

The Project Survey Area included in the wetland delineation (Figures A-2 and A-3) consists of land that may be disturbed during the construction and operation of groundwater remediation activities and totals approximately 600 acres. Some trenching will occur outside of the Survey Area, but will be confined to existing low-maintenance roads in these areas.

Division Chief  
September 8, 2015  
Page 2

## **METHODS**

The following sections summarize the methods used to review existing data for the Survey Area and to conduct the onsite wetland delineation.

### **Desktop Evaluation**

Burns & McDonnell reviewed available background information for the Survey Area to identify locations where wetlands or streams were likely to be present. This information included:

- U.S. Geological Survey (USGS) 1:24,000 Topographic Quadrangle: Crescent, Oklahoma (2002)
- U.S. Fish and Wildlife Service (USFWS) National Wetland Inventory (NWI) Quadrangle: Crescent, Oklahoma (2002)
- USGS National Hydrography Dataset (NHD) (2014)
- Natural Resources Conservation Service (NRCS) 2012 Soil Survey Geographic (SSURGO) digital data for Logan County, Oklahoma
- Geographic Information System (GIS) User Community aerial images (2015)
- Guidance from the Tulsa office of the USACE regarding the presence/absence of Section 10 Waters.

Wetland presence/absence depicted on the NWI maps was compared with local soil and hydrological data, aerial photography, and topographic maps to assess the most likely locations for wetlands and other waters of the U.S. based on available data. These maps are included as Figures A-2 and A-3.

### **Wetland Delineation**

A jurisdictional wetland delineation was conducted on April 23 through 25, 2015, by Jack Finley, senior wetland scientist, and Michael Hogan, Global Positioning System (GPS) specialist, both with Burns & McDonnell. The wetland delineation was conducted in accordance with the 1987 *Corps of Engineers Wetlands Delineation Manual* (1987 Manual) and Version 2.0 (2010) of the *Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Great Plains Region* (Regional Supplement). Sample plots were established and Wetland Determination Data Forms from the Regional Supplement were completed to characterize the Survey Area (Appendix B). Vegetation, soil conditions, and hydrologic indicators were recorded at each of these sample plots. Locations of the sample plots and water features were recorded using a sub-meter-accurate GPS unit. Natural color photographs of sample plots, wetlands, streams, and uplands were taken onsite and are included as Photographs C-1 through C-21 in Appendix C.



Division Chief  
September 8, 2015  
Page 3

## RESULTS

The following sections describe the results of the existing data review and the completed wetland delineation.

### Desktop Evaluation

Topographic, NWI, and NHD information is shown in Figure A-2. The Survey Area is located in the Cross Timbers Transition Zone of the Central Great Plains Ecoregion.<sup>1</sup> It consists of rough plains that are covered by prairie grasses and eastern red cedar, scattered oaks, and elms. Terrain and vegetation are transitional between the less rugged, grass-covered ecoregions to the west and the hilly oak savanna to the east. Today, land use is a mixture of grassland and fallow ground. This area has ridge and plain topography, with the ridges generally running north-south and the plains flat or gently sloped. The topography of the Survey Area ranges from an elevation of 1,010 feet on the bluffs overlooking the Cimarron River Floodplain to 930 feet within the floodplain. Topographic contours suggest that numerous drainageways likely to contain ephemeral or intermittent streams emanate from the bluffs into the floodplain.

NHD data indicates that the Project lies within the Lower Cimarron-Skelton Drainage Hydrologic Unit Code (HUC8) 11050002. NWI data indicate the presence of two freshwater ponds and one emergent wetland near the southern edge of the western Survey Area. NHD data shows an intermittent stream flowing through the eastern Survey Area toward the Cimarron River, which is a perennial river, with numerous freshwater wetlands evident throughout the channel.

As shown in Figure A-3, the NRCS SSURGO digital data indicate that the Survey Area includes 12 soil types:

- CoIC2 Coyle-Ironmound complex, 3 to 5 percent slopes, eroded
- DiRG Darsil-Rock outcrop complex, 15 to 45 percent slopes
- GaGA Gaddy-Gracemore complex, 0 to 1 percent slopes, frequently flooded
- GadA Gaddy loamy fine sand, 0 to 1 percent slopes, occasionally flooded
- GooE Goodnight fine sand, 1 to 15 percent slopes
- IrCE Ironmound-Coyle complex, 5 to 15 percent slopes
- LerA Lebron clay, 0 to 1 percent slopes, occasionally flooded
- PIT Pits
- URB Urban land
- YaaA Yahola loam, 0 to 1 percent slopes, occasionally flooded

---

<sup>1</sup> Woods, A.J., Omernik, J.M., Butler, D.R., Ford, J.G., Henley, J.E., Hoagland, B.W., Arndt, D.S., and Moran, B.C., 2005, *Ecoregions of Oklahoma* (color poster with map, descriptive text, summary tables, and photographs): Reston, Virginia, U.S. Geological Survey (map scale 1:1,250,000).

Division Chief  
September 8, 2015  
Page 4

- YahA Yahola fine sandy loam, 0 to 1 percent slopes, occasionally flooded
- W Water

Of these 12 soil types, 6 (Gaddy-Gracemore complex, 0 to 1 percent slopes, frequently flooded; Gaddy loamy fine sand, 0 to 1 percent slopes, occasionally flooded; Goodnight fine sand, 1 to 15 percent slopes; Lebron clay, 0 to 1 percent slopes, occasionally flooded; Yahola loam, 0 to 1 percent slopes, occasionally flooded; and the Yahola fine sandy loam, 0 to 1 percent slopes) are included on the local and national hydric soil lists.

Aerial imagery indicates a river system with a forested riparian buffer followed by a broad herbaceous community. This community ends abruptly at another woody community that runs in a southwest to northeast direction. Several prominent wooded drainageways emanate from this community in a southerly direction. Numerous areas of disturbance including roads and excavated areas are present. Several dammed impoundments are adjacent to the Survey Area.

#### **Wetland Delineation**

On April 22 through 24, 2015, Jack Finley, senior wetland scientist, and Michael Hogan, Global Positioning System (GPS) Specialist, both with Burns & McDonnell, conducted a wetland delineation of the Survey Area. The vegetation, soils, and hydrology within the Survey Area are described below.

*Vegetation.* The Survey Area was largely composed of grassland. Typical vegetation in the upland portions of the Survey Area included drooping brome (*Bromus tectorum*), southern sedge (*Carex australis*), goldenrod (*Solidago* sp.), common hackberry (*Celtis occidentalis*), and green ash (*Fraxinus pennsylvanica*).

*Soils.* Typical upland soils were dark reddish brown (5YR 3/4 or 5YR 4/6) or dark red (2.5YR 4/4 or 2.5YR 3/4) and silt or sand in texture. Wetland soils were also dark reddish brown (5YR 3/4 or 5YR 4/6) and sandy or silty in texture.

*Hydrology.* The primary sources of hydrology within the Survey Area are precipitation and surface water runoff. Common hydrology indicators included geomorphic position and a positive FAC-Neutral Test.

#### **Jurisdictional Areas**

One Palustrine Emergent (PEM) wetland, one perennial stream, and two intermittent streams were identified during the wetland delineation (Figure A-4; Photographs C-3 through C-21). Sample plots were located in the wetlands and adjacent uplands. USACE data forms from the Regional Supplement were completed for each sample plot (Appendix B).



Division Chief  
September 8, 2015  
Page 5

### **Wetlands**

*Wetland 1 (W-1)*. W-1 (0.28 acre) is a PEM wetland located in the northern portion of the Survey Area (Figure A-4; Photographs C-6, C-7, and C-9). Vegetation in this wetland was dominated by littletooth sedge (*Carex microdonta*), reed canary grass (*Phalaris arundinacea*), and stinging nettle (*Urtica dioica*). The hydrology was indicated by Geomorphic Position (D2) and a positive FAC-Neutral Test (A2).

### **Streams**

*Stream 1 (S-1)* S-1 is a perennial stream (Cimarron River) that flows in an easterly direction at the northern boundary of the Survey Area (Figure A-4; Photographs C-15 and C-16). S-1 averaged more than 400 feet wide, and 988 linear feet of its length were delineated within the Survey Area. S-1 is approximately 6 feet deep at the ordinary high water mark (OHWM). Surrounding vegetation included sandbar willow (*Salix interior*) and eastern red cedar (*Juniperus virginiana*).

*Stream 2 (S-2)* S-2 is an intermittent stream that flows in a northerly direction through the Survey Area (Figure A-4; Photographs C-17 and C-18). S-2 averaged 3 feet wide, and 326 linear feet of its length were delineated within the Survey Area. S-2 had a depth of 0.5 foot at the OHWM, and the substrate of S-2 consisted of silt and sandstone.

*Stream 3 (S-3)* S-3 is an intermittent stream that flows in a northerly direction through the Survey Area (Figure A-4; Photographs C-20 and C-21). S-3 averaged 3 feet wide, and 1,395 linear feet of its length were delineated within the Survey Area. The substrate of S-3 consisted of silt and sandstone, and the depth at the OHWM was 0.3 foot.

### **SUMMARY**

Burns & McDonnell conducted a wetland delineation of the Survey Area to identify wetlands and other waters of the U.S. One wetland and three stream channels were identified. Although impacts to these waters will be avoided to the extent practicable, the installation of the two outfall structures will create permanent, unavoidable impacts at the Cimarron River (S-1). Additionally, temporary impacts will occur at W-1 due to open trenching during construction of the outfall at that location. As a result, it is anticipated that the Project will require authorization under a Nationwide Permit 7 (NWP 7) for intake and outfall structures, requiring formal notification to the USACE.

Burns & McDonnell on behalf of the Trust would like to respectfully request a preliminary jurisdictional determination of the waters described in this report. Additionally, we would like to request concurrence that the Project, as currently designed, would qualify for authorization under a NWP 7.



Division Chief  
September 8, 2015  
Page 6

If you have any questions or require additional information, please contact me by telephone at (816) 822-4311 or by e-mail at [jbailey@burnsmcd.com](mailto:jbailey@burnsmcd.com).

Sincerely,

A handwritten signature in blue ink that reads "Justin E. Bailey".

Justin E. Bailey, PWS  
Senior Wetland Specialist

Attachments:

- Appendix A - Figures
- Appendix B - USACE Data Forms
- Appendix C - Ground Photographs

cc: Brian Weis – Burns & McDonnell  
John Hesemann – Burns & McDonnell  
Jeff Lux – Environmental Properties Management



02/09/2017

David Ball  
Logan County Emergency Management  
312 East Harrison  
Guthrie, OK 73044

Re: Floodplain Permit Application for the Environmental Properties Management, LLC  
Groundwater Remediation Project

Dear Mr. Ball,

Environmental Properties Management LLC (EPM), a Trustee for the Cimarron Environmental Response Trust (CERT), has retained Burns & McDonnell Engineering Company, Inc. (Burns & McDonnell) to provide FEMA floodplain permitting for the proposed Groundwater Remediation Project (Project). These actions are part of a larger effort to remediate groundwater contaminated by a former nuclear fuel production facility.

The Project is located at a site that was formerly owned and operated by Kerr-McGee Nuclear Corporation (KMNC) in Logan County, Oklahoma. From 1966 to 1975, the onsite facilities were utilized for the production of mixed oxide fuel and uranium fuel including enriched uranium reactor fuel pellets and eventually fuel rods. During this time, exposure of process water and material to the environment resulted in the contamination of site groundwater. The site is now owned by CERT. The concentration of uranium, nitrates, and fluorides in the groundwater must be reduced to achieve unrestricted release of the site and license termination from the U.S. Nuclear Regulatory Commission (NRC) and the Oklahoma Department of Environmental Quality (DEQ). Mitigation of these constituents will be achieved through the extraction, treatment, and discharge of affected groundwater.

This phase of the Project will construct four water injection trenches and one groundwater extraction trench, followed by testing of injection and extraction efficiencies as part of final design for the Project. Two of the test trenches will be within the FEMA 100-year floodplain. These test trenches will be excavated to the specified dimensions. The injection wells will be constructed in the trenches and the then the trench will be partially backfilled with aggregate. The trenches will then be returned to their previous contours using the excavated spoils and stabilized.

The groundwater injection and extraction efficiency will be tested by placing a frac tank, utilized to supply clean water, near the targeted injection trench and moved as necessary. Following completion of injection testing activities, this frac tank will be removed from the Project site. Two frac tanks will be utilized to store water generated during the extraction trench tests. These frac tanks will remain onsite pending characterization and treatment (as necessary) of the extracted water. These tanks will be staged outside of the FEMA 100-year floodplain to avoid any potential impacts, to the extent practicable, should flooding occur.

David Ball  
Logan County Emergency Management  
01/27/2017  
Page 2

Per our phone conversation, the following procedures will be followed during construction:

- The spoils will be stockpiled outside of the FEMA 100-year floodplain during construction activities.
- Equipment and materials will not be staged within the limits of the FEMA 100-year floodplain.
- Excess spoils will be spread and stabilized outside of the FEMA 100-year floodplain.

Enclosed is the Logan County Floodplain Development Application, General Vicinity Map, Excavation and Grading Plans, and \$100 permit fee. If you require any additional information or clarification, please contact me by phone at (816) 605-7821, or by email at [kgouvion@burnsmcd.com](mailto:kgouvion@burnsmcd.com).

Sincerely,



Ken Gouvion, CISEC  
Staff Environmental Scientist

Enclosure


**APPENDIX G - EROSION AND SEDIMENT CONTROL PLAN**



Disclaimer: BMPs on map may not be exact or to scale. The authorized contractor/owner's representative will determine the appropriate BMPs to be used onsite and their locations prior to the start of soil-disturbing activities. The ESC Plan will be updated accordingly.



Dry detention basin will be used for dewatering activities.



Injection Well	Silt Fence	NHD Stream	ARC Corridor
Extraction Well	Project Boundary	NHD Waterbody	NWI Freshwater Emergent
Trench	Wetland Survey Boundary	100-foot Natural Vegetated Buffer	NWI Freshwater Forested/Shrub
Soil Stockpile	Delineated Stream	100-year FEMA Floodplain	NWI Freshwater Pond


Scale in Feet

Erosion and Sediment Control Plan  
Groundwater Remediation Project  
Cimarron Environmental  
Response Trust  
Logan County, Oklahoma  
Page 1 of 2

Path: Z:\General\KCMES\Depth\Enviro\_Monitoring\SWPPP02\Working Documents\99761 CERT Groundwater Remediation Project\_OK01\GISDataFiles\ArcDocs\CERT ESC Plan.mxd 1/31/2017  
 COPYRIGHT © 2017 BURNS & McDONNELL ENGINEERING COMPANY, INC.  
 Service Layer Credits: Copyright © 2013 National Geographic Society, i-cubed  
 Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community




Disclaimer: BMPs on map may not be exact or to scale. The authorized contractor/owner's representative will determine the appropriate BMPs to be used onsite and their locations prior to the start of soil-disturbing activities. The ESC Plan will be updated accordingly.



Injection Well	Silt Fence	NHD Stream	ARC Corridor
Extraction Well	Project Boundary	NHD Waterbody	NWI Freshwater Emergent
Trench	Wetland Survey Boundary	100-foot Natural Vegetated Buffer	NWI Freshwater Forested/Shrub
Soil Stockpile	Delineated Stream	100-year FEMA Floodplain	NWI Freshwater Pond

Erosion and Sediment Control Plan  
 Groundwater Remediation Project  
 Cimarron Environmental  
 Response Trust  
 Logan County, Oklahoma  
 Page 2 of 2



Path: Z:\General\KCMES\Depth\Enviro\_Monitoring\SWPPP\02 Working Documents\09761 CERT Groundwater Remediation Project, OK\01 GIS\MapFiles\ArcDocs\CERT ESC Plan.mxd 1/31/2017  
 COPYRIGHT © 2017 BURNS & McDONNELL ENGINEERING COMPANY, INC.  
 Service Layer Credits: Copyright © 2013 National Geographic Society, i-cubed  
 Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

Source: ESRI; USGS NHD; USFWS NWI; FEMA Floodplains; OK DEQ; Cimarron Environmental Response Trust; Burns & McDonnell Engineering Company, Inc.

Issued: 1/31/2017





no.	date	by	ckd	description
A	2/01/17	BC	JH	FOR REVIEW

NOTE:  
TOPOGRAPHY SHOWN IS FROM AN  
AERIAL SURVEY DATED MAY 2014.

**PRELIMINARY - NOT  
FOR CONSTRUCTION**



9400 WARD PARKWAY  
KANSAS CITY, MO 64114  
816-333-9400  
OKLAHOMA FIRM LICENSEE NO. 421

JANUARY 2017	B. CLEMENT
B. CLEMENT	checked J. HESEMANN




**Cimarron Environmental Response Trust  
OVERALL SITE PLAN**


project 96785	contract
drawing <b>BMCD-GWREMED-C001</b>	rev. <b>A</b>
sheet 3	of 11 sheets
file C001-OVERALL SITE PLAN.DWG	

INCHES  
 BURNS & McDONNELL ENGINEERING COMPANY, INC.






UP-1 PILOT TESTING AREA



UP-2 PILOT TESTING AREA

- NOTES:**
- FRAC TANKS, EQUIPMENT TRENCH SPOILS, ETC. SHALL BE STAGED AT AN ELEVATION ABOVE THE FEMA 100-YEAR FLOOD ELEVATION, IN ACCORDANCE WITH THE SWPPP AT THE END OF EACH WORK DAY.
  - MONITOR WELL CONSTRUCTION MATERIALS SHALL BE IN ACCORDANCE WITH THE MONITOR WELL SCHEDULE INCLUDED ON M101.
  - MONITOR WELL CONSTRUCTION AND INSTALLATION SHALL BE COMPLETED BY A LICENSED DRILLER IN THE STATE OF OKLAHOMA AND SHALL BE REGISTERED WITH THE OKLAHOMA DEPARTMENT OF ENVIRONMENTAL EQUALITY.
  - MONITOR WELLS INSTALLED WITHIN INJECTION AND EXTRACTION TRENCHES SHALL HAVE TOTAL DEPTHS AND SCREEN INTERVALS THAT COMPLETELY PENETRATE THE DEPTH OF THE TRENCH AT EACH LOCATION
  - CONTRACTOR SHALL PROTECT EXISTING MONITOR WELLS DURING INJECTION AND EXTRACTION TRENCH INSTALLATION AND PILOT TESTING ACTIVITIES. CONTRACTOR MAY SUBMIT ALTERNATE TRENCH ALIGNMENT FOR ENGINEER APPROVAL IN EFFORT TO PROTECT EXISTING MONITOR WELLS.
  - TOPOGRAPHY SHOWN IS FROM AN AERIAL SURVEY DATED MAY 2014.
  - GROUNDWATER ELEVATION CONTOURS FOR WESTERN AREA TREATMENT FACILITY CREATED FROM WATER LEVEL MEASUREMENTS FROM SANDSTONE A MONITOR WELLS ON MARCH 18, 2015.
  - SEE SHEET C202 FOR CONSTRUCTION DETAILS OF MONITOR WELLS AND INJECTION WELLS.



**PRELIMINARY - NOT FOR CONSTRUCTION**



9400 WARD PARKWAY  
KANSAS CITY, MO 64114  
816-333-9400  
OKLAHOMA FIRM LICENSEE NO. 421

JANUARY 2017	B. CLEMENT
B. CLEMENT	checked J. HESEMANN



Cimarron Environmental Response Trust  
WESTERN AREA SITE PLAN

96785	contract	rev.
		<b>A</b>
sheet 4	of 11	sheets
file C001-OVERALL SITE PLAN.DWG		

BURNS & McDONNELL ENGINEERING COMPANY, INC.

no.	date	by	ckd	description
A	2/01/17	BC	JH	FOR REVIEW

- NOTES:
1. FRAC TANKS, EQUIPMENT, TRENCH SPOILS, ETC. SHALL BE STAGED AT AN ELEVATION ABOVE THE FEMA 100-YEAR FLOOD ELEVATION IN ACCORDANCE WITH THE SWPPP.
  2. CONTRACTOR SHALL PROTECT EXISTING MONITOR WELLS DURING INJECTION AND EXTRACTION TRENCH INSTALLATION AND PILOT TESTING ACTIVITIES. CONTRACTOR MAY SUBMIT ALTERNATE TRENCH ALIGNMENT FOR ENGINEER APPROVAL IN EFFORT TO PROTECT EXISTING MONITOR WELLS.
  3. TOPOGRAPHY SHOWN IS FROM AN AERIAL SURVEY DATED MAY 2014.



**PRELIMINARY - NOT FOR CONSTRUCTION**



9400 WARD PARKWAY  
 KANSAS CITY, MO 64114  
 816-333-9400  
 OKLAHOMA FIRM LICENSEE NO. 421


FEBRUARY 2017	B. CLEMENT
B. CLEMENT	checked J. HESEMANN

Cimmaron Environmental Response Trust  
 BURIAL AREA 1  
 SITE PLAN


96785	contract	rev.
BMCD-GWREMED-C002		<b>A</b>
sheet 5	of 11	sheets
file C001-OVERALL SITE PLAN.DWG		

INCHES  
 BURNS & MCDONNELL ENGINEERING COMPANY, INC.






INJECTION TRENCH GWI-UP1-01  
DETAIL




INJECTION TRENCH GWI-UP1-02  
DETAIL

- NOTES:
1. TOPOGRAPHY SHOWN IS FROM AN AERIAL SURVEY DATED MAY 2014.
  2. STATIC PIEZOMETRIC SURFACE FOR WESTERN AREA TREATMENT FACILITY CREATED FROM WATER LEVEL MEASUREMENTS FROM SANDSTONE A MONITOR WELLS ON MARCH 18, 2015.
  3. SUBSURFACE INFORMATION SHOWN IS BASED ON LIMITED DATA AVAILABLE FROM BORING LOGS COMPLETED AT MONITOR WELLS 1341, 1345, AND 1354 THAT IS PROJECTED TO THE TRENCH ALIGNMENTS. SUBSURFACE INFORMATION SHOWN SHOULD BE CONSIDERED APPROXIMATE.
  4. EXISTING SANDSTONE A MONITOR WELL LOCATIONS AND SCREEN INTERVALS ARE PROJECTED IN CROSS SECTION.
  5. INJECTION WELLS AND MONITOR WELLS INSTALLED IN INJECTION TRENCHES WILL BE CONSTRUCTED SO THAT SCREEN INTERVAL COMPLETELY PENETRATE THE THE VERTICAL THICKNESS OF THE INJECTION TRENCH.
  6. DISTURBED AREAS SHALL BE SEEDED AND STABILIZED IN ACCORDANCE WITH THE ODOT COMMISSION SPECIFICATIONS. SEED MIXTURE SHALL BE IN ACCORDANCE WITH TABLE 735.1 OF THE ODOT COMMISSION CHAPTER 735. SUBMIT SEED MIXTURE TO ENGINEER FOR APPROVAL PRIOR TO APPLICATION.
  7. TRENCH DEPTH SHALL EXTEND TO THE BASE OF SANDSTONE A AS ENCOUNTERED IN THE FIELD OR UP TO 30 FEET BELOW GROUND SURFACE, WHICHEVER IS SHALLOWER.
  8. SEE SHEET C202 FOR MONITOR WELL AND INJECTION WELL CONSTRUCTION DETAILS.

no.	date	by	ckd	description
A	2/01/17	BC	JH	FOR REVIEW



INJECTION TRENCH GWI-UP1-01  
ELEVATION VIEW





INJECTION TRENCH GWI-UP1-02  
ELEVATION VIEW

**PRELIMINARY - NOT FOR CONSTRUCTION**



9400 WARD PARKWAY  
KANSAS CITY, MO 64114  
816-333-9400  
OKLAHOMA FIRM LICENSEE NO. 421

JANUARY 2017	B. CLEMENT
B. CLEMENT	checked J. HESEMANN



**Cimmaron Environmental Response Trust**  
UP-1 INJECTION TRENCH DETAILS

96785 | contract


rev. **A**

sheet 6 of 10 sheets  
file C001-OVERALL SITE PLAN.DWG

BURNS & MCDONNELL ENGINEERING COMPANY, INC.

no.	date	by	ckd	description
A	2/01/17	BC	JH	FOR REVIEW

- NOTES:
1. TOPOGRAPHY SHOWN IS FROM AN AERIAL SURVEY DATED MAY 2014.
  2. STATIC PIEZOMETRIC SURFACE CREATED FROM WATER LEVEL MEASUREMENTS FROM SANDSTONE A MONITOR WELLS ON MARCH 18, 2015.
  3. SUBSURFACE INFORMATION SHOWN IS BASED ON AVAILABLE BORING LOGS FOR NEARBY MONITOR WELLS. SUBSURFACE INFORMATION SHOWN SHOULD BE CONSIDERED APPROXIMATE.
  4. EXISTING SANDSTONE A MONITOR WELL LOCATIONS AND SCREEN INTERVALS ARE PROJECTED IN CROSS SECTION.
  5. INJECTION WELLS AND MONITOR WELLS INSTALLED IN INJECTION TRENCHES WILL BE CONSTRUCTED SO THAT SCREEN INTERVAL COMPLETELY PENETRATE THE THE VERTICAL THICKNESS OF THE INJECTION TRENCH.
  6. TRENCH DEPTH SHALL EXTEND TO THE BASE OF SANDSTONE A AS ENCOUNTERED IN THE FIELD OR UP TO 30 FEET BELOW GROUND SURFACE, WHICHEVER IS SHALLOWER.
  7. SEE SHEET C202 FOR ADDITIONAL MONITOR WELL AND INJECTION WELL CONSTRUCTION DETAILS.



**PRELIMINARY - NOT FOR CONSTRUCTION**




9400 WARD PARKWAY  
KANSAS CITY, MO 64114  
816-333-9400  
OKLAHOMA FIRM LICENSE NO. 421


JANUARY 2017	B. CLEMENT
B. CLEMENT	checked J. HESEMANN

**Cimmaron Environmental Response Trust**  
UP-2 INJECTION TRENCH DETAILS


96785	contract
	rev.
<b>BMCD-GWREMED-C102</b>	<b>A</b>
sheet 7 of 11 sheets	file C001-OVERALL SITE PLAN.DWG




**INJECTION TRENCH GWI-UP2-01  
DETAIL**



**INJECTION TRENCH GWI-UP2-04  
DETAIL**



**INJECTION TRENCH GWI-UP2-01  
ELEVATION VIEW**




**INJECTION TRENCH GWI-UP2-04  
ELEVATION VIEW**




BURNS & MCDONNELL ENGINEERING COMPANY, INC.

no.	date	by	ckd	description
A	2/01/17	BC	JH	FOR REVIEW



**EXTRACTION TRENCH GETR-BA1-01  
DETAIL**


1  
C003



**INJECTION TRENCH GWI-BA1-01  
DETAIL**


2  
C003

- NOTES:**
1. TOPOGRAPHY SHOWN IS FROM AN AERIAL SURVEY DATED MAY 2014.
  2. STATIC PIEZOMETRIC SURFACE FOR BURIAL AREA 1 CREATED FROM WATER LEVEL MEASUREMENTS FROM SANDSTONE B AND TRANSITION ZONE MONITOR WELLS ON AUGUST 8, 2016.
  3. EXISTING SANDSTONE B AND TRANSITION ZONE MONITOR WELL LOCATIONS AND SCREEN INTERVALS ARE PROJECTED IN CROSS SECTION.
  4. CONTRACTOR SHALL ABANDON EXISTING MONITOR WELLS PRIOR TO TRENCH CONSTRUCTION AS DIRECTED BY ENGINEER. FOLLOWING COMPLETION OF TRENCH INSTALLATION, CONTRACTOR SHALL RE-INSTALL MONITOR WELLS AS DIRECTED BY ENGINEER. ENGINEER WILL PROVIDE MONITOR WELL LOCATIONS AND WELL CONSTRUCTION DETAILS FOR BA1 MONITOR WELLS NOT DEPICTED ON SHEET C103 UPON COMPLETION AND ACCEPTANCE OF TRENCH INSTALLATION.
  5. MONITOR WELL 1407 SHALL BE CONSTRUCTED WITH A SCREEN INTERVAL FROM 8 TO 13 FEET BELOW GROUND SURFACE. MONITOR WELL 1408 SHALL BE CONSTRUCTED WITH A SCREEN INTERVAL ACROSS BOTH THE TRANSITION ZONE AND SANDSTONE B. SEE SHEET C202 FOR CONSTRUCTION DETAILS FOR ALL OTHER MONITOR WELL, INJECTION WELL, AND SUMPS DEPICTED ON SHEETS C003 AND C103.



**EXTRACTION TRENCH GETR-BA1-01  
ELEVATION VIEW**

A



**INJECTION TRENCH GWI-BA1-01  
ELEVATION VIEW**



B

**PRELIMINARY - NOT  
FOR CONSTRUCTION**



9400 WARD PARKWAY  
KANSAS CITY, MO 64114  
816-333-9400  
OKLAHOMA FIRM LICENSEE NO. 421

JANUARY 2017	B. CLEMENT
B. CLEMENT	checked J. HESEMANN



**Cimmaron Environmental Response Trust**  
BA1 INJECTION AND EXTRACTION  
TRENCH DETAILS

96785	contract
	rev.

BURNS & McDONNELL ENGINEERING COMPANY, INC.



**APPENDIX H - BEST MANAGEMENT PRACTICE DETAILS**



## SEDIMENT FENCE



1. EXCAVATE A 6"x4" TRENCH.

2. SET THE STAKES ALONG THE DOWN SLOPE SIDE OF THE TRENCH.




3. STAPLE GEOTEXTILE MATERIAL TO STAKES AND EXTEND IT INTO AND AROUND THE BOTTOM OF THE TRENCH.

4. BACKFILL AND COMPACT THE EXCAVATED SOIL OVER THE GEOTEXTILE IN THE TRENCH.



**SHEET FLOW INSTALLATION  
(PERSPECTIVE VIEW)**  
NOT TO SCALE



**DRAINAGEWAY INSTALLATION  
(FRONT ELEVATION)**  
NOT TO SCALE

## SEDIMENT FENCE NOTES:

### A) INSTALLATION:

1. THE HEIGHT OF SEDIMENT FENCE SHALL BE A MINIMUM OF 16 INCHES ABOVE THE ORIGINAL GROUND SURFACE AND SHALL NOT EXCEED 34 INCHES ABOVE THE GROUND SURFACE.
2. THE FABRIC SHALL BE PURCHASED IN A CONTINUOUS ROLL CUT TO THE LENGTH OF THE BARRIER TO AVOID THE USE OF JOINTS. WHEN JOINTS ARE UNAVOIDABLE, FILTER CLOTH SHALL BE SECURELY SPLICED TOGETHER ONLY AT SUPPORT POSTS, WITH A MAX 6-INCH OVERLAP.
3. DIG A TRENCH AT LEAST 6 INCHES DEEP AND 4 INCHES WIDE ALONG THE FENCE ALIGNMENT.
4. DRIVE POSTS AT LEAST 24 INCHES INTO THE GROUND ON THE DOWNSLOPE SIDE OF THE TRENCH. SPACE POSTS A MAXIMUM OF 6 FEET APART.
5. EXTRA-STRENGTH SEDIMENT FENCE FABRIC SHALL BE USED. POSTS FOR THIS TYPE OF FABRIC SHALL BE PLACED A MAXIMUM OF 6 FEET APART. THE SEDIMENT FABRIC SHALL BE FASTENED SECURELY TO THE UPSLOPE SIDE OF THE POSTS USING A MINIMUM OF ONE INCH LONG, HEAVY-DUTY WIRE STAPLES OR TIE-WIRES, AND EIGHT INCHES OF THE FABRIC SHALL BE EXTENDED INTO THE TRENCH. THE FABRIC SHALL NOT BE STAPLED TO EXISTING TREES.
6. PLACE THE BOTTOM 1 FOOT OF FABRIC IN THE MINIMUM-OF-6-INCH DEEP TRENCH, LAPPING TOWARD THE UPSLOPE SIDE. BACKFILL WITH COMPACTED EARTH OR GRAVEL.
7. IF A SEDIMENT FENCE IS TO BE CONSTRUCTED ACROSS A DITCH LINE OR SWALE, IT MUST BE OF SUFFICIENT LENGTH TO ELIMINATE ENDFLOW, AND THE PLAN CONFIGURATION SHALL RESEMBLE AN ARC OR HORSESHOE, PLACED ON A CONTOUR, WITH THE ENDS ORIENTED UPSLOPE. EXTRA-STRENGTH SEDIMENT FABRIC SHALL BE USED WITH A MAXIMUM 3-FOOT SPACING OF POSTS.
8. TO REDUCE MAINTENANCE, EXCAVATE A SHALLOW SEDIMENT STORAGE AREA IN THE UPSLOPE SIDE OF THE FENCE. PROVIDE GOOD ACCESS IN AREAS OF HEAVY SEDIMENTATION FOR CLEAN OUT AND MAINTENANCE.
9. SEDIMENT FENCES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREA HAS BEEN PERMANENTLY STABILIZED.

### B) TROUBLESHOOTING:

1. DETERMINE THE EXACT LOCATION OF UNDERGROUND UTILITIES, BEFORE FENCE INSTALLATION SO UTILITIES ARE NOT DISTURBED.
2. GRADE ALIGNMENT OF FENCE AS NEEDED TO PROVIDE A BROAD, NEARLY LEVEL AREA UPSTREAM OF FENCE TO ALLOW SEDIMENT COLLECTION AREA.

### C) INSPECTION MAINTENANCE:

1. INSPECT SEDIMENT FENCES AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL. MAKE ANY REQUIRED REPAIRS IMMEDIATELY.
2. SHOULD THE FABRIC OF A SEDIMENT FENCE COLLAPSE, TEAR, DECOMPOSE, OR BECOME INEFFECTIVE, REPLACE IT PROMPTLY.
3. REMOVE SEDIMENT DEPOSITS AS NECESSARY TO PROVIDE ADEQUATE STORAGE VOLUME FOR THE NEXT RAIN AND TO REDUCE PRESSURE ON THE FENCE. AVOID DAMAGING OR UNDERMINING THE FENCE DURING CLEANOUT. SEDIMENT ACCUMULATION SHOULD NOT EXCEED 1/2 THE HEIGHT OF THE FENCE.
4. REMOVE ALL FENCING MATERIALS AND UNSTABLE SEDIMENT DEPOSITS, AND BRING THE AREA TO GRADE AND STABILIZE IT AFTER THE CONTRIBUTING DRAINAGE AREA HAS BEEN PROPERLY AND COMPLETELY STABILIZED.

AMERICAN PUBLIC WORKS ASSOCIATION

**APWA**



KANSAS CITY  
METROPOLITAN CHAPTER

SEDIMENT FENCE

STANDARD DRAWING  
NUMBER ESC-10  
ADOPTED:



**SEDIMENT FENCE INSTALLATION  
SLICING METHOD**




**NOTE**

VIBRATORY PLOW IS NOT ACCEPTABLE BECAUSE OF HORIZONTAL COMPACTION.

**SEDIMENT FENCE INSTALLATION SLICING METHOD NOTES:**

1. LIMIT PONDING HEIGHT TO 24"
2. ATTACH FABRIC TO UPSTREAM SIDE OF POST.
3. DRIVE OVER EACH SIDE OF SEDIMENT FENCE 2 TO 4 TIMES WITH DEVICE EXERTING 60 PSI OR GREATER AFTER MATERIAL IS SLICED INTO THE GROUND.
4. SPACE POSTS A MAX OF 7' ON OPEN RUNS AND 4' ON POOLING AREAS.
5. SINK POSTS AS FAR BELOW GROUND AS FABRIC ABOVE GROUND.




I:\KCM\APWA\27787\CIVIL\details\draft 4-22-03\division III\ESC-11.dwg 04-23-2003 08:50 JRA

SOURCE: TOM CARPENTER, 2000


<b>AMERICAN PUBLIC WORKS ASSOCIATION</b>	
<b>APWA</b>	KANSAS CITY METROPOLITAN CHAPTER
SEDIMENT FENCE INSTALLATION SLICING METHOD	STANDARD DRAWING NUMBER ESC-11 ADOPTED:

## SUPER SEDIMENT FENCE


1. EXCAVATE A 6"X4" TRENCH




2. SET THE METAL T-POSTS OR FENCE POSTS ON THE DOWNSLOPE SIDE OF THE TRENCH. SECURE WIRE FENCING TO THE POSTS.



3. ATTACH THE GEOTEXTILE FABRIC TO THE WIRE FENCE AND EXTEND IT INTO AND AROUND THE BOTTOM OF THE TRENCH.




4. BACKFILL AND COMPACT THE EXCAVATED SOIL.



### EXTENSION OF FABRIC AND WIRE INTO THE TRENCH

NOT TO SCALE



### SECTIONAL FENCE ANCHOR DETAIL

## SUPER SEDIMENT FENCE NOTES:

### A) CONSTRUCTION SPECIFICATIONS:

- FENCING SHALL BE 42-INCHES IN HEIGHT.
- WIRE FENCE SHALL BE FASTENED SECURELY TO THE FENCE POSTS WITH WIRE TIES AND STAPLES. THE LOWER TENSION WIRE, BRACE AND TRUSS RODS, DRIVE ANCHORS, AND POST CAPS ARE NOT REQUIRED EXCEPT ON THE ENDS OF THE FENCE.
- SEDIMENT FENCE SHALL BE FASTENED SECURELY TO THE WIRE FENCE WITH TIES SPACED EVERY 24 INCHES AT THE TOP AND MID-SECTION.
- SEDIMENT FENCE AND WIRE SHALL BE EMBEDDED A MINIMUM OF 8-INCHES INTO THE GROUND.
- WHEN TWO SECTIONS OF GEOTEXTILE FABRIC ADJOIN EACH OTHER, THEY SHALL BE OVERLAPPED BY 6-INCHES AND FOLDED.
- WIRE FENCE WILL BE BETWEEN 9 AND 14 GAUGE AND SHALL HAVE A MAXIMUM MESH SPACING OF 6-INCHES.
- SEDIMENT FENCE SHALL MEET THE FOLLOWING REQUIREMENTS FOR GEOTEXTILE CLASS F: ADDITIONAL SPECIFICATIONS ARE FOUND IN ASTM 6461.

#### SEDIMENT FENCE REQUIREMENTS

TENSION STRENGTH	50 LB/IN OR MORE	ASTM 4632
TENSION MODULUS	20 LB/IN OR MORE	ASTM 4632
FLOW RATE	0.3 GAL/FT <sup>2</sup> /MINUTE OR LESS	ASTM 5141
FILTERING EFFICIENCY	75 % OR MORE	ASTM 5141

### B) INSTALLATION:

- THE HEIGHT OF A SEDIMENT FENCE SHALL BE A MINIMUM OF 16 INCHES ABOVE THE ORIGINAL GROUND SURFACE AND SHALL NOT EXCEED 34-INCHES ABOVE GROUND SURFACE.
- THE FILTER FABRIC SHALL BE PURCHASED IN A CONTINUOUS ROLL AND CUT TO THE LENGTH OF THE BARRIER TO AVOID THE USE OF JOINTS. WHEN JOINTS ARE UNAVOIDABLE, FILTER CLOTH SHALL BE SPLICED TOGETHER ONLY AT A SUPPORT POST, WITH A MINIMUM 6-INCH OVERLAP, AND SECURELY SEALED.
- A TRENCH SHALL BE EXCAVATED APPROXIMATELY 4 INCHES WIDE AND 6 INCHES DEEP ON THE UPSLOPE SIDE OF THE PROPOSED LOCATION OF THE FENCE.
- WHEN WIRE SUPPORT IS USED, STANDARD-STRENGTH FILTER CLOTH MAY BE USED. POSTS FOR THIS TYPE OF INSTALLATION SHALL BE PLACED A MAXIMUM OF 10 FEET APART. THE WIRE MESH FENCE MUST BE FASTENED SECURELY TO THE UPSLOPE SIDE OF THE POSTS USING HEAVY DUTY WIRE STAPLES AT LEAST 1 INCH LONG, TIE WIRES, OR HOG RINGS. THE WIRE SHALL EXTEND INTO THE TRENCH A MINIMUM OF 2 INCHES AND SHALL NOT EXTEND MORE THAN 34 INCHES ABOVE THE ORIGINAL GROUND SURFACE. THE STANDARD-STRENGTH FABRIC SHALL BE STAPLED OR WIRED TO THE FENCE, AND 8 INCHES OF THE FABRIC SHALL BE EXTENDED INTO THE TRENCH. THE FABRIC SHALL NOT BE STAPLED TO EXISTING TREES.
- IF A SEDIMENT FENCE IS TO BE CONSTRUCTED ACROSS A DITCH LINE OR SWALE, IT MUST BE OF SUFFICIENT LENGTH TO ELIMINATE ENDFLOW, AND THE PLAN CONFIGURATION SHALL RESEMBLE AN ARC OR HORSESHOE WITH THE ENDS ORIENTED UPSLOPE. EXTRA-STRENGTH FILTER FABRIC SHALL BE USED FOR THIS APPLICATION WITH A MAXIMUM 3-FOOT SPACING OF POSTS.
- THE 4 INCH BY 6 INCH TRENCH SHALL BE BACKFIELD AND THE SOIL COMPACTED OVER THE FILTER FABRIC.
- SEDIMENT FENCES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREA HAS BEEN PERMANENTLY STABILIZED. SEDIMENT ACCUMULATION SHOULD NOT EXCEED 1/2 THE HEIGHT OF THE FENCE.

### C) INSPECTION AND MAINTENANCE:

- INSPECT SEDIMENT FENCES AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL. MAKE ANY REQUIRED REPAIRS IMMEDIATELY.
- SHOULD THE FABRIC OF A SEDIMENT FENCE COLLAPSE, TEAR, DECOMPOSE, OR BECOME INEFFECTIVE, REPLACE IT PROMPTLY.
- MAINTENANCE SHALL BE PERFORMED AS NEEDED AND SEDIMENT BUILD-UPS REMOVED WHEN BULGES DEVELOP IN THE SEDIMENT FENCE OR WHEN SEDIMENT REACHES 50% OF THE FENCE HEIGHT. AVOID DAMAGING OR UNDERMINING THE FENCE DURING CLEANOUT.
- REMOVE ALL FENCING MATERIALS AND UNSTABLE SEDIMENT DEPOSITS, AND BRING THE AREA TO GRADE AND STABILIZE IT AFTER THE CONTRIBUTING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

AMERICAN PUBLIC WORKS ASSOCIATION

**APWA**

KANSAS CITY  
METROPOLITAN CHAPTER

SUPER SEDIMENT FENCE

STANDARD DRAWING  
NUMBER ESC-12  
ADOPTED:

## SECTION 32 91 00 - RIGHT-OF-WAY RESTORATION

### PART 1 - GENERAL

1.01 SUMMARY: This Section covers restoration of the right-of-way (ROW) associated with the T-Line Contractor, including site preparation, top soiling, mulching and seeding, for all disturbed areas except cropland fields. Cropland fields will be re-established to the desired crop rotation by the landowner following construction.

1.02 REFERENCES:

A. Applicable Standards:

1. AASHTO M140 Standard Specification for Emulsified Asphalt - American Association of State Highway and Transportation Officials Standard Method of Test.

1.03 SUBMITTALS:

A. Submit as specified in DIVISION 01.

B. Compliance Submittals:

1. Include, but not limited to, the following:
  - a. Certification from vendor that seed meets requirements of these specifications.
  - b. Seed mix showing purity and germination of each seed type and total pounds of seed required per acre.
  - c. T-Line Contractor is responsible for determining the choice of mulch most suitable for the Project area. Documentation is to be submitted to the Owner's Agent for approval. Reference Part 2.02 paragraph A of this section for more information.
  - d. Documentation from the manufacturer regarding appropriate methods for determining use/effectiveness, installation, and maintenance for all Best Management Practices (BMP's) to be installed throughout construction.

### PART 2 - PRODUCTS

2.01 SEED:

- A. Seed shall be fresh, clean, new crop seed.
- B. Seed mix will be provided in PART 3 - SEEDING.
- C. Seed shall conform to all applicable laws of the State of Oklahoma.
- D. Seed shall be labeled according to the U.S. Department of Agriculture Federal Seed Act and shall be furnished in containers with tags showing seed mixture, purity, germination, weed content, name of seller, and date on which seed was tested.
- E. Wet, moldy, or seed that has been damaged in storage shall not be used.

2.02 MULCH: May be vegetative mulch or wood cellulose fiber.

- A. Check with the local Agriculture County Extension Service office to determine choice of mulch most suitable for the Project area. Specify only one type of mulch that shall be free from noxious weed seed, mold, and other deleterious materials. Chosen mulch shall be submitted to Owner's Agent for approval.
- B. Asphalt Emulsion: Conform to AASHTO M140, Type SS-1.

SECTION 32 91 00 - RIGHT-OF-WAY RESTORATION: continued

- C. Wood-Cellulose Fiber:
  - 1. Mulch shall not contain germination or growth-inhibiting ingredients.
  - 2. Mulch shall be dyed an appropriate color to aid in visual inspection.
  - 3. Mulch material shall be easily and evenly dispersed when agitated in water.
  - 4. Supply in packages of not more than 100 pounds gross weight, and be marked by the manufacturer to show the air dry weight content.
- D. Mulch: Furnish in air-dry condition and of proper consistency for placing with commercial mulch blowing equipment. Mulch shall contain no fertile seed.
- E. This does not include any mulch produced onsite from vegetation within the ROW.

2.03 JUTE NETTING:

- A. Jute netting or other equal approved by the Owner's Agent shall consist of a uniform, open, plain-weave mesh of smolder-resistant, unbleached single jute yarn.
  - 1. Yarn shall be of loosely twisted construction and shall not vary in thickness by more than one-half its normal diameter.
  - 2. Jute mesh shall be furnished in rolled strips and shall be as follows:
    - a. Minimum width of 42 inches.
    - b. 5.5 wrap yarns by 3.5 filling yarns per inch.
  - 3. Staples shall be of No. 11 gauge, or heavier, steel wire, "U" shaped and not less than 6 inches in length.
  - 4. Additional staples may be required depending on the existing soil and or weather conditions.

PART 3 - EXECUTION

- 3.01 RIGHT-OF-WAY RESTORATION: Following line construction activities, remove construction roads and restore right-of-way as follows:
- A. All ruts in existing roads shall be filled and compacted in 6-inch lifts and the roads graded to approximately the original contours.
  - B. Construction roads and ruts in agricultural land shall be plowed and disced to remove any hard compacted areas and shall be graded to the original contours.
  - C. All disturbed areas shall be finish graded to the original ground contours. Dockets, swales, and high points shall be graded, using hand methods where necessary, to provide an unconcentrated flow of runoff around foundations and through structures.
  - D. Annual Ryegrass shall not be used in or around wheat fields.
  - E. T-Line Contractor shall provide Owner's Agent with two days notice of planned seeding, mulching, and fertilizing so Owner/Owner's Agent may view the process, if he/she chooses to do so.
  - F. Topsoil:
    - 1. Distribute over required areas without compaction other than that obtained with spreading equipment.
    - 2. Place to the extent material is available within the following limits:
      - a. Not less than 4 inches in depth.



SECTION 32 91 00 - RIGHT-OF-WAY RESTORATION: continued

- b. Do not exceed 6 inches in depth.
- G. Shape and grade to match contours of adjacent areas and permit good natural drainage.
- H. Maintenance and Repair:
  - 1. Maintenance: T-Line Contractor is responsible for protecting newly topsoiled areas from actions of the elements.
  - 2. Correction of Settlement: T-Line Contractor is responsible for correcting settlement in excess of 18 inches and damages created thereby within one year after acceptance of the Work.
  - 3. T-Line Contractor is responsible for making repairs within ten days from and after due notification by Owner of embankment or backfill settlement and resulting damage.
  - 4. T-Line Contractor is responsible for making own arrangements for access to the site for purposes of repair.

3.02 SEEDING AND SPRIGGING:

- A. Seedbed Preparation:
  - 1. Where practical, remove any rocks or other obstructions which might interfere with tilling, seeding, and sprigging operations.
  - 2. In areas where ground surface is compacted hard enough to prevent drill penetration, thoroughly loosen and pulverize topsoil to a depth of at least 3 inches.
  - 3. Maintain tilled areas until seeded or sprigged.
- B. Seeding:
  - 1. The rate of application shall be in accordance with Table 1.

SECTION 32 91 00 - RIGHT-OF-WAY RESTORATION: continued

TABLE 1

PLANTING ZONES																		
Number/Pounds per Acre (Ac)																		
Plant Species	Adapted Varieties	Size	Type 1	Type 2	Type 3	Type 4												
Big Bluestem (Andropogon gerardii)	Kaw or Comparable	PLS	6	6	--	--												
Little Bluestem (Schizachyrium scoparium)	Aldous, Cimarron (only in SW), or Comparable	PLS	5	5	--	--												
Indiangrass (Sorghastrum nutans)	Cheyenne, Lometa, or Comparable	PLS	6	6	--	--												
Switchgrass (Panicum virgatum)	Blackwell, Caddo, Alamo, Kanlow, or Comparable	PLS	5	5	--	--												
Sideoats Grama (Bouteloua curtipendula)	El Reno, Haskell, or Comparable	PLS	5	5	--	--												
Sand Lovegrass (Eragrostis trichodes)	Bend, Mason, or Comparable	PLS	2	--	--	--												
Costal Bermudagrass (Cynodon dactylon)	--	Bushels of sprigs/acre	--	--	30	--												
Tall Fescue (Festuca arundinacea)	(Only in SE)	PLS	--	--	20	--												
Wheat Grass (Bromus inermis)	Western or comparable	PLS	--	--	112	--												
Alfalfa (Medicago spp.)	--	PLS	--	--	10-20	--												
Red Clover <sup>1</sup> (Trifolium pretense L.)	All	PLS	--	--	5													
Wheat (Triticum spp.)	--	Bulk	--	--	--	100												
Annual Ryegrass <sup>2</sup> (Lolium multiflorum)	--	Bulk	--	--	--	100												
<p>Notes:</p> <p>Do not use non-regionally specific cultivar (i.e. something such as Cave-In-Rock)</p> <p>Switchgrass developed in Illinois is not to be used.</p> <p>All seed mixes shall be approved by the Owner's Agent or on-site environmental inspector.</p> <p><sup>1</sup>Inoculate legume seed.</p> <p><sup>2</sup>Annual Ryegrass shall not be used in or around wheat fields.</p> <table style="width: 100%; border: none;"> <tr> <td style="width: 33%;">Type 1</td> <td style="width: 33%;">Grassland Sandy</td> <td style="width: 33%;">Use Mixture</td> </tr> <tr> <td>Type 2</td> <td>Grassland Upland</td> <td>Use Mixture</td> </tr> <tr> <td>Type 3</td> <td>Hay Land/Pasture Land</td> <td>Use one species</td> </tr> <tr> <td>Type 4</td> <td>Temporary Cover</td> <td>Use one species</td> </tr> </table>							Type 1	Grassland Sandy	Use Mixture	Type 2	Grassland Upland	Use Mixture	Type 3	Hay Land/Pasture Land	Use one species	Type 4	Temporary Cover	Use one species
Type 1	Grassland Sandy	Use Mixture																
Type 2	Grassland Upland	Use Mixture																
Type 3	Hay Land/Pasture Land	Use one species																
Type 4	Temporary Cover	Use one species																

SECTION 32 91 00 - RIGHT-OF-WAY RESTORATION: continued

1. The Pure Live Seed Index (PLS) shall be determined by the following formula:

$$\text{PLS} = \frac{\% \text{ Germination} \times \% \text{ Purity}}{100}$$

2. Methods of Application:
  - a. Dry Seeding: Accomplish sowing by use of a rangeland drill, having drills no more than 4 inches apart.
    - (1) Drill seed to a depth of 1/2-inch to 1 inch.
    - (2) Overlap successive seed strips to provide uniform coverage.
  - b. In areas that cannot be drilled, broadcast seed at double the application rate for drilling and harrow into the soil.
  - c. Sprigging of bermudagrass will be done with traditional sprigging equipment into a tilled seed bed.
- C. Seeding shall be performed at all disturbed areas, on Dry Ditch Crossings and on all other areas as appropriate.
- D. Temporary Seeding:
  1. Construction Requirements – This work shall consist of preparing a seedbed and sowing a temporary cover crop during the construction process. Seeding shall be monitored until a uniform vegetative cover can be established on a continuous basis on all cut and fill slopes, waste sites and borrow pits during construction.
  2. Bulk seeding rates shall be adjusted upward so that seeding is accomplished in quantities linked with the PLS.
  3. Seeding Rate:
    - a. Mar 1 – Dec 1 100 lbs/acre cereal rye or wheat.
  4. Maintenance – The cover crop shall be maintained until permanent vegetation is installed.
  5. Seasonal Limitations - Perform Grassland seeding from December 1 to June 1 (the optimal seeding period being March 1 through May 15) unless otherwise authorized, in writing, by the Project Engineer. Perform Hay Land and Pasture Land seeding September 1 through October 31, Bermuda grass February 1 through June 15, unless otherwise authorized in writing, by the Project Engineer.

3.03 MULCHING:

- A. Apply mulch to all seeded areas. On slopes exceeding 15 percent, apply with an asphalt emulsion.
- B. Apply to seeded areas within 48 hours after seeding.
- C. Apply vegetative mulch at the rate of 2-1/2 tons per acre by means of a mechanical spreader or other approved methods.
- D. Apply wood cellulose - fiber mulch hydraulically at the rate of 1,000 gallons per acre.
- E. Vegetative mulch with asphalt emulsion:
  1. Apply vegetative mulch at the rate of 2-1/2 tons per acre.
  2. Apply asphalt emulsion at the rate of 100 gallons per ton of straw (250 gallons per acre).



SECTION 32 91 00 - RIGHT-OF-WAY RESTORATION: continued

3. Mulching machine shall inject emulsified asphalt at the proper rate directly into the air stream carrying the straw.


3.04 JUTE NETTING:

- A. Where other restorative measures do not result in stable slopes, further stabilize those slopes by means of jute netting, or other approved method.
- B. Install jute netting in accordance with manufacturer's recommendations.

END OF SECTION 32 91 00

## EROSION CONTROL BLANKET

SHALLOW  
SLOPE




**NOTE:**


ON SHALLOW SLOPES, PROTECTIVE EROSION CONTROL BLANKETS MAY BE APPLIED ACROSS THE SLOPE.

**NOTE:**

WHERE THERE IS A BERM AT THE TOP OF THE SLOPE, BRING THE MATERIAL OVER THE BERM AND ANCHOR IT BEHIND THE BERM.




STEEP  
SLOPE



**NOTE:**

ON STEEP SLOPES, APPLY PROTECTIVE BLANKET PERPENDICULAR TO THE DIRECTION OF FLOW AND ANCHOR SECURELY.

### TOP OF SLOPE BLANKET ANCHOR SLOT




**NOTE:**

BRING MATERIAL DOWN TO A LEVEL AREA BEFORE TERMINATING THE INSTALLATION.

DITCH

FLOW



**NOTE:**

IN DITCHES, APPLY PROTECTIVE COVERING PARALLEL TO THE DIRECTION OF FLOW. USE CHECK SLOTS AS REQUIRED. AVOID JOINING MATERIAL IN THE CENTER OF THE DITCH IF AT ALL POSSIBLE. FOLLOW BLANKET MANUFACTURER'S RECOMMENDATIONS FOR ALLOWABLE VELOCITY AND SHEAR STRESS.

## EROSION CONTROL BLANKET NOTES (1 OF 2):

### A) SITE PREPARATION:

AFTER SITE HAS BEEN SHAPED AND GRADED, PREPARE A FRIABLE SEEDBED RELATIVELY FREE FROM CLODS AND ROCKS MORE THAN 1 1/2 INCHES IN DIAMETER AND ANY FOREIGN MATERIAL THAT WILL PREVENT UNIFORM CONTACT OF THE PROTECTIVE COVERING WITH THE SOIL SURFACE.

### B) PLANTING:

LIME, FERTILIZE, AND SEED IN ACCORDANCE WITH SEEDING OR PLANTING PLAN. WHEN USING JUTE MESH ON A SEEDED AREA, APPLY APPROXIMATELY ONE HALF THE SEED AFTER LAYING THE MAT. THE PROTECTIVE COVERING CAN BE LAID OVER SPRIGGED AREAS WHERE SMALL GRASS PLANTS HAVE BEEN INSERTED INTO THE SOIL. WHERE GROUND COVERS ARE TO BE PLANTED, LAY THE PROTECTIVE COVERING FIRST AND THEN PLANT THROUGH THE MATERIAL AS PER PLANTING PLAN.

### C) LAYING AND STAPLING:

IF INSTRUCTIONS HAVE BEEN FOLLOWED, ALL NEEDED CHECK SLOTS WILL HAVE BEEN INSTALLED, AND THE PROTECTIVE COVERING WILL BE LAID ON A FRIABLE SEEDBED FREE FROM CLODS, ROCKS, ROOTS, ETC. THAT MIGHT IMPEDE GOOD CONTACT.

1. START LAYING THE PROTECTIVE COVERING FROM THE TOP OF THE CHANNEL OR SLOPE AND UNROLL DOWN-GRADE. ALLOW TO LAY LOOSELY ON SOIL; DO NOT STRETCH.
2. UPSLOPE ENDS OF THE BLANKET SHOULD BE BURIED IN AN ANCHOR SLOT NO LESS THAN 6-INCHES DEEP. TAMP EARTH FIRMLY OVER THE MATERIAL. WHEN TOP IS RELATIVELY FLAT, EXTEND BLANKET ABOUT 40 INCHES AWAY FROM SLOPE. STAPLE THE MATERIAL AT A MINIMUM OF EVERY 12 INCHES ACROSS THE TOP END.
3. EDGES OF THE MATERIAL SHALL BE STAPLED EVERY 3 FEET. WHERE MULTIPLE WIDTHS ARE LAID SIDE BY SIDE, THE ADJACENT EDGES SHALL BE OVERLAPPED A MINIMUM OF 6 INCHES AND STAPLED TOGETHER.
4. STAPLES SHALL BE PLACED DOWN THE CENTER, STAGGERED WITH THE EDGES AT 3-FOOT INTERVALS.

### D) TROUBLESHOOTING:

CONSULT WITH A QUALIFIED DESIGN PROFESSIONAL, IF ANY OF THE FOLLOWING OCCUR:

1. MOVEMENT OF THE BLANKET OR EROSION UNDER THE BLANKET IS OBSERVED.
2. VARIATIONS IN TOPOGRAPHY ON SITE INDICATE EROSION CONTROL MAT WILL NOT FUNCTION AS INTENDED; CHANGES IN PLAN MAY BE NEEDED, OR A BLANKET WITH A SHORTER OR LONGER LIFE MAY BE NEEDED.
3. DESIGN SPECIFICATIONS FOR SEED VARIETY, SEEDING DATES, OR EROSION CONTROL MATERIALS CANNOT BE MET; SUBSTITUTION MAY BE REQUIRED. UNAPPROVED SUBSTITUTIONS COULD RESULT IN FAILURE TO ESTABLISH VEGETATION.

### E) MAINTENANCE & INSPECTION

INSPECT CONTROLS AFTER EACH RAIN EVENT OF 1/2 INCH OR GREATER, AND EVERY 7 DAYS UNTIL VEGETATION IS ESTABLISHED, FOR EROSION OR UNDERMINING BENEATH THE NETTING, BLANKETS, OR MATS. IF ANY AREA SHOWS EROSION, PULL BACK THAT PORTION OF THE MATERIAL, ADD SOIL, TAMP DOWN, AND RESEED; RESECURE THE MATERIAL IN PLACE. IF NETTING, BLANKETS OR MATS BECOME DISLOCATED OR DAMAGED, REPAIR OR REPLACE AND RESECURE IMMEDIATELY.

**AMERICAN PUBLIC WORKS ASSOCIATION**



KANSAS CITY  
METROPOLITAN CHAPTER

EROSION CONTROL BLANKET  
SHEET 1 OF 2

STANDARD DRAWING  
NUMBER ESC-04  
ADOPTED:

**APPENDIX I - INSPECTION AND MAINTENANCE REPORT FORMS**



# Site Inspection Report

Inspection Date: \_\_\_\_\_

General Information (OKR10 Part 4.3.13.E)	
Name of Project: <b>Groundwater Remediation Project</b>	DEQ Permit No.: <b>1027644</b>
Inspector Name:	Inspector Title:
Inspector's Contact Information:	
Inspection Frequency:	
Standard Frequency: <input type="checkbox"/> Every 7 days and within 24 hours of a 0.50" rain, or discharge from snowmelt <input type="checkbox"/> Every 14 days and within 24 hours of a 0.50" rain, or discharge from snowmelt Reduced Frequency: <input type="checkbox"/> Once per month (for stabilized areas)	
Weather at the time of this inspection: _____	
Was this inspection after a 0.50" storm event? <input type="checkbox"/> Yes <input type="checkbox"/> No, Total rainfall that triggered the inspection (in inches):	
Are there any discharges at the time of inspection? <input type="checkbox"/> Yes <input type="checkbox"/> No	

List all areas where soil stabilization is required to begin because construction work in that area has permanently or temporarily stopped and all areas where stabilization has been implemented:

Stabilization of Exposed Soil (OKR10 Part 4.3.13.D)			
Stabilization Area	Stabilization Method	Have You Initiated Stabilization?	Notes (describe your observation)
		<input type="checkbox"/> Yes <input type="checkbox"/> No If yes, provide date:	
		<input type="checkbox"/> Yes <input type="checkbox"/> No If yes, provide date:	
		<input type="checkbox"/> Yes <input type="checkbox"/> No If yes, provide date:	
		<input type="checkbox"/> Yes <input type="checkbox"/> No If yes, provide date:	
		<input type="checkbox"/> Yes <input type="checkbox"/> No If yes, provide date:	

*(Notes: For each area where stabilization has been initiated, describe the progress that has been made, and what additional actions are necessary to complete stabilization. Note the effectiveness of stabilization in preventing erosion. If stabilization has been initiated but not completed, make a note of the date it is to be completed. If stabilization has been completed, make a note of the date it was completed. If stabilization has not yet been initiated, make a note of the date it is to be initiated, and the date it is to be completed.)*

Provide a list/description of all structural and non-structural BMPs that your SWP3 indicates will be installed and implemented at your site. You must separately identify the **location** of each control. During Inspection, identify whether they are **installed and operating properly**, or any **corrective action** is necessary. Provide the **date** on which the condition that triggered the need for maintenance or corrective action was first identified. In the notes section you must describe the **specifics about the problem** you observed.

**Condition and Effectiveness of BMP Controls & Pollution Prevention (OKR10 Part 3.3, 4 & 5)**

No.	BMP Description & Location	Is BMP Installed & Operating Properly?	Corrective Action (CA) Required?	Date on Which Maintenance or CA First Identified?	Notes (describe if you observed any problem)
1.	Silt Fence/Fiber Rolls/Berm/Wattles Location:	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
2.	Silt Dikes/Check Dams/Rock Dams Location:	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
3.	Stabilized Construction Entrance/Exit Location:	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
4.	Inlet Protection on all storm drain Location:	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
5.	Sand Bag Barrier/Gravel Bag Barrier Location:	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
6.	Vegetated Swales Location:	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
7.	Compost Blankets/Geotextiles/Mats Location:	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
8.	Vegetative Buffers Location:	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
9.	Sediment Trap/ Sediment Basin Location:	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
10.	Concrete Washout Pit Location:	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
11.	Dust Control/Prevention	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
12.		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
13.		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
14.		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
15.		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		
16.		<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No		

**(Note:** *The permit differentiates between conditions requiring repairs and maintenance, and those requiring corrective action. The permit requires maintenance in order to keep controls in effective operating condition and requires repairs if controls are not operating as intended. Corrective actions are triggered only for specific, more serious conditions – whether a required stormwater control was never installed, or was installed incorrectly, or not installed in accordance with the requirements of OKR10)*



Pollution Prevention and Waste Management (OKR10 Part 3.3.3)		
Items of Inspection	Response & Reason	Action(s) Needed
Is the site free of floatables, litter, and construction debris?	<input type="checkbox"/> Yes <input type="checkbox"/> No If no, reason:	
Are material storage and handling areas, including fueling areas, free of spills and leaks?	<input type="checkbox"/> Yes <input type="checkbox"/> No If no, reason:	
Are spill kits available where spills and leaks are likely to occur?	<input type="checkbox"/> Yes <input type="checkbox"/> No If no, reason:	
Are dumpsters and waste receptacles covered when not in use?	<input type="checkbox"/> Yes <input type="checkbox"/> No If no, reason:	
Has preventative maintenance been conducted on equipment and machinery?	<input type="checkbox"/> Yes <input type="checkbox"/> No If no, reason:	
Are material stockpiles sufficiently contained?	<input type="checkbox"/> Yes <input type="checkbox"/> No If no, reason:	
Has there been any sediment tracked-out from the site onto the surface of paved street, sidewalks or other paved areas outside of the site?	<input type="checkbox"/> Yes <input type="checkbox"/> No If no, reason:	
Is the project free from visible erosion and/or sedimentation?	<input type="checkbox"/> Yes <input type="checkbox"/> No If no, reason:	

Complete the following section if a discharge is occurring at the time of inspection:

Description of Discharges (OKR10 Part 4.3.13.D.2.f)	
Was a stormwater discharge or other discharge occurring from any part of your site at the time of the inspection? <input type="checkbox"/> Yes <input type="checkbox"/> No, If yes, provide the following information for each point of discharge:	
Specify Discharge Location	Observations (Visual Quality of the Discharge)
1.	Describe the discharge (color, odor, floating, settled/suspended solids, foam, & oil sheen): Are there any visible signs of erosion and/or sediment accumulation that can be attributed to your discharge? <input type="checkbox"/> Yes <input type="checkbox"/> No, If yes, describe what you see, specify the location(s) where these conditions were found, and indicate whether modification, maintenance, or corrective action is needed to resolve the issue:
2.	Describe the discharge (color, odor, floating, settled/suspended solids, foam, & oil sheen): Are there any visible signs of erosion and/or sediment accumulation that can be attributed to your discharge? <input type="checkbox"/> Yes <input type="checkbox"/> No, If yes, describe what you see, specify the location(s) where these conditions were found, and indicate whether modification, maintenance, or corrective action is needed to resolve the issue:

**Contractor or Subcontractor Certification and Signature:**

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Signature: \_\_\_\_\_

Date: \_\_\_\_\_

Print Name: \_\_\_\_\_

Affiliation: \_\_\_\_\_



# Corrective Action Report

Today's Date: \_\_\_\_\_

(You are only required to fill out this form if any of the corrective action triggering conditions occurs on your site. Routine maintenance and repairs are generally not considered to be a corrective action triggering condition.)

<b>Section A: Initial Report (Part 4.3.14.B.1 of OKR10)</b> (Complete this section <u>within 24 hours</u> of discovering the condition that triggered corrective action)	
<b>Name of Project:</b> <b>Groundwater Remediation Project</b>	<b>DEQ's Permit No.</b> OKR1027644
<b>Date Problem First Discovered:</b>	<b>Time Problem First Discovered:</b>
<b>Name &amp; Contact Information of the Individual:</b>	
<b>What site conditions triggered the requirement to conduct corrective action</b> ( <i>check the box that applies</i> ): <input type="checkbox"/> A required stormwater control was never installed or was installed incorrectly, or not in accordance with the corresponding OKR10 permit requirement <input type="checkbox"/> A stormwater control is not effective enough for the discharge to meet applicable water quality standards <input type="checkbox"/> A prohibited discharge (OKR10 Parts 3.1 and 3.3.3.A) is occurring or has occurred. <input type="checkbox"/> DEQ requires corrective action as a result of permit violations found during an DEQ inspection	
<b>Provide a description of the problem:</b>	
<b>Deadline for completing corrective action:</b>	<i>not more than 7 calendar days after the date you discovered the problem</i>

<b>Section B: Corrective Action Progress (Part 4.3.14.B.2 of OKR10)</b> (Complete this section <u>no later than 7 calendar days</u> after discovering the condition that triggered corrective action)			
<b>Section B.1: Why the Problem Occurred</b>			
Cause(s) of Problem	How It Was Determined & Date of Determining the Cause		
1.	1.		
2.	2.		
<b>Section B.2: Stormwater Control Modifications to be Implemented to Correct the Problem</b>			
Stormwater Control Modification(s) Needed to Correct Problem	Date of Completion	SWP3 Update Necessary?	SWP3 Modifications Notes
1.		<input type="checkbox"/> Yes <input type="checkbox"/> No, If yes, provide date SWP3 modified:	
2.		<input type="checkbox"/> Yes <input type="checkbox"/> No, If yes, provide date SWP3 modified:	

## Section C: Certification and Signature by Permittee

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

**Name:** \_\_\_\_\_ **Title:** \_\_\_\_\_

**Signature:** \_\_\_\_\_ **Date:** \_\_\_\_\_

## Groundwater Remediation Project SWP3 Modification Log

<b>No.</b>	<b>Description of the Modification</b>	<b>Date of Modification</b>	<b>Modification Prepared by</b> [Name(s) and Title]	<b>Signature by Designated Corporate Official</b>
1.				
2.				
3.				
4.				
5.				
6.				
7.				
8.				
9.				

## Groundwater Remediation Project Grading and Stabilization Activities Log

<b>Date Grading Initiated</b>	<b>Description of Grading Activity</b>	<b>Description of Stabilization Measure and Location</b>	<b>Date Grading Activity Ceased</b> (Temporary or Permanent)	<b>Date When Stabilization Initiated</b>



**APPENDIX J - SPILL REPORT FORM**

## **Procedures for Determining if a Hazardous Material Spill is a Reportable Quantity**

- 1) First determine the type and quantity of material that has been spilled.
- 2) Obtain a safety data sheet (SDS) for the spilled material and determine whether any of the constituents are listed in Table 302.4 in 40 CFR 302.
- 3) If none of the constituents in the spilled material are listed in the table (excluding ethylene glycol), the spill is not reportable.
- 4) If the constituents in the spilled material are listed in the table, use the following equation to determine the pounds of material spilled:

$$\text{Pounds Spilled} = (V) (\text{Wt}\%) (\text{Sg}) (0.0834)$$

Where:

V = Volume of the material spilled, in gallons

Wt% = The weight percent of the constituents in the spilled material (see the SDS)

Sg = Specific gravity of spilled material (see SDS)

For Example:

V = 7 gallons

Wt% = 3.5

Sg = 1.04

Pounds Spilled = (7) (3.5) (1.04) (0.0834) = 2.13 pounds

- 5) If, based on the calculation, the pounds spilled are greater than the Final RQ (reportable quantity) value listed in Table 302.4 of 40 CFR 302 or the State's reportable quantity minimum amount, the spill must be reported to the appropriate Federal, State, and local agencies.

**Groundwater Remediation Project  
Storm Water Pollution Prevention Plan**

**SPILL REPORT FORM**

Spill Reported By: \_\_\_\_\_  
Name Phone Number

Date Reported: \_\_\_\_\_ Time: \_\_\_\_\_

Date of Spill: \_\_\_\_\_ Time: \_\_\_\_\_

Name of Facility: \_\_\_\_\_

Legal Description: \_\_\_\_ 1/4 \_\_\_\_ 1/4 \_\_\_\_ 1/4 SEC \_\_\_\_, TWP \_\_\_\_, Range \_\_\_\_,  
County \_\_\_\_\_

Describe Spill Location and Events Leading to Spill: \_\_\_\_\_

---

---

---

Material Spilled: \_\_\_\_\_

Source of Spill: \_\_\_\_\_

Amount Spilled (Gallons or Pounds): \_\_\_\_\_

Amount Spilled to Waterway (Gallons or Pounds): \_\_\_\_\_

Nearest Municipality: \_\_\_\_\_

Containment or Cleanup Action: \_\_\_\_\_

---

---

List Environmental Damage (fish kill, etc.): \_\_\_\_\_



List Injuries or Personal Contamination: \_\_\_\_\_

\_\_\_\_\_

Date and Time Cleanup Completed or Terminated: \_\_\_\_\_

If Cleanup Delayed, Nature and Duration of Delay: \_\_\_\_\_

\_\_\_\_\_

Description of Materials Contaminated: \_\_\_\_\_

\_\_\_\_\_

Approximate Depth of Soil Excavation: \_\_\_\_\_

Action To Be Taken to Prevent Future Spills: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Agencies Notified:

Local: \_\_\_\_\_ Date: \_\_\_\_\_

State: \_\_\_\_\_ Date: \_\_\_\_\_

Federal: \_\_\_\_\_ Date: \_\_\_\_\_

Signed: \_\_\_\_\_

Contractor Superintendent or  
Environmental Inspector



CREATE AMAZING.

Burns & McDonnell Dallas  
15950 North Dallas Parkway  
Dallas, TX 75248  
O 972-455-3100  
F 972-386-4026  
[www.burnsmcd.com](http://www.burnsmcd.com)