3.7 PLANT SYSTEMS

3.7.8 Auxiliary Saltwater (ASW) System

LCO 3.7.8 Two ASW trains shall be OPERABLE.

APPLICABILITY: MODES 1, 2, 3, and 4.

ACTIONS

CONDITION	REQUIRED ACTION	COMPLETION TIME
A. One ASW train inoperable.	A.1 ----------NOTE---------- Enter applicable Conditions and Required Actions of LCO 3.4.6, "RCS Loops - MODE 4," for residual heat removal loops made inoperable by ASW. ---------- Restore ASW train to OPERABLE status	----------NOTE---------- A Completion Time of 144 hours is applicable for ASW pump 1-1 on a one-time basis, for Unit 1 cycle 23. ---------- 72 hours
B. Required Action and associated Completion Time of Condition A not met.	B.1 Be in MODE 3. AND B.2 ----------NOTE---------- LCO 3.0.4.a is not applicable when entering MODE 4. ---------- Be in MODE 4.	6 hours 12 hours