

To: NRC (DC DESK)
Destination:

MAC: N/A
Description:

Holder #: 1242

Document:	Revision:	II	IC#	Comment:	Copy Totals		
					INF	CTL	MST
CH0632B	02				1	0	0

Instructions to the Addressee: Please verify the document(s) received agrees with the above information. Notify Document Control if changes are required to addressee information, or mark the transmittal and return as indicated below.

Engineering managers are required by NEP-121 to determine if new, revised, or temporary changes to procedures affect job functions of their personnel. Managers will communicate change information appropriately and provide documentation of any training conducted to the Engineering Training Coordinator.

Operations department must attach old document(s) or portions of document(s) superseded by the above to this transmittal.

The signature indicates acknowledgment of receipt of the above document(s) and that documents have been updated. Return signed and dated transmittal to Document Control within 15 working days of transmittal date to mail code:

291001

____ SA2A
____ Florida Power Corporation
Document Control, SA2A
Crystal River Energy Complex
15760 W. Power Line St.
Crystal River, FL 34428-6708

AO450/1

Signature of Addressee: _____ Date: _____

Effective Date 10/22/99

CHEMISTRY SAMPLING PROCEDURE
CH-632B
EMERGENCY PLAN IMPLEMENTING PROCEDURE
FLORIDA POWER CORPORATION
CRYSTAL RIVER UNIT 3
POST ACCIDENT SAMPLING AND ANALYSIS OF REACTOR COOLANT
WHEN ON THE "A" DECAY HEAT SYSTEM

APPROVED BY: Procedure Owner


(SIGNATURE ON FILE)

DATE: 10/22/99

PROCEDURE OWNER: Chemrad Specialist II

TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
<u>1.0</u> <u>PURPOSE</u>	1
<u>2.0</u> <u>REFERENCES</u>	1
2.1 <u>DEVELOPMENTAL REFERENCES</u>	1
2.3 <u>CMIS REFERENCES</u>	1
<u>3.0</u> <u>PERSONNEL INDOCTRINATION</u>	2
3.1 <u>DESCRIPTION</u>	2
3.2 <u>LIMITS & PRECAUTIONS</u>	2
<u>4.0</u> <u>INSTRUCTIONS</u>	3
4.1 <u>SAMPLE TEAM CHECKLIST</u>	3
4.2 <u>SAMPLE LINE-UP</u>	5
4.3 <u>GAMMA ISOTOPIC ANALYSIS</u>	7
4.4 <u>BORON ANALYSIS</u>	10
4.5 <u>GRAB SAMPLE COLLECTION AT CASB-5</u>	11
4.6 <u>DEMINERALIZED WATER FLUSH</u>	18
4.7 <u>SYSTEM RESTORATION</u>	21
<u>5.0</u> <u>CONTINGENCIES</u>	22
5.1 <u>CAT-8 HI-HI LEVEL ALARM</u>	22
5.2 <u>NOTIFICATIONS AND SHIPMENT</u>	23
 <u>ENCLOSURES</u>	
1 <u>TECHNICAL SUPPORT CENTER DATA SHEET</u>	25
2 <u>ASSESSMENT OF CORE DAMAGE BASED ON REACTOR COOLANT</u> <u>SAMPLE ("A" DECAY HEAT)</u>	26

1.0 PURPOSE

This procedure provides instructions for sampling the "A" Decay Heat Train under accident conditions for Gamma Isotopic and Boron analyses using the Post Accident Sampling System.

2.0 REFERENCES

2.1 DEVELOPMENTAL REFERENCES

- | 2.1.1 APEX Technologies Post Accident Sample System Modules Manual, FPC Manual #2034
- | 2.1.2 EOP-14, Enclosure 2, PPO Post Event Actions
- | 2.1.3 FD-302-700, Post Accident Sampling System
- | 2.1.4 Nuclear Regulatory Commission RTM-96, Response Technical Manual
- | 2.1.5 NUREG 0737, Post-TMI Requirements
- | 2.1.6 PASS users Manual, Volumes A through C, Crystal River Installation
- | 2.1.7 Radiological Emergency Response Plan
- | 2.1.8 Regulatory Guide 1.97, Instrumentation For Light-water Cooled Nuclear Power Plants to Assess Plant and Environs Conditions During and Following an Accident
- | 2.1.9 RSP-600, ALARA Program
- | 2.1.10 6059-S-002, APEX Technologies PASS Process Flow Diagrams

2.3 CMIS REFERENCES

DPDP-5A BREAKER 27, DPDP-5B BREAKER 8, CACP-1, CAV-126, CAV-1, CAV-3, CAV-431, CAV-432, CAV-429, CAV-430, CAV-626, CAV-627, CAV-484, CAV-439, CAV-636, CAV-519, CAV-447, CAV-437, CAV-448, CAV-623, CAV-625, CAP-10, CAP-14, CAV-436, CAV-434, CAV-441, CAV-440, CAV-624, CA-74-FI, CA-56-CI, CASB-5, AHF-55, CAV-492, CAV-493, CAV-445, CAV-446, CAV-471, DWV-337, CAP-8, CAT-8.

3.0 PERSONNEL INDOCTRINATION

3.1 DESCRIPTION

NOTE: The PASS is powered by the B ES Bus through ACDP-59.

The Post Accident Sampling System (PASS) is an on-line system designed to sample and evaluate various liquid and gaseous sample streams during an accident, including the "A" Decay Heat train. The liquid PASS Automated Isotopic And Chemical Measurement System (AIMS) consists of the subassembly used to perform Gamma Isotopic and Boron analyses of the "A" Decay Heat train.

3.2 LIMITS & PRECAUTIONS

- 3.2.1 Performance of all or part of this procedure will be done by direction of the Emergency Coordinator or designee.
- 3.2.2 Entries into the controlled access areas must have Radiation Monitoring Team preplanning, concurrence, and coverage as outlined in EM-104, Operation of the Operational Support Center. Controlled access areas will be defined by the Radiation Monitoring Team personnel.
- 3.2.3 During post-accident sampling, extremely high radiation exposure levels could be experienced. The ability to perform this procedure and stay within exposure limits will require ALARA pre-planning.
- 3.2.4 Return to the Lab if the dose rate at places requiring work is determined by the Health Physics Technician to be in excess of the limits specified in the pre-job briefing.
- 3.2.5 All sampling actions are performed on the Main Control Board by Operations, or in the Count Room either on the VAX Computer or from PASS CACP-1 and Nuclear Data Mimic Panels unless otherwise noted.
- 3.2.6 Section 4.1 must be completed prior to any sample team re-entry.
- 3.2.7 Sections 4.3, Gamma Isotopic Analysis and section 4.4, Boron Analysis, can be performed simultaneously.

4.0 INSTRUCTIONS

NOTE: Section 4.1 must be completed prior to any sample team re-entries.

4.1 SAMPLE TEAM CHECKLIST

ACTIONS	DETAILS												
4.1.1 ASSEMBLE Sample Team and REVIEW applicable procedures.	1. REVIEW the following procedures: — CH-632B, Post Accident Sampling and Analysis of the Reactor Coolant System When On the "A" Decay Heat Train — EM-104, Operation of the Operation Support Center 2. LIST personnel performing entry and their dose margins: <table border="1"><thead><tr><th data-bbox="941 934 1031 976"><u>Name</u></th><th data-bbox="1144 934 1339 976"><u>Dose Margin</u></th></tr></thead><tbody><tr><td data-bbox="909 997 1437 1039">1. _____</td><td></td></tr><tr><td data-bbox="909 1050 1437 1092">2. _____</td><td></td></tr><tr><td data-bbox="909 1102 1437 1144">3. _____</td><td></td></tr><tr><td data-bbox="909 1155 1437 1197">4. _____</td><td></td></tr><tr><td data-bbox="909 1207 1437 1249">5. _____</td><td></td></tr></tbody></table> <p style="text-align: right;"><u> / </u> Initial/Date</p>	<u>Name</u>	<u>Dose Margin</u>	1. _____		2. _____		3. _____		4. _____		5. _____	
<u>Name</u>	<u>Dose Margin</u>												
1. _____													
2. _____													
3. _____													
4. _____													
5. _____													

4.1.2 DETERMINE analyses to be performed.	LIST analyses to be performed: _____ _____ _____ _____ <p style="text-align: right;"><u> / </u> Initial/Date</p>
---	---

4.1 SAMPLE TEAM CHECKLIST (Continued)

ACTIONS	DETAILS
4.1.3 DISCUSS supplies for obtaining a sample utilizing CASB-2.	<p><u>IF</u> obtaining CASB-2 grab sample, <u>THEN ENSURE</u> the following:</p> <ul style="list-style-type: none"> ___ Allen wrench, or equivalent as determined by Chemistry supervision, for removing T-Handle from grab sampler and attaching to new grab sampler ___ Knife, or equivalent as determined by Chemistry supervision, to cut transit cover strap from lifting eye ___ New tie-wrap, or equivalent as determined by Chemistry supervision, to attach transit cover to new grab sampler lifting eye <p style="text-align: right;">_____/_____ Initial/Date</p>

NOTE: The following breakers are normally in the locked open (Off) position by Operations due to not having automatic ES closure functions.

4.1.4 ALIGN electrical power supplies	<p>___ VERIFY operations has performed EOP-14, Enclosure 2, PPO Post Event Actions</p> <p>YES ___ NO ___</p> <p><u>IF</u> EOP-14, Enclosure 2 was not performed, <u>THEN NOTIFY</u> Operations <u>ENSURE CLOSED</u> the following breakers:</p> <ul style="list-style-type: none"> ___ DPDP-5A Brk. No. 27. ___ DPDP-5B Brk. No. 8. <p style="text-align: right;">_____/_____ Initial/Date</p>
---------------------------------------	--

4.2 SAMPLE LINE-UP

ACTIONS	DETAILS
4.2.1 PERFORM valve lineup to sample "A" Decay Heat train.	ENSURE CLOSED the following valves:
	1. ___ CAV-126 2. ___ CAV-1 3. ___ CAV-3 4. ___ CAV-431 5. ___ CAV-432 6. ___ CAV-429 7. ___ CAV-430 8. ___ CAV-626 9. ___ CAV-627 10. ___ CAV-484 11. ___ CAV-439 12. ___ CAV-636
	ENSURE OPEN the following:
	13. ___ CAV-519 14. ___ CAV-447 15. ___ CAV-437 16. ___ CAV-448
	ENSURE the following:
	17. ___ CAV-623 to SAMPLE 18. ___ CAV-625 to SAMPLE 19. ___ CAV-626 to DRAIN TANK 20. ___ CAP-10 to AUTO 21. ___ CAP-10 Flow Control Switch to FULL CLOCKWISE 22. ___ CAP-14 to ON
	_____ Initial/Date

4.2.2 NOTIFY operations to OPEN Containment Isolation Valves	NOTIFY Operations OPEN the following:
	1. ___ CAV-436 2. ___ CAV-434
	_____ Initial/Date

4.2 SAMPLE LINE-UP (Continued)

ACTIONS	DETAILS
---------	---------

NOTE: Refer to section 5.0 if a HI-HI alarm occurs at CAT-8.

4.2.3 PERFORM valve lineup to sample "A" Decay Heat train.

OPEN the following:

1. ___ CAV-441
2. ___ CAV-440

NOTE: Adjusting CAV-624 valve control knob towards OPEN or CLOSED position will vary flow and pressure accordingly.

3. ___ THROTTLE CAV-624 to obtain flow rate between 0.35-0.50 gpm on CA-74-FI.

Initial/Date

4.3 GAMMA ISOTOPIC ANALYSIS

ACTIONS	DETAILS
4.3.1 FLUSH Sample lines	1. ___ ENSURE Section 4.2 SAMPLE LINE-UP performed. NOTE: While sample is flushing continue with step 4.3.2. 2. ___ FLUSH for at least 5 minutes. <div style="text-align: right;">_____/_____ Initial/Date</div>

4.3.2 PERFORM pre-analysis PASS detector checks.	1. ___ VERIFY greater than 50 pounds of liquid nitrogen at PASS liquid nitrogen monitor. ***** CAUTION: Do not reset liquid nitrogen monitor until high voltage bias has been lowered to zero. ***** 2. ___ ENSURE high voltage applied to the PASS detector at value specified in PASS AND RANGE AIMS equipment logbook. 3. ___ ENSURE weekly calibration check has been performed within the past 7 days per CH-234 as indicated on weekly count room QC logsheet in Count Room Task logbook. <div style="text-align: right;">_____/_____ Initial/Date</div>
--	---

4.3 GAMMA ISOTOPIC ANALYSIS (Continued)

ACTIONS	DETAILS
4.3.3 PERFORM Gamma Isotopic Analysis	<ol style="list-style-type: none"> 1. ____ LOG ON the VAX computer as Username: PASS 2. ____ SELECT PASS MENU. 3. ____ ENTER NO to the prompt DO YOU WANT A SPECTRAL DISPLAY WINDOW? (Default). 4. ____ SELECT LIQUID SAMPLING. 5. ____ SELECT A DECAY HEAT TRAIN. 6. ____ <u>EITHER</u>: <ol style="list-style-type: none"> a. ____ ENTER Q to quit MUX display and continue with procedure, b. ____ <u>OR</u> RETURN to update MUX values. 7. ____ ENTER NO to abort sample (Default value). 8. ____ UPDATE sample parameters. 9. ____ SELECT ACCEPT. 10. ____ SELECT QUIT key to exit. 11. ____ ENTER LO to log off VAX computer. 12. ____ ATTACH gamma scan to this procedure. 13. ____ NOTIFY OSC Chemistry Coordinator or his designee of results. <p style="margin-left: 40px;">Gamma Scan ID number:_____</p> <p style="margin-left: 120px;">_____/_____/_____ Initial/Date/Time</p> <p style="margin-left: 40px;">Gamma Scan ID number:_____</p> <p style="margin-left: 120px;">_____/_____/_____ Initial/Date/Time</p> <p style="margin-left: 40px;">Gamma Scan ID number:_____</p> <p style="margin-left: 120px;">_____/_____/_____ Initial/Date/Time</p> <ol style="list-style-type: none"> 14. ____ <u>IF</u> Additional Gamma Isotopic Analysis are required, <u>THEN</u> REPEAT steps 1 through 13. 15. ____ <u>IF</u> all analyses are complete, <u>THEN</u> PERFORM Demineralized Water Flush per Section 4.6. <p style="margin-left: 120px;">_____/_____ Initial/Date</p>

4.3 GAMMA ISOTOPIC ANALYSIS (Continued)

ACTIONS	DETAILS
4.3.4 PERFORM Core Damage Assessment	1. OSC Chemistry Coordinator PERFORM Core damage assessment per Enclosure 2.
	<u> </u> Initial/Date

4.4 BORON ANALYSIS

ACTIONS	DETAILS
4.4.1 PERFORM Boron analysis	1. ___ ENSURE Section 4.2 SAMPLE LINE-UP performed. 2. ___ FLUSH sample through the Boronometer for at least one hour. _____ flush start time

NOTE: The Boron concentration of the sample will be displayed at the readout (CA-56-CI) located on PASS Analyzer Panel (CACP-1) in courtroom.

Boron _____ PPM

3. ___ NOTIFY OSC Chemistry Coordinator or his designee of results.

_____/_____/_____
Initial/Date/Time

4. ___ IF all analyses are complete, THEN PERFORM Demineralized Water Flush per Section 4.6.

Initial/Date

4.5 GRAB SAMPLE COLLECTION AT CASB-5

ACTIONS	DETAILS
---------	---------

NOTE: Spare grab sample bombs are stored in the Oil Tank warehouse FIMIS # 1400513

4.5.1 PREPARE CASB-5 (Grab Sampler) Sample Station for Sample collection.

NOTE: CASB-5 exhaust fan (AHF-55) switch is located to the right of the Intermediate Building door (across from RM-A7).

— START CASB-5 exhaust fan (AHF-55).

Initial/Date

4.5.2 PERFORM Valve Alignment

1. — ENSURE Section 4.2 SAMPLE LINE-UP performed.
2. — OPEN CAV-445.
3. — OPEN CAV-446.
4. — CLOSE CAV-447.
5. — FLUSH for at least 15 minutes.

Initial/Date

4.5.3 ISOLATE Grab sample.

NOTE: The T-handle operator for CAV-492 and CAV-493 is attached to CASB-5.

1. — CLOSE CAV-492 using T-handle
2. — CLOSE CAV-493 using T-handle

Initial/Date

4.5.4 ISOLATE CASB-5

1. — OPEN CAV-447
2. — CLOSE CAV-445
3. — CLOSE CAV-446

Initial/Date

4.5 GRAB SAMPLE COLLECTION AT CASB-5 (Continued)

ACTIONS		DETAILS	
4.5.5	CLOSE Sample Isolation Valves.	1. ___	CLOSE CAV-441
		2. ___	CLOSE CAV-440
			<u> </u> Initial/Date

NOTE: Refer to Section 5.0 if a HI-HI alarm occurs at CAT-8.

4.5.6	ESTABLISH Demineralized Water Flush	1. ___	CLOSE CAV-624
		2. ___	OPEN DWV-337
		3. ___	OPEN CAV-471
		4. ___	START CAP-8

NOTE: Adjusting CAV-624 valve control knob towards OPEN or CLOSED position will vary flow and pressure accordingly.

5. ___ THROTTLE CAV-624 to obtain a flow rate between 0.35-0.50 gpm on CA-74-FI.

NOTE: While sample is flushing, you may continue with step 4.5.7.

6. ___ FLUSH for at least 10 minutes.

Initial/Date

4.5 GRAB SAMPLE COLLECTION AT CASB-5 (Continued)

ACTIONS	DETAILS
4.5.7 A.I.M.S. Flushing Pre-Requisites	<ol style="list-style-type: none"> 1. ___ VERIFY greater than 50 pounds of liquid nitrogen at PASS liquid nitrogen monitor. 2. ___ ENSURE high voltage applied to the PASS detector at value specified in PASS and RANGE AIMS Equipment logbook. <p style="text-align: center;">***** CAUTION: Do not reset liquid nitrogen monitor until high voltage bias has been lowered to zero. *****</p> <ol style="list-style-type: none"> 3. ___ ENSURE weekly calibration check performed within past seven days per CH-234 as indicated on weekly Count Room QC logsheet in Count Room Task Logbook. <p style="text-align: right;">_____ Initial/Date</p>

4.5.8 PERFORM A.I.M.S. Flush	<ol style="list-style-type: none"> 1. ___ LOG ON the VAX computer as Username: PASS 2. ___ SELECT PASS MENU. 3. ___ ENTER NO to DO YOU WANT A SPECTRAL DISPLAY WINDOW? (Default) 4. ___ SELECT FLUSH SAMPLE LINES. 5. ___ SELECT SUMP DEMIN FLUSH. 6. ___ MAXIMIZE MCA Display 1 and toggle through ADC's until RCS CONFIGURATION shown. 7. ___ SELECT the ERASE function on MCA Display to re-acquire spectrum. 8. ___ When a low stable count rate is indicated MINIMIZE MCA Display 1. 9. ___ SELECT RETURN. 10. ___ DEPRESS PF4 to QUIT. 11. ___ ENTER LO to log off. <p style="text-align: right;">_____ Initial/Date</p>
------------------------------	---

4.5 GRAB SAMPLE COLLECTION AT CASB-5 (Continued)

ACTIONS		DETAILS		
4.5.9	FLUSH CASB-5 (Grab Sampler)	1. ___	OPEN CAV-445	_____ Initial/Date
		2. ___	OPEN CAV-446	
		3. ___	CLOSE CAV-447	
		4. ___	FLUSH for at least 5 minutes.	
<hr/>				
4.5.10	ISOLATE CASB-5	1. ___	OPEN CAV-447	_____ Initial/Date
		2. ___	CLOSE CAV-445	
		3. ___	CLOSE CAV-446	
<hr/>				
4.5.11	SECURE Demineralized water flush after grab sampling	1. ___	STOP CAP-8	_____ Initial/Date
		2. ___	CLOSE DWV-337	
		3. ___	CLOSE CAV-471	
		4. ___	CLOSE CAV-519	
		5. ___	CLOSE CAV-447	
		6. ___	CLOSE CAV-623	
		7. ___	CLOSE CAV-624	
		8. ___	CLOSE CAV-625	
		9. ___	CLOSE CAV-626	
<hr/>				
4.5.12	NOTIFY Operations to CLOSE Containment Isolation Valves.	NOTIFY Operations CLOSE the following:		_____ Initial/Date
		1. ___	CAV-436	
		2. ___	CAV-434	

4.5 GRAB SAMPLE COLLECTION AT CASB-5 (Continued)

ACTIONS	DETAILS
4.5.13 REMOVE CASB-5 (GRAB SAMPLER)	<ol style="list-style-type: none"> 1. ___ OBTAIN 3/4" wrench from Primary Chemistry lab key locker. 2. ___ PROCEED to CASB-5 location, 95' elevation Auxiliary building. 3. ___ REMOVE the Grab Sampler ramp from storage location. 4. ___ INSTALL the Grab Sampler ramp in front of sample station. 5. ___ DISCONNECT CASB-5 from the sample station: <ol style="list-style-type: none"> a. ___ SQUEEZE disengagement lever. b. ___ PUSH the engagement handle to its rearmost position. c. ___ PULL UP on cart handle locking mechanism to release the cart. d. ___ REMOVE CASB-5 cart from sample station. 6. ___ INSTALL the transit cover over the quick connects. 7. ___ REMOVE the cart and move to the Turbine Building crane well. 8. ___ UNBOLT CASB-5 from the cart using 3/4" wrench. 9. ___ REMOVE T-handle operator. 10. ___ GO TO section 5.0 to prepare CASB-5 for shipment off-site.

Initial/Date

4.5 GRAB SAMPLE COLLECTION AT CASB-5 (Continued)

ACTIONS	DETAILS
4.5.14	INSTALL new Grab Sampler.
	<ol style="list-style-type: none"> 1. ___ BOLT new Grab Sampler onto cart. 2. ___ REMOVE transit cover. 3. ___ ATTACH transit cover to lifting ring on grab sampler. 4. ___ ATTACH T-handle operator to grab sampler. 5. ___ OPEN CAV-492 using T-handle. 6. ___ OPEN CAV-493 using T-handle. 7. ___ PROCEED to sample station.

CAUTION: When connecting CASB-5, force should NEVER be used. Damage to quick connects will result from forcing connection.

NOTE: Repeated attempts may be necessary to successfully align CASB-5.

8. ___ ENGAGE Grab Sampler CASB-5:
 - a. ___ One person GUIDE CASB-5
 - b. ___ Another person PUSH CASB-5 UP Ramp AND onto Platform,
 - c. ___ HALT CASB-5 several inches from connection points.

NOTE: WHEN positioned correctly, front of CASB-5 will make metal to metal contact with curved face of sample station.

- d. ___ SLOWLY PUSH CASB-5 into Sample Station.
- e. ___ ENGAGE Cart to Station Locking Mechanism.
- f. ___ PUSH Locking Mechanism handle completely down, DRIVING lock bolt through hole in cart.

4.5 GRAB SAMPLE COLLECTION AT CASB-5 (Continued)

ACTIONS	DETAILS
4.5.14 (Continued)	<p>***** CAUTION: When engaging handle, force should NEVER be used. Damage to quick connects will result from forcing connection. *****</p> <p>NOTE: Due to environmental conditions, the click may not be heard.</p> <p>g. — <u>GENTLY PULL</u> Engagement Handle forward until a distinct "click" is heard. This signifies that quick connect couplings have engaged.</p> <p>h. — <u>ENSURE engagement:</u> a. — <u>UNLOCK</u> Cart from station by pulling up on cart handle locking mechanism. b. — <u>MOVE</u> engagement handle back and forth. c. — <u>IF</u> properly connected, Cart will move back and forth.</p> <p>i. — <u>RE-LOCK</u> Cart to Station by pushing locking mechanism handle completely down, driving lock bolt through hole in cart.</p>

Initial/Date

4.6 DEMINERALIZED WATER FLUSH

ACTIONS		DETAILS	
4.6.1	CLOSE Sample Isolation Valves	1. <input type="checkbox"/>	CLOSE CAV-441
		2. <input type="checkbox"/>	CLOSE CAV-440
			_____/_____ Initial/Date

NOTE: Refer to Section 5.0 if a HI-HI alarm occurs at CAP-8.

4.6.2	ESTABLISH Demineralized Water Flow	1. <input type="checkbox"/>	CLOSE CAV-624
		2. <input type="checkbox"/>	OPEN DWV-337
		3. <input type="checkbox"/>	OPEN CAV-471
		4. <input type="checkbox"/>	START CAP-8
			_____/_____ Initial/Date

NOTE: Adjusting the CAV-624 valve control knob towards OPEN or CLOSED position will vary flow and pressure accordingly.

5. THROTTLE CAV-624 to obtain flow, between 0.35-0.50 gpm on CA-74-FI.

4.6.3	FLUSH system	NOTE: Steps 4.6.3 and 4.6.4 may be performed concurrently.	
		<input type="checkbox"/>	FLUSH system for at least 10 minutes.
			_____/_____ Initial/Date

4.6 DEMINERALIZED WATER FLUSH (Continued)

ACTIONS	DETAILS
4.6.4 A.I.M.S. Flushing Pre-Requisites	1. ____ VERIFY greater than 50 pounds of liquid nitrogen at PASS liquid nitrogen monitor. 2. ____ ENSURE high voltage applied to the PASS detector at value specified in PASS And RANGE AIMS Equipment Logbook.
***** CAUTION: Do not reset liquid nitrogen monitor until high voltage bias has been lowered to zero. *****	
	3. ____ ENSURE weekly calibration check performed within past seven days per CH-234 as indicated on weekly Count Room QC logsheet in Count Room Task Logbook.

Initial/Date

4.6 DEMINERALIZED WATER FLUSH (Continued)

ACTIONS	DETAILS
---------	---------

NOTE: ERASE cannot be performed from a remote terminal

- 4.6.5 PERFORM A.I.M.S. Flush
1. ___ LOG ON the VAX computer as
Username: PASS
 2. ___ SELECT PASS MENU.
 3. ___ ENTER NO to DO YOU WANT A
SPECTRAL DISPLAY WINDOW?
(Default)
 4. ___ SELECT FLUSH SAMPLE LINES.
 5. ___ SELECT SUMP DEMIN FLUSH.
 6. ___ MAXIMIZE MCA Display 1 and
toggle through ADC's until
RCS CONFIGURATION shown.
 7. ___ SELECT the ERASE function
on MCA Display to re-
acquire spectrum.
 8. ___ When a low stable count
rate is indicated MINIMIZE
MCA Display 1.
 9. ___ SELECT RETURN.
 10. ___ DEPRESS PF4 to QUIT.
 11. ___ ENTER LO to log off.

Initial/Date

- 4.6.6 SECURE Demineralized Water
Flush
1. ___ STOP CAP-8
 2. ___ CLOSE DWV-337
 3. ___ CLOSE CAV-471
 4. ___ CLOSE CAV-519
 5. ___ CLOSE CAV-447
 6. ___ CLOSE CAV-623
 7. ___ CLOSE CAV-624
 8. ___ CLOSE CAV-625
 9. ___ CLOSE CAV-626

NOTIFY Operations CLOSE the
following:

10. ___ CAV-436
11. ___ CAV-434

Initial/Date

4.7 SYSTEM RESTORATION

ACTIONS	DETAILS
---------	---------

4.7.1 SECURE flow

ENSURE CLOSED the following:

1. ___ CAV-441
2. ___ CAV-440
3. ___ CAV-471
4. ___ CAV-447
5. ___ CAV-448
6. ___ CAV-484
7. ___ CAV-519
8. ___ CAV-623
9. ___ CAV-624
10. ___ CAV-625
11. ___ CAV-626
12. ___ CAV-627

Initial/Date

5.0 CONTINGENCIES

5.1 CAT-8 HI-HI LEVEL ALARM

ACTIONS	DETAILS
5.1.1 PERFORM lineup	ENSURE the following: 1. ___ CAP-10 OFF 2. ___ CAV-623 CLOSED 3. ___ CAV-627 CLOSED 4. ___ CONCURRENTLY PERFORM the following until CAT-8 HI-HI level alarm light clears: o DEPRESS and hold RESET button on Drain Tank level indicator o SELECT CAP-10 to ON 5. ___ OPEN CAV-623 6. ___ SELECT CAP-10 to AUTO 7. ___ RETURN to the step in the procedure which was in progress when the CAT-8 HI-HI level alarm occurred.

Initial/Date

5.2 NOTIFICATIONS AND SHIPMENT

ACTIONS	DETAILS
NOTE: The Emergency 24 hour access phone number is (804) 522-5833.	
NOTE: Spare grab sample bombs are stored in the Oil Tank warehouse FIMIS # 1400513.	
5.2.1 PERFORM notifications	<ul style="list-style-type: none">— Notify the Manager, Nuclear Operations Materials Controls that a grab sample has been taken and to initiate acquisition process for shielded sample cask.— Notify the BWX Technologies Emergency Sample Coordinator when a grab sample has been collected that will require offsite analysis.— Required information to be made available:<ul style="list-style-type: none">o Utility and plant nameo Name and phone of ChemRad Specialist to whom follow-up communication should be addressed.o Number and type of samples to be shipped (i.e., liquid, gaseous, or iodine cartridge).o Measured radiation levels at the surface and three feet from the shipping container.o Estimated shipping time, mode of transportation, carrier, and estimated arrival at BWX Technologies site in Lynchburg, VA.

(Continued on next page)

5.2 NOTIFICATIONS AND SHIPMENT (Cont'd)

ACTIONS	DETAILS
5.2.1 Continued	Shipping Address: BWX Technologies Lynchburg Technology Center Route 726, Mt. Athos Road Lynchburg, VA. 24506 Attn: Kenneth D. Long (804) 522-5982
	— All data accumulated per this procedure is to be summarized on Enclosure 1 and forwarded to the Emergency Coordinator via Chemistry Supervision.
	<u> </u> Initial/Date

TECHNICAL SUPPORT CENTER DATA SHEET

"A" DECAY HEAT TRAIN SAMPLE

Gamma Isotopic and/or Boron Analysis Results

Boron _____ ppm _____ / ____ / ____
Initial/Date/Time

Boron _____ ppm _____ / ____ / ____
Initial/Date/Time

Boron _____ ppm _____ / ____ / ____
Initial/Date/Time

Boron _____ ppm _____ / ____ / ____
Initial/Date/Time

Total Activity _____ uCi/cc

Major Contributing Isotopes

Isotope	Activity
_____	_____ uCi/cc
_____	_____ uCi/cc
_____	_____ uCi/cc
_____	_____ uCi/cc
_____	_____ uCi/cc
_____	_____ uCi/cc
_____	_____ uCi/cc
_____	_____ uCi/cc
_____	_____ uCi/cc
_____	_____ uCi/cc
_____	_____ uCi/cc
_____	_____ uCi/cc
_____	_____ uCi/cc

_____ / ____ / ____
Initial/Date/Time

ASSESSMENT OF CORE DAMAGE BASED ON REACTOR COOLANT SAMPLE ("A" DECAY HEAT)

1. This method of confirming core damage assumes that releases from the core are uniformly mixed in the "A" Decay Heat Train AND there is no dilution from injection.
2. The baseline coolant concentrations in Table 1 are for 0.5 hour after shutdown of a core that has been through at least one refueling cycle.
3. The half-life of the fission products should be considered in analyzing samples.
4. Compare the "A" Decay Heat PASS sample activities from Enclosure 1 with the baseline coolant concentrations in Table 1. This table overestimates the concentration of the long-lived fission products (Cs and Sr) in a new core.
5. Determine the extent of core damage as indicated by Table 1 (i.e., normal, gas gap, core melt).

TABLE 1

BASELINE REACTOR COOLANT CONCENTRATION

Nuclide	Normal Concentration (uCi/g)	Concentration After Gap Release (uCi/g)	Concentration After Core Melt (uCi/g)	TMI Concentration + 48 Hours (uCi/g)
I-131	4E-2	2E4	1E5	1.3E4
I-133	1E-1	3E4	2E5	6.5E3
I-135	2E-1	3E4	2E5	No Data
Cs-134	7E-3	2E3	8E3	6.3E1
Cs-137	9E-3	9E2	5E3	2.8E2
Ba-140	No Data	No Data	3E4	No Data
Sr-90	1E-5	No Data	1E4	5.3

6. Report determination to Dose Assessment Coordinator.

Initial/Date

PROCEDURE DEVELOPMENT AND REVISION RECORD

Procedure: CH0632B New Rev: 2 PRR#: 17340

Title: POST ACCIDENT SAMPLING AND ANALYSIS OF REACTOR COOLANT WHEN ON THE "A" DECAY HEAT SYSTEM

MINOR CHANGES

If Minor Changes are included, check the applicable box(es) and provide a list of affected steps.
The following corrections are incorporated throughout:

- | | |
|---|---|
| <input type="checkbox"/> Sentence Structure | <input type="checkbox"/> Redundant words or phrases |
| <input type="checkbox"/> Punctuation | <input type="checkbox"/> Abbreviations |
| <input type="checkbox"/> Capitalization | <input type="checkbox"/> Obviously incorrect units of measure |
| <input type="checkbox"/> Spelling | <input type="checkbox"/> Inadvertently omitted symbols (#, %, etc.) |
| <input type="checkbox"/> Organizational Changes: position titles,
department names, or telephone numbers | <input type="checkbox"/> Obvious step numbering discrepancies |
| <input type="checkbox"/> Format | |

The following corrections are incorporated in the step(s) indicated: "Throughout" is used in lieu of Step# if a specific change affects a large number of steps.

Correcting equipment nomenclature that does not agree with field labels or balance of procedure

Changing information that is obviously incorrect and referenced correctly elsewhere

Misplaced decimals that are neither setpoint values nor tolerances

Reference to a procedure when an approved procedure has taken the place of another procedure

Fixing branching points when it is clear the branching steps were originally intended but were overlooked or incorrectly stated due to step number changes

Adding clarifying information such as NOTES and CAUTIONS

Adding words to clarify steps, NOTES, or CAUTIONS which clearly do not change the methodology or intent of the steps

PROCEDURE DEVELOPMENT AND REVISION RECORD

Procedure: CH0632B New Rev: 2 PRR#: 17340

Title: POST ACCIDENT SAMPLING AND ANALYSIS OF REACTOR COOLANT WHEN ON THE "A" DECAY HEAT SYSTEM

MINOR CHANGES

If Minor Changes are included, check the applicable box(es) and provide a list of affected steps.
The following corrections are incorporated throughout:

- | | |
|--|--|
| <input type="checkbox"/> Sentence Structure | <input type="checkbox"/> Redundant words or phrases |
| <input type="checkbox"/> Punctuation | <input type="checkbox"/> Abbreviations |
| <input type="checkbox"/> Capitalization | <input type="checkbox"/> Obviously incorrect units of measure |
| <input type="checkbox"/> Spelling | <input type="checkbox"/> Inadvertently omitted symbols (#, %, etc.) |
| <input checked="" type="checkbox"/> Organizational Changes: position titles,
department names, or telephone numbers | <input checked="" type="checkbox"/> Obvious step numbering discrepancies |
| <input checked="" type="checkbox"/> Format | |

The following corrections are incorporated in the step(s) indicated: "Throughout" is used in lieu of Step# if a specific change affects a large number of steps.

Correcting equipment nomenclature that does not agree with field labels or balance of procedure

Changing information that is obviously incorrect and referenced correctly elsewhere

Misplaced decimals that are neither setpoint values nor tolerances

Reference to a procedure when an approved procedure has taken the place of another procedure

Fixing branching points when it is clear the branching steps were originally intended but were overlooked or incorrectly stated due to step number changes

5.2 Adding clarifying information such as NOTES and CAUTIONS

Adding words to clarify steps, NOTES, or CAUTIONS which clearly do not change the methodology or intent of the steps

PROCEDURE DEVELOPMENT AND REVISION RECORD

Procedure: FP0701 New Rev: 25 PRR#: 17771

Title: INCORE MONITOR HANDLING

NON-INTENT CHANGES

Changes are incorporated for the reasons provided. "Throughout" is used in lieu of Step # if a specific change affects a large number of steps. For new or cancelled procedures the reason is provided.

4.6.5 - 4.6.5.3 Added information for routing and securing cables to cable support assemblies.

Enclosure 11 Changed NIA cables numbers NIA41, 43, 45, 47, 49, 51 to NIA328, 329, 330, 331, 332
Enclosure 12 and 333 respectively.

Enclosure 15 Added new Incore Cable Connection Separation Schedule
(7 pages).

2.1.11 Added MAR 96-11-03-01, Subcooling Margin Monitor Upgrade as a reference.
