

To: NRC (DC DESK)

MAC: N/A

Holder #: 1242

Destination:

Description:

Document:	Revision:	II	IC#	Comment:	Copy Totals		
					INF	CTL	MST
CH0632C	02				1	0	0
CH0632D	04				1	0	0

**Instructions to the Addressee:** Please verify the document(s) received agrees with the above information. Notify Document Control if changes are required to addressee information, or mark the transmittal and return as indicated below.

Engineering managers are required by NEP-121 to determine if new, revised, or temporary changes to procedures affect job functions of their personnel. Managers will communicate change information appropriately and provide documentation of any training conducted to the Engineering Training Coordinator.

Operations department must attach old document(s) or portions of document(s) superseded by the above to this transmittal.

The signature indicates acknowledgment of receipt of the above document(s) and that documents have been updated. Return signed and dated transmittal to Document Control within 15 working days of transmittal date to mail code:

\_\_\_\_ SA2A  
\_\_\_\_ Florida Power Corporation  
Document Control, SA2A  
Crystal River Energy Complex  
15760 W. Power Line St.  
Crystal River, FL 34428-6708

091002

A0450/

Signature of Addressee: \_\_\_\_\_ Date: \_\_\_\_\_

Rev. 2

Effective Date 10/23/99

CHEMISTRY SAMPLING PROCEDURE

CH-632C

EMERGENCY PLAN IMPLEMENTING PROCEDURE

FLORIDA POWER CORPORATION

CRYSTAL RIVER UNIT 3

POST ACCIDENT SAMPLING AND ANALYSIS OF REACTOR COOLANT  
WHEN ON THE "B" DECAY HEAT SYSTEM

APPROVED BY: Procedure Owner

  
(SIGNATURE ON FILE)

DATE: 10/22/99

PROCEDURE OWNER: Nuclear Chemistry

## TABLE OF CONTENTS

<u>SECTION</u>		<u>PAGE</u>
<u>1.0</u>	<u>PURPOSE</u> .....	1
<u>2.0</u>	<u>REFERENCES</u> .....	1
	2.1 <u>DEVELOPMENTAL REFERENCES</u> .....	1
	2.2 <u>CMIS REFERENCES</u> .....	1
<u>3.0</u>	<u>PERSONNEL INDOCTRINATION</u> .....	2
	3.1 <u>DESCRIPTION</u> .....	2
	3.2 <u>LIMITS &amp; PRECAUTIONS</u> .....	2
<u>4.0</u>	<u>INSTRUCTIONS</u> .....	3
	4.1 <u>SAMPLE TEAM CHECKLIST</u> .....	3
	4.2 <u>SAMPLE LINE-UP</u> .....	6
	4.3 <u>GAMMA ISOTOPIC ANALYSIS</u> .....	8
	4.4 <u>BORON ANALYSIS</u> .....	10
	4.5 <u>GRAB SAMPLE COLLECTION AT CASB-5</u> .....	11
	4.6 <u>DEMINERALIZED WATER FLUSH</u> .....	18
	4.7 <u>SYSTEM RESTORATION</u> .....	20
<u>5.0</u>	<u>CONTINGENCIES</u> .....	21
	5.1 <u>CAT-8 HI-HI LEVEL ALARM</u> .....	21
	5.2 <u>NOTIFICATIONS AND SHIPMENT</u> .....	22

## ENCLOSURES

1	Technical Support Center Data Sheet .....	23
2	Assessment of Core Damage Based on Reactor Coolant Sample ("B" Decay Heat) .....	24

## **1.0 PURPOSE**

This procedure provides instructions for sampling the "B" Decay Heat Train under accident conditions for Gamma Isotopic and Boron analyses using the Post Accident Sampling System.

## **2.0 REFERENCES**

### **2.1 DEVELOPMENTAL REFERENCES**

- 2.1.1 APEX Technologies Post Accident Sample System Modules Manual, FPC Manual #2034
- 2.1.2 EOP-14, Enclosure 2, PPO Post Event Actions
- 2.1.3 FD-302-700, Post Accident Sampling System
- 2.1.4 Nuclear Regulatory Commission RTM-96, Response Technical Manual
- 2.1.5 NUREG 0737, Post-TMI Requirements
- 2.1.6 PASS Users Manual Volumes A through C, Crystal River Installation
- 2.1.7 Radiological Emergency Response Plan
- 2.1.8 Regulatory Guide 1.97, Instrumentation For Light-Water Cooled Nuclear Power Plants To Assess Plant And Environs Conditions During And Following An Accident
- 2.1.9 RSP-600, ALARA Program
- 2.1.10 6059-S-002, APEX Technologies PASS Process Flow Diagrams

### **2.2 CMIS REFERENCES**

DPDP-5A BREAKER 27, DPDP-5B BREAKER 8, CACP-1, CAV-126, CAV-1, CAV-3, CAV-431, CAV-432, CAV-429, CAV-430, CAV-626, CAV-627, CAV-484, CAV-439, CAV-636, CAV-519, CAV-447, CAV-437, CAV-448, CAV-623, CAV-625, CAP-10, CAP-14, CAV-436, CAV-434, CAV-442, CAV-440, CAV-624, CA-74-FI, CA-56-CI, CASB-5, AHF-55, CAV-492, CAV-493, CAV-445, CAV-446, CAV-471, DWV-337, CAP-8, CAT-8.

### **3.0      PERSONNEL INDOCTRINATION**

#### **3.1      DESCRIPTION**

**NOTE:** The PASS is powered by the B ES Bus through ACDP-59.

The Post Accident Sampling System (PASS) is an on-line system designed to sample and evaluate various liquid and gaseous sample streams during an accident, including the "B" Decay Heat train. The liquid PASS Automated Isotopic And Chemical Measurement System (AIMS) consists of the subassembly used to perform Gamma Isotopic and Boron analyses of the "B" Decay Heat train.

#### **3.2      LIMITS & PRECAUTIONS**

3.2.1 Performance of all or part of this procedure will be done by direction of the Emergency Coordinator or designee.

3.2.2 Entries into the controlled access areas must have Radiation Monitoring Team preplanning, concurrence, and coverage as outlined in EM-104, Operation of the Operational Support Center. Controlled access areas will be defined by the Radiation Monitoring Team personnel.

3.2.3 During post-accident sampling, extremely high radiation exposure levels could be experienced. The ability to perform this procedure and stay within exposure limits will require ALARA pre-planning.

3.2.4 Return to the Lab if the dose rate at places requiring work is determined by the Health Physics Technician to be in excess of the limits specified in the pre-job briefing.

3.2.5 All sampling actions are performed on the Main Control Board by Operations, or in the Count Room either on the VAX Computer or from PASS CACP-1 and Nuclear Data Mimic Panels unless otherwise noted.

3.2.6 Section 4.1 must be completed prior to any sample team re-entry.

3.2.7 Sections 4.3, Gamma Isotopic Analysis, and Section 4.4, Boron Analysis, can be performed simultaneously.

#### 4.0 INSTRUCTIONS

NOTE: Section 4.1 must be completed prior to any sample team re-entries.

#### 4.1 SAMPLE TEAM CHECKLIST

ACTIONS	DETAILS										
4.1.1 ASSEMBLE Sample Team and REVIEW applicable procedures.	<p>1. REVIEW the following procedures:</p> <p>_____ CH-632C, Post Accident Sampling and Analysis of the Reactor Coolant System When on the "B" Decay Heat Train</p> <p>_____ EM-104, Operation Of The Operational Support Center</p> <p>2. LIST personnel performing entry and their dose margins:</p> <table><thead><tr><th>Name</th><th>Dose Margin</th></tr></thead><tbody><tr><td>1. _____</td><td>_____</td></tr><tr><td>2. _____</td><td>_____</td></tr><tr><td>3. _____</td><td>_____</td></tr><tr><td>4. _____</td><td>_____</td></tr></tbody></table> <p>_____/_____ Initial/Date</p>	Name	Dose Margin	1. _____	_____	2. _____	_____	3. _____	_____	4. _____	_____
Name	Dose Margin										
1. _____	_____										
2. _____	_____										
3. _____	_____										
4. _____	_____										
4.1.2 DETERMINE analyses to be performed.	<p>LIST analyses to be performed:</p> <p>_____</p> <p>_____</p> <p>_____</p> <p>_____/_____ Initial/Date</p>										

4.1 SAMPLE TEAM CHECKLIST (Cont'd)

ACTIONS	DETAILS
4.1.3 DISCUSS supplies for obtaining a sample utilizing CASB-2.	<p data-bbox="841 365 1360 432"><u>IF</u> obtaining CASB-2 grab sample, <u>THEN</u> ENSURE the following:</p> <ul style="list-style-type: none"><li data-bbox="841 462 1455 617">___ Allen wrench, or equivalent, as determined by Chemistry supervision, for removing T-Handle from grab sampler and attaching to new grab sampler</li><li data-bbox="841 617 1435 743">___ Knife, or equivalent, as determined by Chemistry supervision, to cut transit cover strap from lifting eye</li><li data-bbox="841 743 1435 898">___ New tie-wrap, or equivalent as determined by Chemistry supervision, to attach transit cover to new grab sampler lifting eye</li></ul> <p data-bbox="1260 932 1455 991" style="text-align: right;">_____ Initial/Date</p>

4.1 SAMPLE TEAM CHECKLIST (Cont'd)

ACTIONS	DETAILS
NOTE: The following breakers are normally in the locked open (Off) position by Operations due to not having automatic ES closure functions.	
4.1.4 ALIGN electrical power supplies	<div>___ VERIFY Operations has performed EOP-14, Enclosure 2 PPO Post Event Actions. YES ___ NO ___</div> <div>IF EOP-14, Enclosure 2 was not performed, THEN NOTIFY Operations ENSURE CLOSED the following breakers:</div> <div>___ DPDP-5A Brk. No. 27 ___ DPDP-5B Brk. No. 8</div> <div>_____ Initial/Date</div>



## 4.2 SAMPLE LINE-UP

ACTIONS	DETAILS
4.2.1 PERFORM valve lineup to sample "B" Decay Heat train.	<div data-bbox="896 367 1459 394">ENSURE CLOSED the following valves:</div> <div data-bbox="896 430 1130 800"><ul style="list-style-type: none"><li>1. <input type="checkbox"/> CAV-126</li><li>2. <input type="checkbox"/> CAV-1</li><li>3. <input type="checkbox"/> CAV-3</li><li>4. <input type="checkbox"/> CAV-431</li><li>5. <input type="checkbox"/> CAV-432</li><li>6. <input type="checkbox"/> CAV-429</li><li>7. <input type="checkbox"/> CAV-430</li><li>8. <input type="checkbox"/> CAV-626</li><li>9. <input type="checkbox"/> CAV-627</li><li>10. <input type="checkbox"/> CAV-484</li><li>11. <input type="checkbox"/> CAV-439</li><li>12. <input type="checkbox"/> CAV-636</li></ul></div> <div data-bbox="896 835 1312 863">ENSURE OPEN the following:</div> <div data-bbox="896 898 1130 1016"><ul style="list-style-type: none"><li>13. <input type="checkbox"/> CAV-519</li><li>14. <input type="checkbox"/> CAV-447</li><li>15. <input type="checkbox"/> CAV-437</li><li>16. <input type="checkbox"/> CAV-448</li></ul></div> <div data-bbox="896 1052 1229 1079">ENSURE the following:</div> <div data-bbox="896 1115 1435 1325"><ul style="list-style-type: none"><li>17. <input type="checkbox"/> CAV-623 to SAMPLE</li><li>18. <input type="checkbox"/> CAV-625 to SAMPLE</li><li>19. <input type="checkbox"/> CAV-626 to DRAIN TANK</li><li>20. <input type="checkbox"/> CAP-10 to AUTO</li><li>21. <input type="checkbox"/> CAP-10 Flow Control Switch to FULL CLOCKWISE</li><li>22. <input type="checkbox"/> CAP-14 to ON</li></ul></div> <div data-bbox="1279 1360 1474 1417"><div>____/____</div>Initial/Date</div>
4.2.2 NOTIFY Operations to OPEN Containment Isolation Valves	<div data-bbox="883 1514 1476 1541">NOTIFY Operations OPEN the following:</div> <div data-bbox="883 1577 1166 1633"><ul style="list-style-type: none"><li>1. <input type="checkbox"/> CAV-436</li><li>2. <input type="checkbox"/> CAV-434</li></ul></div> <div data-bbox="1312 1669 1507 1726"><div>____/____</div>Initial/Date</div>

4.2 SAMPLE LINE-UP (Cont'd)

ACTIONS	DETAILS
---------	---------

NOTE: Refer to Section 5.0 if a HI-HI alarm occurs at CAT-8.

4.2.3 PERFORM valve lineup to  
SAMPLE "B" Decay Heat  
train.

OPEN the following:

1. ☐ CAV-442
2. ☐ CAV-440

NOTE: Adjusting CAV-624 valve  
control knob towards OPEN or  
CLOSED position will vary  
flow and pressure  
accordingly.

3. ☐ THROTTLE CAV-624 to obtain  
flow rate between  
0.35-0.50 gpm on CA-74-FI.

\_\_\_\_\_  
Initial/Date

4.3 GAMMA ISOTOPIC ANALYSIS

ACTIONS		DETAILS
4.3.1	FLUSH Sample lines	<p>1. ____ ENSURE Section 4.2 SAMPLE LINE-UP performed.</p> <p>NOTE: While sample is flushing continue with Step 4.3.2.</p> <p>2. ____ FLUSH for at least 5 minutes</p> <p>____/____ Initial/Date</p>
4.3.2	PERFORM pre-analysis PASS detector checks.	<p>1. ____ VERIFY greater than 50 pounds of liquid nitrogen at PASS liquid nitrogen monitor.</p> <p>***** CAUTION: Do not reset liquid nitrogen monitor until high voltage bias has been lowered to zero. *****</p> <p>2. ____ ENSURE high voltage applied to the PASS detector at value specified in PASS AND RANGE equipment logbook.</p> <p>3. ____ ENSURE a weekly calibration check performed within the past 7 days per CH-234 as indicated on weekly countroom QC logsheet in Count Room Task logbook</p> <p>____/____ Initial/Date</p>

### 4.3 GAMMA ISOTOPIC ANALYSIS (Cont'd)

ACTIONS	DETAILS
4.3.3 PERFORM Gamma Isotopic Analysis	<ol style="list-style-type: none"> <li>1. ____ LOG ON the VAX computer as Username: PASS</li> <li>2. ____ SELECT PASS MENU.</li> <li>3. ____ ENTER NO to the prompt DO YOU WANT A SPECTRAL DISPLAY WINDOW?(Default)</li> <li>4. ____ SELECT LIQUID SAMPLING.</li> <li>5. ____ SELECT B DECAY HEAT TRAIN</li> <li>6. <u>EITHER</u>:               <ol style="list-style-type: none"> <li>a. ____ ENTER Q to quit MUX display and continue with procedure,</li> <li>b. ____ <u>OR</u> RETURN to update MUX values.</li> </ol> </li> <li>7. ____ ENTER NO to abort sample (Default value).</li> <li>8. ____ UPDATE sample parameters.</li> <li>9. ____ SELECT ACCEPT.</li> <li>10. ____ SELECT QUIT key to exit</li> <li>11. ____ ENTER LO to log off VAX computer.</li> <li>12. ____ ATTACH gamma scan to this procedure.</li> <li>13. ____ NOTIFY OSC Chemistry Coordinator or his designee of results.  <div style="text-align: right;">Gamma Scan ID number: _____</div> <div style="text-align: right;">_____/_____/_____ Initial/Date/Time</div> <div style="text-align: right;">Gamma Scan ID number: _____</div> <div style="text-align: right;">_____/_____/_____ Initial/Date/Time</div> <div style="text-align: right;">Gamma Scan ID number: _____</div> <div style="text-align: right;">_____/_____/_____ Initial/Date/Time</div> </li> <li>14. ____ <u>IF</u> Additional Gamma Isotopic Analysis are required, <u>THEN</u> REPEAT steps 1 through 13.</li> <li>15. ____ <u>IF</u> all analyses are complete, <u>THEN</u> PERFORM Demineralized Water Flush per Section 4.6.</li> </ol> <div style="text-align: right;">_____/_____/_____ Initial/Date</div>

### 4.3 GAMMA ISOTOPIC ANALYSIS (Cont'd)

ACTIONS	DETAILS
4.3.4      PERFORM Core Damage Assessment	1. ____ OSC Chemistry Coordinator or designee PERFORM Core damage assessment per Enclosure 2  <div style="text-align: right;">_____ Initial/Date</div>

### 4.4 BORON ANALYSIS

- 4.4.1      PERFORM Boron analysis
1. \_\_\_\_ ENSURE Section 4.2 SAMPLE LINE-UP performed.
  2. \_\_\_\_ FLUSH sample through the Boronometer for at least one hour.
- \_\_\_\_\_  
flush start time

NOTE: The Boron concentration of the sample will be displayed at the readout (CA-56-CI) located on PASS Analyzer Panel (CACP-1) in countroom.

Boron \_\_\_\_\_ PPM

3. \_\_\_\_ NOTIFY OSC Chemistry Coordinator or his designee of results.

\_\_\_\_\_  
Initial/Date/Time

4. \_\_\_\_ IF all analyses are complete,  
THEN PERFORM Demineralized Water Flush per Section 4.6.

\_\_\_\_\_  
Initial/Date

4.5 GRAB SAMPLE COLLECTION AT CASB-5

ACTIONS	DETAILS
<b>NOTE: Spare grab sample bombs are stored in the Oil Tank warehouse FIMIS # 1400513.</b>	
4.5.1 PREPARE CASB-5 (Grab Sampler) Sample Station for Sample collection.	<b>NOTE: CASB-5 exhaust (AHF-55) fan switch is located to the right of the Intermediate Building door (across from RM-A7)</b>  — START CASB-5 (AHF-55) exhaust fan.  <div style="text-align: right;">_____ Initial/Date</div>
4.5.2 PERFORM Valve Alignment	<ol style="list-style-type: none"><li>1. — ENSURE Section 4.2 SAMPLE LINE-UP performed.</li><li>2. — OPEN CAV-445.</li><li>3. — OPEN CAV-446.</li><li>4. — CLOSE CAV-447.</li><li>5. — FLUSH for at least 15 minutes.</li></ol> <div style="text-align: right;">_____ Initial/Date</div>
4.5.3 ISOLATE Grab sample.	<b>NOTE: The T-handle operator for CAV-492 and CAV-493 is attached to CASB-5.</b> <ol style="list-style-type: none"><li>1. — CLOSE CAV-492 using T-handle.</li><li>2. — CLOSE CAV-493 using T-handle.</li></ol> <div style="text-align: right;">_____ Initial/Date</div>
4.5.4 ISOLATE CASB-5	<ol style="list-style-type: none"><li>1. — OPEN CAV-447</li><li>2. — CLOSE CAV-445</li><li>3. — CLOSE CAV-446</li></ol> <div style="text-align: right;">_____ Initial/Date</div>
4.5.5 CLOSE Sample Isolation Valves.	<ol style="list-style-type: none"><li>1. — CLOSE CAV-442</li><li>2. — CLOSE CAV-440</li></ol> <div style="text-align: right;">_____ Initial/Date</div>

4.5 GRAB SAMPLE COLLECTION AT CASB-5 (Cont'd)

ACTIONS	DETAILS
---------	---------

NOTE: Refer to Section 5.0 if a HI-HI alarm occurs at CAT-8.

4.5.6 ESTABLISH Demineralized Water  
Flush

1. ☐ CLOSE CAV-624
2. ☐ OPEN DWV-337
3. ☐ OPEN CAV-471
4. ☐ START CAP-8

NOTE: Adjusting CAV-624 valve control knob towards OPEN or CLOSED position will vary flow and pressure accordingly.

5. ☐ THROTTLE CAV-624 to obtain a flow rate between 0.35-0.50 gpm on CA-74-FI.

NOTE: While sample is flushing you may continue with 4.5.7.

6. ☐ FLUSH for at least 10 minutes

\_\_\_\_\_  
Initial/Date

GRAB SAMPLE COLLECTION AT CASB-5 (Cont'd)

ACTIONS		DETAILS
4.5.7	A.I.M.S. Flushing Pre-Requisites	<ol style="list-style-type: none"> <li>1. ____ VERIFY greater than 50 pounds of liquid nitrogen at PASS liquid nitrogen monitor.</li> <li>2. ____ ENSURE high voltage applied to the PASS detector at value specified in PASS and RANGE AIMS Equipment logbook.</li> </ol> <p>*****</p> <p><b>CAUTION: Do not reset liquid nitrogen monitor until high voltage bias has been lowered to zero.</b></p> <p>*****</p> <ol style="list-style-type: none"> <li>3. ____ ENSURE weekly calibration check performed within past seven days per CH-234 as indicated on weekly Count Room QC logsheet in Count Room Task Logbook.</li> </ol>

\_\_\_\_\_  
Initial/Date

```

4.5.8      PERFORM A.I.M.S. Flush
1.  ____  LOG ON the VAX computer as
          Username: PASS
2.  ____  SELECT PASS MENU.
3.  ____  ENTER NO to DO YOU WANT A
          SPECTRAL DISPLAY WINDOW?
          (Default)
4.  ____  SELECT FLUSH SAMPLE LINES.
5.  ____  SELECT SUMP DEMIN FLUSH.
6.  ____  MAXIMIZE MCA Display 1 and
          toggle through ADC's until
          RCS CONFIGURATION shown.
7.  ____  SELECT the ERASE function
          on MCA Display to re-
          acquire spectrum.
8.  ____  When a low stable
          countrate is indicated
          MINIMIZE MCA Display 1.
9.  ____  SELECT RETURN.
10. ____  DEPRESS PF4 to QUIT.
11. ____  ENTER LO to log off.

```

Initial/Date



4.5 GRAB SAMPLE COLLECTION AT CASB-5 (Cont'd)

ACTIONS		DETAILS
4.5.9	FLUSH CASB-5 (Grab Sampler)	1. <input type="checkbox"/> OPEN CAV-445. 2. <input type="checkbox"/> OPEN CAV-446. 3. <input type="checkbox"/> CLOSE CAV-447. 4. <input type="checkbox"/> FLUSH for at least 5 minutes.
		_____ Initial/Date
4.5.10	ISOLATE CASB-5	1. <input type="checkbox"/> OPEN CAV-447. 2. <input type="checkbox"/> CLOSE CAV-445. 3. <input type="checkbox"/> CLOSE CAV-446.
		_____ Initial/Date
4.5.11	SECURE Demineralized water flush after grab sampling	1. <input type="checkbox"/> STOP CAP-8. 2. <input type="checkbox"/> CLOSE DWV-337. 3. <input type="checkbox"/> CLOSE CAV-471. 4. <input type="checkbox"/> CLOSE CAV-519. 5. <input type="checkbox"/> CLOSE CAV-447. 6. <input type="checkbox"/> CLOSE CAV-623. 7. <input type="checkbox"/> CLOSE CAV-624. 8. <input type="checkbox"/> CLOSE CAV-625. 9. <input type="checkbox"/> CLOSE CAV-626.
		_____ Initial/Date
4.5.12	NOTIFY Operations to CLOSE Containment Isolation Valves.	NOTIFY Operations CLOSE the following: 1. <input type="checkbox"/> CAV-436 2. <input type="checkbox"/> CAV-434
		_____ Initial/Date

4.5 GRAB SAMPLE COLLECTION AT CASB-5 (Cont'd)

ACTIONS	DETAILS
4.5.13 REMOVE CASB-5 (GRAB SAMPLER)	<ol style="list-style-type: none"><li>1. — OBTAIN 3/4" wrench from Primary Chemistry lab key locker.</li><li>2. — PROCEED to CASB-5 location, 95' elevation Auxiliary building.</li><li>3. — REMOVE the Grab Sampler ramp from storage location.</li><li>4. — INSTALL the Grab Sampler ramp in front of sample station.</li><li>5. — DISCONNECT CASB-5 from the sample station:<ol style="list-style-type: none"><li>a. — SQUEEZE disengagement lever</li><li>b. — PUSH the engagement handle to its rearmost position.</li><li>c. — PULL UP on cart handle locking mechanism to release the cart.</li><li>d. — REMOVE CASB-5 cart from sample station.</li></ol></li><li>6. — INSTALL the transit cover over the quick connects.</li><li>7. — REMOVE the cart and move to the Turbine Building crane well.</li><li>8. — UNBOLT CASB-5 from the cart using 3/4" wrench.</li><li>9. — REMOVE T-handle operator.</li><li>10. — GO TO section 5.0 to prepare CASB-5 for shipment off-site.</li></ol>

\_\_\_\_\_  
Initial/Date

4.5 GRAB SAMPLE COLLECTION AT CASB-5 (Cont'd)

ACTIONS	DETAILS
4.5.14 INSTALL new Grab Sampler.	1. <input type="checkbox"/> BOLT new Grab Sampler onto cart. 2. <input type="checkbox"/> REMOVE transit cover. 3. <input type="checkbox"/> ATTACH transit cover to lifting ring on grab sampler. 4. <input type="checkbox"/> ATTACH T-handle operator to grab sampler. 5. <input type="checkbox"/> OPEN CAV-492 using T-handle. 6. <input type="checkbox"/> OPEN CAV-493 using T-handle. 7. <input type="checkbox"/> PROCEED to sample station.
	***** <b>CAUTION: When connecting CASB-5, force should NEVER be used. Damage to quick connects will result from forcing connection.</b> *****
	<b>NOTE: Repeated attempts may be necessary to successfully align CASB-5.</b>
	8. ENGAGE Grab Sampler CASB-5 a. <input type="checkbox"/> One person GUIDE CASB-5 b. <input type="checkbox"/> Another person PUSH CASB-5 UP Ramp AND onto Platform, c. <input type="checkbox"/> HALT CASB-5 several inches from connection points.
	<b>NOTE: WHEN positioned correctly, front of CASB-5 will make metal to metal contact with curved face of sample station.</b>
	d. <input type="checkbox"/> SLOWLY PUSH CASB-5 into Sample Station. e. <input type="checkbox"/> ENGAGE Cart to Station Locking Mechanism. f. <input type="checkbox"/> PUSH Locking Mechanism handle completely down, DRIVING lock bolt through hole in cart.

\_\_\_\_\_  
Initial/Date

4.5      GRAB SAMPLE COLLECTION AT CASB-5 (Cont'd)

ACTIONS	DETAILS
4.5.14      (Continued)	<p data-bbox="873 373 1490 583">***** CAUTION:      When engaging handle,                  force should NEVER be                  used. Damage to quick                  connects will result from                  forcing connection. *****</p> <p data-bbox="873 646 1490 714">NOTE: Due to environmental conditions,          the click may not be heard.</p> <p data-bbox="873 772 1490 1386">g. ____ GENTLY <u>PULL</u> Engagement Handle          forward until a distinct          "click" is heard. This          signifies that quick connect          couplings have engaged. h. ____ ENSURE engagement:       a. ____ <u>UNLOCK</u> Cart from                  station by pulling up                  on cart handle locking                  mechanism.       b. ____ <u>MOVE</u> engagement handle                  back and forth.       c. ____ <u>IF</u> properly connected,                  Cart will move back                  and forth. i. ____ <u>RE-LOCK</u> Cart to Station by          pushing locking mechanism          handle completely down,          driving lock bolt through          hole in cart.</p> <div data-bbox="1295 1396 1490 1453"><p>_____ Initial/Date</p></div>

**4.6      DEMINERALIZED WATER FLUSH**

ACTIONS		DETAILS
4.6.1	CLOSE Sample Isolation Valves	1. <input type="checkbox"/> CLOSE CAV-442 2. <input type="checkbox"/> CLOSE CAV-440
		<div>Initial/Date</div>

**NOTE: Refer to Section 5.0 if a HI-HI alarm occurs at CAT-8.**

4.6.2	ESTABLISH Demineralized Water Flow	1. <input type="checkbox"/> CLOSE CAV-624 2. <input type="checkbox"/> OPEN DWV-337 3. <input type="checkbox"/> OPEN CAV-471 4. <input type="checkbox"/> START CAP-8
		<div>NOTE: Adjusting the CAV-624 valve control knob towards OPEN or CLOSED position will vary flow and pressure accordingly.</div>
		5. <input type="checkbox"/> THROTTLE CAV-624 to obtain flow, between 0.35-0.50 gpm on CA-74-FI.
		<div>Initial/Date</div>

4.6.3	FLUSH system	<div>NOTE: Steps 4.6.3 and 4.6.4 may be performed concurrently.</div>
		<div><input type="checkbox"/> FLUSH system for at least 10 minutes.</div>
		<div>Initial/Date</div>

#### 4.6 DEMINERALIZED WATER FLUSH (Cont'd)

ACTIONS	DETAILS
4.6.4 A.I.M.S. Flushing Pre-Requisites	<ol style="list-style-type: none"> <li>1. ____ VERIFY greater than 50 pounds of liquid nitrogen at PASS liquid nitrogen monitor.</li> <li>2. ____ ENSURE high voltage applied to the PASS detector at value specified in PASS And RANGE AIMS Equipment Logbook.</li> </ol> <p>*****</p> <p><b>CAUTION: Do not reset liquid nitrogen monitor until high voltage bias has been lowered to zero.</b></p> <p>*****</p> <li>3. ____ ENSURE weekly calibration check performed within past seven days per CH-234 as indicated on weekly Count Room QC logsheet in Count Room Task Logbook.</li> <div style="text-align: right;"> _____  Initial/Date </div>

**NOTE: ERASE cannot be performed from a remote terminal**

4.6.5 PERFORM A.I.M.S. Flush	<ol style="list-style-type: none"> <li>1. ____ LOG ON the VAX computer as Username: PASS</li> <li>2. ____ SELECT PASS MENU.</li> <li>3. ____ ENTER NO to DO YOU WANT A SPECTRAL DISPLAY WINDOW? (Default)</li> <li>4. ____ SELECT FLUSH SAMPLE LINES.</li> <li>5. ____ SELECT SUMP DEMIN FLUSH.</li> <li>6. ____ MAXIMIZE MCA Display 1 and toggle through ADC's until RCS CONFIGURATION shown.</li> <li>7. ____ SELECT the ERASE function on MCA Display to re-acquire spectrum.</li> <li>8. ____ When a low stable countrate is indicated MINIMIZE MCA Display 1.</li> <li>9. ____ SELECT RETURN.</li> <li>10. ____ DEPRESS PF4 to QUIT.</li> <li>11. ____ ENTER LO to log off.</li> </ol>
------------------------------	--

#### 4.6 DEMINERALIZED WATER FLUSH (Cont'd)

ACTIONS		DETAILS
4.6.6	SECURE Demineralized Water Flush	<ol style="list-style-type: none"><li>1. <input type="checkbox"/> STOP CAP-8</li><li>2. <input type="checkbox"/> CLOSE DWV-337.</li><li>3. <input type="checkbox"/> CLOSE CAV-471</li><li>4. <input type="checkbox"/> CLOSE CAV-519</li><li>5. <input type="checkbox"/> CLOSE CAV-447</li><li>6. <input type="checkbox"/> CLOSE CAV-623</li><li>7. <input type="checkbox"/> CLOSE CAV-624</li><li>8. <input type="checkbox"/> CLOSE CAV-625</li><li>9. <input type="checkbox"/> CLOSE CAV-626</li></ol> <p>NOTIFY Operations CLOSE the following:</p> <ol style="list-style-type: none"><li>10. <input type="checkbox"/> CAV-436</li><li>11. <input type="checkbox"/> CAV-434.</li></ol> <div style="text-align: right;">_____ Initial/Date</div>

#### 4.7 SYSTEM RESTORATION

4.7.1	SECURE flow	ENSURE CLOSED the following:
		<ol style="list-style-type: none"><li>1. <input type="checkbox"/> CAV-442</li><li>2. <input type="checkbox"/> CAV-440</li><li>3. <input type="checkbox"/> CAV-471</li><li>4. <input type="checkbox"/> CAV-447</li><li>5. <input type="checkbox"/> CAV-448</li><li>6. <input type="checkbox"/> CAV-484</li><li>7. <input type="checkbox"/> CAV-519</li><li>8. <input type="checkbox"/> CAV-623</li><li>9. <input type="checkbox"/> CAV-624</li><li>10. <input type="checkbox"/> CAV-625</li><li>11. <input type="checkbox"/> CAV-626</li><li>12. <input type="checkbox"/> CAV-627</li></ol>

\_\_\_\_\_  
Initial/Date

## 5.0 CONTINGENCIES

### 5.1 CAT-8 HI-HI LEVEL ALARM

ACTIONS	DETAILS
5.1.1 PERFORM lineup	<p>ENSURE the following:</p> <ol style="list-style-type: none"><li>1. <input type="checkbox"/> CAP-10 OFF</li><li>2. <input type="checkbox"/> CAV-623 CLOSED</li><li>3. <input type="checkbox"/> CAV-627 CLOSED</li><li>4. <input type="checkbox"/> CONCURRENTLY PERFORM the following until CAT-8 HI-HI level alarm light clears:<ul style="list-style-type: none"><li>o DEPRESS and hold RESET button on Drain Tank level indicator</li><li>o SELECT CAP-10 to ON</li></ul></li><li>5. <input type="checkbox"/> OPEN CAV-623.</li><li>6. <input type="checkbox"/> SELECT CAP-10 to AUTO</li><li>7. <input type="checkbox"/> RETURN to the step in the procedure which was in progress when the CAT-8 HI-HI level alarm occurred</li></ol>

            
Initial/Date



## 5.2 NOTIFICATIONS AND SHIPMENT

ACTIONS	DETAILS
	NOTE: The Emergency 24 hour access phone number is (804) 522-5833.
	NOTE: Spare grab sample bombs are stored in the Oil Tank warehouse FIMIS # 1400513.
5.2.1 PERFORM notifications	<ul style="list-style-type: none"><li>— NOTIFY the Manager, Nuclear Operations Materials Controls, that a grab sample has been taken and to initiate acquisition process for shielded sample cask.</li><li>— NOTIFY the BWX Technologies Emergency Sample Coordinator when a grab sample has been collected that will require offsite analysis.</li><li>— Required information to be made available:<ul style="list-style-type: none"><li>o Utility and plant name</li><li>o Name and phone of ChemRad Specialist to whom follow-up communication should be addressed.</li><li>o Number and type of samples to be shipped (i.e., liquid, gaseous, or iodine cartridge).</li><li>o Measured radiation levels at the surface and three feet from the shipping container.</li><li>o Estimated shipping time, mode of transportation, carrier, and estimated arrival at BWX Technologies site in Lynchburg, VA.</li></ul></li></ul> <p>Shipping Address: BWX Technologies Lynchburg Technology Center Route 726, Mt. Athos Road Lynchburg, VA. 24506 Attn: Kenneth D. Long (804)-522-5982</p> <ul style="list-style-type: none"><li>— All data accumulated per this procedure is to be summarized on Enclosure 1 and forwarded to the Emergency Coordinator via Chemistry Supervision.</li></ul>

\_\_\_\_\_  
Initial/Date

## TECHNICAL SUPPORT CENTER DATA SHEET

"B" DECAY HEAT TRAIN SAMPLEGamma Isotopic and/or Boron Analysis Results

Boron	_____	ppm	____/____/____ Initial/Date/Time
Boron	_____	ppm	____/____/____ Initial/Date/Time
Boron	_____	ppm	____/____/____ Initial/Date/Time
Boron	_____	ppm	____/____/____ Initial/Date/Time

Total Activity \_\_\_\_\_ uCi/cc

Major Contributing Isotopes

Isotope	Activity	
_____	_____	uCi/cc
_____	_____	uCi/cc
_____	_____	uCi/cc
_____	_____	uCi/cc
_____	_____	uCi/cc
_____	_____	uCi/cc
_____	_____	uCi/cc
_____	_____	uCi/cc
_____	_____	uCi/cc
_____	_____	uCi/cc
_____	_____	uCi/cc

\_\_\_\_/\_\_\_\_/\_\_\_\_  
Initial/Date/Time

## ASSESSMENT OF CORE DAMAGE BASED ON REACTOR COOLANT SAMPLE ('B' DECAY HEAT)

1. This method of confirming core damage assumes that releases from the core are uniformly mixed in the 'B' Decay Heat Train AND there is no dilution from injection.
2. The baseline coolant concentrations in Table 1 are for 0.5 hour after shutdown of a core that has been through at least one refueling cycle.
3. The half-life of the fission products should be considered in analyzing samples.
4. Compare the 'B' Decay Heat PASS sample activities from Enclosure 1 with the baseline coolant concentrations in Table 1. This table overestimates the concentration of the long-lived fission products (Cs and Sr) in a new core.
5. Determine the extent of core damage as indicated by Table 1 (i.e., normal, gas gap, core melt).

TABLE 1

## BASELINE REACTOR COOLANT CONCENTRATION

Nuclide	Normal Concentration (uCi/g)	Concentration After Gap Release (uCi/g)	Concentration After Core Melt (uCi/g)	TMI Concentration + 48 Hours (uCi/g)
I-131	4E-2	2E4	1E5	1.3E4
I-133	1E-1	3E4	2E5	6.5E3
I-135	2E-1	3E4	2E5	No Data
Cs-134	7E-3	2E3	8E3	6.3E1
Cs-137	9E-3	9E2	5E3	2.8E2
Ba-140	No Data	No Data	3E4	No Data
Sr-90	1E-5	No Data	1E4	5.3

6. Report determination to Dose Assessment Coordinator.

\_\_\_\_\_  
Initial/Date

# PROCEDURE DEVELOPMENT AND REVISION RECORD

Procedure: CH0632C

New Rev: 2

PRR#: 17341

Title: POST ACCIDENT SAMPLING AND ANALYSIS OF REACTOR COOLANT WHEN ON THE "B" DECAY HEAT SYSTEM

## MINOR CHANGES

If Minor Changes are included, check the applicable box(es) and provide a list of affected steps.  
The following corrections are incorporated throughout:

- |   |   |
|---|---|
| <input type="checkbox"/> Sentence Structure   | <input type="checkbox"/> Redundant words or phrases                 |
| <input type="checkbox"/> Punctuation  | <input type="checkbox"/> Abbreviations                              |
| <input type="checkbox"/> Capitalization   | <input type="checkbox"/> Obviously incorrect units of measure       |
| <input type="checkbox"/> Spelling   | <input type="checkbox"/> Inadvertently omitted symbols (#, %, etc.) |
| <input type="checkbox"/> Organizational Changes: position titles,<br>department names, or telephone numbers | <input type="checkbox"/> Obvious step numbering discrepancies       |
|   | <input type="checkbox"/> Format                                     |

The following corrections are incorporated in the step(s) indicated: "Throughout" is used in lieu of Step# if a specific change affects a large number of steps.

Correcting equipment nomenclature that does not agree  
with field labels or balance of procedure

Changing information that is obviously incorrect and  
referenced correctly elsewhere

Misplaced decimals that are neither setpoint values nor  
tolerances

Reference to a procedure when an approved procedure  
has taken the place of another procedure

Fixing branching points when it is clear the branching  
steps were originally intended but were overlooked or  
incorrectly stated due to step number changes

Adding clarifying information such as NOTES and CAUTIONS

Adding words to clarify steps, NOTES, or CAUTIONS which  
clearly do not change the methodology or intent of the  
steps

# PROCEDURE DEVELOPMENT AND REVISION RECORD

Procedure: CH0632C

New Rev: 2

PRR#: 17341

Title: POST ACCIDENT SAMPLING AND ANALYSIS OF REACTOR COOLANT WHEN ON THE "B" DECAY HEAT SYSTEM

## MINOR CHANGES

If Minor Changes are included, check the applicable box(es) and provide a list of affected steps.  
The following corrections are incorporated throughout:

- |  |  |
|--|--|
| <input type="checkbox"/> Sentence Structure  | <input type="checkbox"/> Redundant words or phrases                      |
| <input type="checkbox"/> Punctuation   | <input type="checkbox"/> Abbreviations                                   |
| <input type="checkbox"/> Capitalization  | <input type="checkbox"/> Obviously incorrect units of measure            |
| <input type="checkbox"/> Spelling  | <input type="checkbox"/> Inadvertently omitted symbols (#, %, etc.)      |
| <input checked="" type="checkbox"/> Organizational Changes: position titles,<br>department names, or telephone numbers | <input checked="" type="checkbox"/> Obvious step numbering discrepancies |
|  | <input checked="" type="checkbox"/> Format                               |

The following corrections are incorporated in the step(s) indicated: "Throughout" is used in lieu of Step# if a specific change affects a large number of steps.

Correcting equipment nomenclature that does not agree with field labels or balance of procedure

Changing information that is obviously incorrect and referenced correctly elsewhere

Misplaced decimals that are neither setpoint values nor tolerances

Reference to a procedure when an approved procedure has taken the place of another procedure

Fixing branching points when it is clear the branching steps were originally intended but were overlooked or incorrectly stated due to step number changes

5.2

Adding clarifying information such as NOTES and CAUTIONS

Adding words to clarify steps, NOTES, or CAUTIONS which clearly do not change the methodology or intent of the steps

## PROCEDURE DEVELOPMENT AND REVISION RECORD

---

Procedure: CH0632C

New Rev: 2

PRR#: 17341

Title: POST ACCIDENT SAMPLING AND ANALYSIS OF REACTOR COOLANT WHEN ON THE "B" DECAY HEAT SYSTEM

---

### NON-INTENT CHANGES

---

Changes are incorporated for the reasons provided. "Throughout" is used in lieu of Step # if a specific change affects a large number of steps. For new or cancelled procedures the reason is provided.

---

3.2.1, 3.2.2, 4.1.1, 4.1.3,  
4.1.4

Clarify instructions.

---

3.2.4

Correct dose limits to agree with pre-job briefing.

---

Effective Date 10/23/99

EMERGENCY PLAN IMPLEMENTING PROCEDURE

CH-632D

EMERGENCY PLAN IMPLEMENTING PROCEDURE

FLORIDA POWER CORPORATION

CRYSTAL RIVER UNIT 3

POST ACCIDENT SAMPLING AND ANALYSIS OF THE REACTOR BUILDING SUMP

APPROVED BY: Procedure Owner

  
(SIGNATURE ON FILE)

DATE: 10/22/99

PROCEDURE OWNER: Nuclear Chemistry

## TABLE OF CONTENTS

<u>SECTION</u>		<u>PAGE</u>
<u>1.0</u>	<u>PURPOSE</u> .....	1
<u>2.0</u>	<u>REFERENCES</u> .....	1
	2.1 <u>DEVELOPMENTAL REFERENCES</u> .....	1
	2.2 <u>CMIS REFERENCES</u> .....	1
<u>3.0</u>	<u>PERSONNEL INDOCTRINATION</u> .....	2
	3.1 <u>DESCRIPTION</u> .....	2
	3.2 <u>LIMITS &amp; PRECAUTIONS</u> .....	2
<u>4.0</u>	<u>INSTRUCTIONS</u> .....	3
	4.1 <u>SAMPLE TEAM CHECKLIST</u> .....	3
	4.2 <u>SAMPLE LINE-UP</u> .....	6
	4.3 <u>GAMMA ANALYSIS</u> .....	9
	4.4 <u>BORON ANALYSIS</u> .....	12
	4.5 <u>GRAB SAMPLE COLLECTION AT CASB-5</u> .....	13
	4.6 <u>DEMINERALIZED WATER FLUSH</u> .....	21
	4.7 <u>SYSTEM RESTORATION</u> .....	24
<u>5.0</u>	<u>CONTINGENCIES</u> .....	25
	5.1 <u>SUSPECTED SAMPLE LINE BLOCKAGE</u> .....	25
	5.2 <u>HIGH RADIATION LEVELS IN SAMPLE LINES</u> .....	25
	5.3 <u>CAT-8 HI-HI LEVEL ALARM</u> .....	25
	5.4 <u>NOTIFICATIONS AND SHIPMENT</u> .....	26
 <u>ENCLOSURES</u>		
1	Technical Support Center Data Sheet .....	27
2	Assessment of Core Damage Based on Reactor Building Sump Sample ....	28



## **1.0 PURPOSE**

This procedure provides instructions for sampling the Reactor Building Sump under accident conditions for Gamma Isotopic and Boron analyses using the Post Accident Sampling System.

## **2.0 REFERENCES**

### **2.1 DEVELOPMENTAL REFERENCES**

- 2.1.1 APEX Technologies Post Accident Sample System Modules Manual, FPC Manual #2034
- 2.1.2 EOP-14, Enclosure 2, PPO Post Event Actions
- 2.1.3 FD-302-700, Post Accident Sampling System
- 2.1.4 Nuclear Regulatory Commission RTM-96, Response Technical Manual
- 2.1.5 NUREG 0737, Post-TMI Requirements
- 2.1.6 PASS Users Manual Volumes A through C, Crystal River Installation
- 2.1.7 Radiological Emergency Response Plan
- 2.1.8 Regulatory Guide 1.97, Instrumentation For Light-Water Cooled Nuclear Power Plants To Assess Plant And Environs Conditions During And Following An Accident
- 2.1.9 RSP-600, ALARA Program
- 2.1.10 6059-S-002, APEX Technologies PASS Process Flow Diagrams

### **2.2 CMIS REFERENCES**

DPDP-5A BREAKER 27, DPDP-5B BREAKER 8, CACP-1, CAV-126, CAV-1, CAV-3, CAV-431, CAV-432, CAV-429, CAV-430, CAV-626, CAV-627, CAV-484, CAV-439, CAV-636, CAV-519, CAV-447, CAV-437, CAV-448, CAV-623, CAV-625, CAP-10, CAP-14, CAV-436, CAV-434, CAV-500, CAV-624, CA-74-FI, CA-56-CI, CASB-5, AHF-55, CAV-492, CAV-493, CAV-445, CAV-446, CAV-471, DWV-337, CAP-8, CAT-8, CAV-470, CAV-433, CAV-435

### 3.0 PERSONNEL INDOCTRINATION

#### 3.1 DESCRIPTION

NOTE: The PASS is powered by the B ES Bus through ACDP-59.

The Post Accident Sampling System (PASS) is an on-line system designed to sample and evaluate various liquid and gaseous sample streams during an accident, including the Reactor Building Sump. The liquid PASS Automated Isotopic And Chemical Measurement System (AIMS) consists of the subassembly used to perform Gamma Isotopic and Boron analyses of the Reactor Building Sump.

#### 3.2 LIMITS & PRECAUTIONS

3.2.1 Performance of all or part of this procedure will be done by direction of the Emergency Coordinator or designee.

3.2.2 Entries into the controlled access areas must have Radiation Monitoring Team preplanning, concurrence, and coverage as outlined in EM-104, Operation of the Operational Support Center. Controlled access areas will be defined by the Radiation Monitoring Team personnel.

3.2.3 During post-accident sampling, extremely high radiation exposure levels could be experienced. The ability to perform this procedure and stay within exposure limits will require ALARA pre-planning.

3.2.4 Return to the Lab if the dose rate at places requiring work is determined by the Health Physics Technician to be in excess of the limits specified in the pre-job briefing.

3.2.5 All sampling actions are performed on the Main Control Board by Operations, or in the Count Room either on the VAX Computer or from PASS CACP-1 and Nuclear Data Mimic Panels unless otherwise noted.

3.2.6 Section 4.1 must be completed prior to any sample team re-entry.

3.2.7 Sections 4.3, Gamma Isotopic Analysis, and Section 4.4, Boron Analysis, can be performed simultaneously.

#### 4.0 INSTRUCTIONS

NOTE: Section 4.1 must be completed prior to any sample team re-entries.

#### 4.1 SAMPLE TEAM CHECKLIST

ACTIONS	DETAILS												
4.1.1 ASSEMBLE Sample Team and REVIEW applicable procedures.	<p>1. REVIEW the following procedures:</p> <p>_____ CH-632C, Post Accident Sampling and Analysis of the Reactor Coolant System When on the "B" Decay Heat Train</p> <p>_____ EM-104, Operation Of The Operational Support Center</p> <p>2. LIST personnel performing entry and their dose margins:</p> <table><thead><tr><th><u>Name</u></th><th><u>Dose Margin</u></th></tr></thead><tbody><tr><td>1. _____</td><td></td></tr><tr><td>2. _____</td><td></td></tr><tr><td>3. _____</td><td></td></tr><tr><td>4. _____</td><td></td></tr><tr><td>5. _____</td><td></td></tr></tbody></table> <p style="text-align: right;">_____ Initial/Date</p>	<u>Name</u>	<u>Dose Margin</u>	1. _____		2. _____		3. _____		4. _____		5. _____	
<u>Name</u>	<u>Dose Margin</u>												
1. _____													
2. _____													
3. _____													
4. _____													
5. _____													
4.1.2 DETERMINE Reactor Building Sump sample lineup and analyses to perform	<p>1. SELECT sample lineup to perform</p> <p>a. _____ Primary Sample Path</p> <p>b. _____ Alternate Sample Path</p> <p>2. LIST analyses to perform:</p> <p>_____</p> <p>_____</p> <p>_____</p> <p>_____</p> <p style="text-align: right;">_____ Initial/Date</p>												

4.1 SAMPLE TEAM CHECKLIST (Cont'd)

ACTIONS		DETAILS
4.1.3	DISCUSS supplies for obtaining a sample utilizing CASB-2.	<p><u>IF</u> obtaining CASB-2 grab sample, <u>THEN</u> ENSURE the following:</p> <ul style="list-style-type: none"><li>— Allen wrench, or equivalent, as determined by Chemistry supervision, for removing T-Handle from grab sampler and attaching to new grab sampler</li><li>— Knife, or equivalent, as determined by Chemistry supervision, to cut transit cover strap from lifting eye</li><li>— New tie-wrap, or equivalent as determined by Chemistry supervision, to attach transit cover to new grab sampler lifting eye</li></ul>

\_\_\_\_\_  
Initial/Date

4.1 SAMPLE TEAM CHECKLIST (Cont'd)

ACTIONS	DETAILS
---------	---------

NOTE: The following breakers are normally in the locked open (Off) position by Operations due to not having automatic ES closure functions

4.1.4 ALIGN electrical power supplies

\_\_\_ VERIFY Operations has performed EOP-14, Enclosure 2, PPO Post Event Actions.

YES \_\_\_ NO \_\_\_

IF EOP-14, Enclosure 2, was not performed,

THEN NOTIFY Operations ENSURE CLOSED the following breakers:

1. \_\_\_ DPDP-5A, Brk. No. 27

2. \_\_\_ DPDP-5B, Brk. No. 8

\_\_\_\_\_  
Initial/Date

## 4.2 SAMPLE LINE-UP

ACTIONS	DETAILS
4.2.1 PERFORM valve lineup to sample RB Sump	<p data-bbox="873 338 1438 369">ENSURE CLOSED the following valves:</p> <ol data-bbox="873 373 1133 743" style="list-style-type: none"><li>1. <input type="checkbox"/> CAV-126</li><li>2. <input type="checkbox"/> CAV-1</li><li>3. <input type="checkbox"/> CAV-3</li><li>4. <input type="checkbox"/> CAV-431</li><li>5. <input type="checkbox"/> CAV-432</li><li>6. <input type="checkbox"/> CAV-429</li><li>7. <input type="checkbox"/> CAV-430</li><li>8. <input type="checkbox"/> CAV-626</li><li>9. <input type="checkbox"/> CAV-627</li><li>10. <input type="checkbox"/> CAV-484</li><li>11. <input type="checkbox"/> CAV-439</li><li>12. <input type="checkbox"/> CAV-636</li></ol> <p data-bbox="873 779 1287 810">ENSURE OPEN the following:</p> <ol data-bbox="873 814 1130 932" style="list-style-type: none"><li>13. <input type="checkbox"/> CAV-519</li><li>14. <input type="checkbox"/> CAV-447</li><li>15. <input type="checkbox"/> CAV-437</li><li>16. <input type="checkbox"/> CAV-448</li></ol> <p data-bbox="873 968 1203 999">ENSURE the following:</p> <ol data-bbox="873 1003 1430 1205" style="list-style-type: none"><li>17. <input type="checkbox"/> CAV-623 to SAMPLE</li><li>18. <input type="checkbox"/> CAV-625 to SAMPLE</li><li>19. <input type="checkbox"/> CAV-626 to DRAIN TANK</li><li>20. <input type="checkbox"/> CAP-10 to AUTO</li><li>21. <input type="checkbox"/> CAP-10 Flow Control Switch to FULL CLOCKWISE</li><li>22. <input type="checkbox"/> CAP-14 to ON</li></ol>

\_\_\_\_\_  
Initial/Date

#### 4.2 SAMPLE LINE-UP (Cont'd)

ACTIONS	DETAILS
4.2.2 OPEN Containment Isolation Valves	<p>___ IF using the Primary Sample Path THEN NOTIFY Operations OPEN the following:</p> <ol style="list-style-type: none"><li>1. ___ CAV-436</li><li>2. ___ CAV-434</li></ol> <p>NOTE: CAV-500 is in the Intermediate Building.</p> <p>___ IF using the Alternate Sample Path, THEN</p> <ol style="list-style-type: none"><li>1. ___ OPEN CAV-500</li><li>2. ___ OPEN CAV-439</li><li>3. ___ CLOSE CAV-448</li></ol> <p>_____ Initial/Date</p>

4.2.3 INITIATE demineralized water flow to PRIME CAP-8	<p>OPEN the following:</p> <ol style="list-style-type: none"><li>1. ___ DWV-337</li><li>2. ___ CAV-471</li><li>3. ___ START CAP-8</li><li>4. ___ THROTTLE CAV-624 to obtain flow rate between 0.35-0.50 gpm on CA-74-FI</li></ol>
--	---

\_\_\_\_\_  
Initial/Date

## 4.2 SAMPLE LINE-UP (Cont'd)

ACTIONS	DETAILS
4.2.4 OPEN Containment Isolation Valves	<p>___ IF using the Primary Sample Path, THEN NOTIFY Operations OPEN the following:</p> <p>1. ___ CAV-433</p> <p>2. ___ CAV-435</p> <p>___ IF using the Alternate Sample Path, THEN NOTIFY Operations OPEN the following:</p> <p>1. ___ CAV-434</p> <p>2. ___ CAV-436</p> <p style="text-align: right;">_____/_____ Initial/Date</p>
4.2.5 SECURE the demineralized priming water	<p>WHEN sample flow has stabilized on CA-74-FI (approximately 5 minutes), THEN CLOSE:</p> <p>___ CAV-471</p> <p>___ DWV-337</p> <p style="text-align: right;">_____/_____ Initial/Date</p>
4.2.6 ADJUST sample flow for Gamma Isotopic, Boron, or Grab Sample	<p>___ THROTTLE CAV-624 to obtain flow rate between 0.35-0.50 gpm on CA-74-FI</p> <p style="text-align: right;">_____/_____ Initial/Date</p>

**NOTE:** Refer to Section 5.0 if a HI-HI alarm occurs at CAT-8.



### 4.3 GAMMA ANALYSIS

ACTIONS		DETAILS
4.3.1	FLUSH RB Sump Sample	<p>1. — ENSURE Section 4.2 SAMPLE LINE-UP performed</p> <p>NOTE: While flushing you may continue with Step 4.3.2 and 4.3.3.</p> <p>2. — FLUSH for at least 35 minutes</p>
4.3.2	PERFORM pre-analysis PASS detector checks	<p>1. — VERIFY greater than 50 pounds of liquid nitrogen at PASS liquid nitrogen monitor</p> <p>*****</p> <p><b>CAUTION: Do not reset liquid nitrogen monitor until high voltage bias has been lowered to zero.</b></p> <p>*****</p> <p>2. — ENSURE high voltage applied to PASS detector at value specified in PASS AND RANGE equipment logbook</p> <p>3. — ENSURE a weekly calibration check has been performed within the past 7 days as indicated on weekly countroom QC log sheet in Count Room Task logbook</p>

\_\_\_\_\_  
Initial/Date

#### 4.3 GAMMA ANALYSIS (Cont'd)

ACTIONS	DETAILS
4.3.3 PERFORM Gamma Isotopic Analysis	<ol style="list-style-type: none"> <li>1. <input type="checkbox"/> LOG ON VAX computer as Username: PASS</li> <li>2. <input type="checkbox"/> SELECT PASS MENU</li> <li>3. <input type="checkbox"/> ENTER NO to prompt DO YOU WANT A SPECTRAL DISPLAY WINDOW?(Default)</li> <li>4. <input type="checkbox"/> SELECT LIQUID SAMPLING</li> <li>5. <input type="checkbox"/> SELECT Reactor Building Sump Sample</li> </ol>

**NOTE: Ensure sample flush time is completed prior to continuing.**

6. EITHER:
  - a. ☐ ENTER Q to quit MUX display and continue with procedure,
  - b. ☐ OR RETURN to update MUX values
7. ☐ ENTER NO to abort sample (Default value)
8. ☐ UPDATE sample parameters
9. ☐ SELECT ACCEPT
10. ☐ SELECT QUIT key to exit
11. ☐ ENTER LO to log off VAX computer
12. ☐ ATTACH gamma scan to this procedure
13. ☐ REPORT results to OSC Chemistry Coordinator or his designee

Gamma Scan ID number: \_\_\_\_\_

\_\_\_\_\_/\_\_\_\_\_/\_\_\_\_\_  
Initial/ Date / Time

Gamma Scan ID number: \_\_\_\_\_

\_\_\_\_\_/\_\_\_\_\_/\_\_\_\_\_  
Initial/ Date / Time

Gamma Scan ID number: \_\_\_\_\_

\_\_\_\_\_/\_\_\_\_\_/\_\_\_\_\_  
Initial/ Date / Time

Continued on Next Page

4.3      GAMMA ANALYSIS (Cont'd)

ACTIONS		DETAILS
4.3.3	Cont'd	14. ____ <u>IF</u> Additional Gamma Isotopic Analysis are required, <u>THEN</u> REPEAT Steps 1 through 13
		15. ____ <u>IF</u> all analyses are complete, <u>THEN</u> PERFORM Demineralized Water Flush per Section 4.6
		_____ Initial/Date

4.3.4	PERFORM Core Damage Assessment	1. ____ OSC Chemistry Coordinator or designee PERFORM Core damage assessment per Enclosure 2
		_____ Initial/Date

#### 4.4 BORON ANALYSIS

ACTIONS		DETAILS
4.4.1	PERFORM Boron analysis	1. <input type="checkbox"/> ENSURE Section 4.2 SAMPLE LINE-UP performed 2. <input type="checkbox"/> FLUSH sample through the Boronometer for at least one hour  <div style="text-align: right;">_____ Flush Start Time</div> <p><b>NOTE: The Boron concentration of the sample will be displayed at the readout (CA-56-CI) located on PASS Analyzer Panel (CACP-1) in courtroom.</b></p> Boron _____ PPM _____
		3. <input type="checkbox"/> NOTIFY OSC Chemistry Coordinator or designee of results  <div style="text-align: right;">_____/_____/_____ Initial/ Date / Time</div> 4. <input type="checkbox"/> <u>IF</u> all analyses are complete, <u>THEN</u> PERFORM Demineralized Water Flush per Section 4.6  <div style="text-align: right;">_____ Initial/Date</div>

#### 4.5 GRAB SAMPLE COLLECTION AT CASB-5

NOTE: Spare grab sample bombs are stored in the Oil Tank warehouse FIMIS # 1400513.

ACTIONS		DETAILS
4.5.1	PREPARE CASB-5 (Grab Sampler) Sample Station for Sample collection	NOTE: CASB-5 exhaust fan (AHF-55) switch is located to the right of the Intermediate Building door (across from RM-A7)  ___ START CASB-5 exhaust fan  <div style="text-align: right;">_____ Initial/Date</div>
4.5.2	PERFORM Valve Alignment	1. ___ ENSURE Section 4.2 SAMPLE LINE-UP performed 2. ___ OPEN CAV-445 3. ___ OPEN CAV-446 4. ___ CLOSE CAV-447 5. ___ FLUSH for at least 15 minutes  <div style="text-align: right;">_____ Initial/Date</div>
4.5.3	ISOLATE Grab sample	NOTE: The T-handle operator for CAV-492 and CAV-493 is attached to CASB-5.  1. ___ CLOSE CAV-492 using T-handle 2. ___ CLOSE CAV-493 using T-handle  <div style="text-align: right;">_____ Initial/Date</div>
4.5.4	ISOLATE CASB-5	1. ___ OPEN CAV-447 2. ___ CLOSE CAV-445 3. ___ CLOSE CAV-446 4. ___ STOP CAP-8  <div style="text-align: right;">_____ Initial/Date</div>

#### 4.5 GRAB SAMPLE COLLECTION AT CASB-5 (Cont'd)

ACTIONS	DETAILS
4.5.5 CLOSE Sample Isolation Valves	<p>___ IF using the Primary Sample Path  <u>THEN</u> NOTIFY Operations CLOSE the following:            1. ___ CAV-433            2. ___ CAV-435</p> <p>___ IF using the Alternate Sample Path,  <u>THEN</u> NOTIFY Operations CLOSE the following:            1. ___ CAV-434            2. ___ CAV-436</p> <p><b>NOTE: CAV-500 is in the Intermediate Building.</b></p> <p>___ CLOSE CAV-500</p> <p style="text-align: right;">_____/_____            Initial/Date</p>

**NOTE: Refer to Section 5.0 if a HI-HI alarm occurs at CAT-8.**

4.5.6 ESTABLISH Demineralized Water Flush	<p>1. ___ CLOSE CAV-624            2. ___ OPEN DWV-337            3. ___ OPEN CAV-471            4. ___ START CAP-8            5. ___ THROTTLE CAV-624 to obtain a flow rate between 0.35-0.50 gpm on CA-74-FI</p> <p><b>NOTE: While flushing you may continue with Step 4.5.7 and Step 4.5.8.</b></p> <p>6. ___ FLUSH for at least 10 minutes</p> <p style="text-align: right;">_____/_____            Initial/Date</p>
---	--

#### 4.5 GRAB SAMPLE COLLECTION AT CASB-5 (Cont'd)

	ACTIONS	DETAILS
4.5.7	A.I.M.S. Flushing Pre-Requisites	<ol style="list-style-type: none"> <li>1. <input type="checkbox"/> VERIFY greater than 50 pounds of liquid nitrogen at PASS liquid nitrogen monitor</li> <li>2. <input type="checkbox"/> ENSURE high voltage applied to the PASS detector at value specified in PASS and RANGE AIMS Equipment Logbook</li> </ol> <p>*****  <b>CAUTION: Do not reset liquid nitrogen monitor until high voltage bias has been lowered to zero.</b>          *****</p> <ol style="list-style-type: none"> <li>3. <input type="checkbox"/> ENSURE weekly calibration check performed within past seven days per CH-234 as indicated on weekly Count Room QC log sheet in Count Room Task Logbook</li> </ol> <p style="text-align: right;">_____ Initial/Date</p>
4.5.8	PERFORM A.I.M.S. Flush	<ol style="list-style-type: none"> <li>1. <input type="checkbox"/> LOG ON the VAX computer as Username: PASS</li> <li>2. <input type="checkbox"/> SELECT PASS MENU</li> <li>3. <input type="checkbox"/> ENTER NO to DO YOU WANT A SPECTRAL DISPLAY WINDOW? (Default)</li> <li>4. <input type="checkbox"/> SELECT FLUSH SAMPLE LINES</li> <li>5. <input type="checkbox"/> SELECT SUMP DEMIN FLUSH</li> <li>6. <input type="checkbox"/> MAXIMIZE MCA Display 1 and toggle through ADC's until RCS CONFIGURATION shown</li> <li>7. <input type="checkbox"/> SELECT the ERASE function on MCA Display to re-acquire spectrum</li> <li>8. <input type="checkbox"/> When a low stable count rate is indicated MINIMIZE MCA Display 1</li> <li>9. <input type="checkbox"/> SELECT RETURN</li> <li>10. <input type="checkbox"/> DEPRESS PF4 to QUIT</li> <li>11. <input type="checkbox"/> ENTER LO to log off</li> </ol> <p style="text-align: right;">_____ Initial/Date</p>

4.5 GRAB SAMPLE COLLECTION AT CASB-5 (Cont'd)

ACTIONS		DETAILS	
4.5.9	FLUSH CASB-5	1. <input type="checkbox"/> OPEN CAV-445	<div>Initial/Date</div>
		2. <input type="checkbox"/> OPEN CAV-446	
		3. <input type="checkbox"/> CLOSE CAV-447	
		4. <input type="checkbox"/> FLUSH for at least 5 minutes	
4.5.10	ISOLATE CASB-5	1. <input type="checkbox"/> OPEN CAV-447	<div>Initial/Date</div>
		2. <input type="checkbox"/> CLOSE CAV-445	
		3. <input type="checkbox"/> CLOSE CAV-446	
4.5.11	SECURE Demineralized water flush after grab sampling	1. <input type="checkbox"/> STOP CAP-8	<div>Initial/Date</div>
		2. <input type="checkbox"/> CLOSE DWV-337	
		3. <input type="checkbox"/> CLOSE CAV-471	
		CLOSE the following:	
		4. <input type="checkbox"/> CAV-519	
		5. <input type="checkbox"/> CAV-447	
		6. <input type="checkbox"/> CAV-623	
		7. <input type="checkbox"/> CAV-624	
		8. <input type="checkbox"/> CAV-625	
		9. <input type="checkbox"/> CAV-626	



4.5 GRAB SAMPLE COLLECTION AT CASB-5 (Cont'd)

ACTIONS	DETAILS
4.5.12 CLOSE Containment Isolation Valves	<p>NOTIFY Operations CLOSE the following:</p> <ol style="list-style-type: none"> <li>1.   ___ CAV-436</li> <li>2.   ___ CAV-434</li> </ol> <p><b>NOTE: CAV-500 is in the Intermediate Building</b></p> <ol style="list-style-type: none"> <li>3.   ___ <u>IF</u> Alternate Sample Path was used,           <u>THEN</u> CLOSE CAV-439</li> <li>4.   ENSURE CLOSED:               <ul style="list-style-type: none"> <li>      ___ CAV-448</li> <li>      ___ CAV-500</li> </ul> </li> </ol> <div style="text-align: right; margin-top: 20px;"> <u>                  /</u>  Initial/Date </div>

#### 4.5 GRAB SAMPLE COLLECTION AT CASB-5 (Cont'd)

ACTIONS		DETAILS
4.5.13	REMOVE CASB-5 (GRAB SAMPLER)	<ol style="list-style-type: none"> <li>1. — OBTAIN 3/4" wrench from Primary Chemistry lab key locker</li> <li>2. — PROCEED to CASB-5 location, 95' elevation Auxiliary building</li> <li>3. — REMOVE the Grab Sampler ramp from storage location</li> <li>4. — INSTALL the Grab Sampler ramp in front of sample station</li> <li>5. — DISCONNECT CASB-5 from the sample station: <ol style="list-style-type: none"> <li>a. — SQUEEZE disengagement lever</li> <li>b. — PUSH the engagement handle to its rearmost position</li> <li>c. — PULL UP on cart handle locking mechanism to release the cart</li> <li>d. — REMOVE CASB-5 cart from sample station</li> </ol> </li> <li>6. — INSTALL the transit cover over the quick-connects</li> <li>7. — REMOVE the cart and move to the Turbine Building crane well</li> <li>8. — UNBOLT CASB-5 from the cart using 3/4" wrench</li> <li>9. — REMOVE T-handle operator</li> <li>10. — GO TO Section 5.0 to prepare CASB-5 for shipment off-site</li> </ol>

\_\_\_\_\_  
Initial/Date

#### 4.5 GRAB SAMPLE COLLECTION AT CASB-5 (Cont'd)

ACTIONS	DETAILS
4.5.14    INSTALL new Grab Sampler	<ol style="list-style-type: none"> <li>1.    <input type="checkbox"/>    BOLT new Grab Sampler onto cart</li> <li>2.    <input type="checkbox"/>    REMOVE transit cover</li> <li>3.    <input type="checkbox"/>    ATTACH transit cover to lifting ring on grab sampler</li> <li>4.    <input type="checkbox"/>    ATTACH T-handle operator to grab sampler</li> <li>5.    <input type="checkbox"/>    OPEN CAV-492 using T-handle</li> <li>6.    <input type="checkbox"/>    OPEN CAV-493 using T-handle</li> <li>7.    <input type="checkbox"/>    PROCEED to sample station</li> </ol>
	<p>*****</p> <p><b>CAUTION: When connecting CASB-5, force should NEVER be used. Damage to quick connects will result from forcing connection.</b></p> <p>*****</p>
	<p><b>NOTE: Repeated attempts may be necessary to successfully align CASB-5.</b></p>
	<ol style="list-style-type: none"> <li>8. <input type="checkbox"/>    ENGAGE Grab Sampler CASB-5 <ol style="list-style-type: none"> <li>a. <input type="checkbox"/> One person GUIDE CASB-5</li> <li>b. <input type="checkbox"/> Another person PUSH CASB-5 UP Ramp AND onto Platform,</li> <li>c. <input type="checkbox"/> HALT CASB-5 several inches from connection points</li> </ol> </li> </ol>
	<p><b>NOTE: WHEN positioned correctly, front of CASB-5 will make metal to metal contact with curved face of sample station.</b></p>
	<ol style="list-style-type: none"> <li>d. <input type="checkbox"/> SLOWLY PUSH CASB-5 into Sample Station</li> <li>e. <input type="checkbox"/> ENGAGE Cart to Station Locking Mechanism</li> <li>f. <input type="checkbox"/> PUSH Locking Mechanism handle completely down, DRIVING lock bolt through hole in cart</li> </ol>

\_\_\_\_\_  
Initial/Date

(Continued on next page)

#### 4.5 GRAB SAMPLE COLLECTION AT CASB-5 (Cont'd)

ACTIONS	DETAILS
4.5.14 INSTALL new Grab Sampler (Cont'd)	<p>*****</p> <p>CAUTION: When engaging handle, force should NEVER be used. Damage to quick connects will result from forcing connection.</p> <p>*****</p> <p>NOTE: Due to environmental conditions, the click may not be heard.</p> <p>g. <u>GENTLY PULL</u> Engagement Handle forward until a distinct "click" is heard. This signifies that quick connect couplings have engaged</p> <p>h. <u>ENSURE</u> engagement:</p> <ul style="list-style-type: none"> <li>— <u>UNLOCK</u> Cart from station by pulling up on cart handle locking mechanism</li> <li>— <u>MOVE</u> engagement handle back and forth</li> <li>— <u>IF</u> properly connected, Cart will move back and forth</li> </ul> <p>i. <u>RE-LOCK</u> Cart to Station by pushing locking mechanism handle completely down, driving lock bolt through hole in cart</p> <p style="text-align: right;">_____ Initial/Date</p>

#### 4.6 DEMINERALIZED WATER FLUSH

ACTIONS		DETAILS
4.6.1	CLOSE Sample Isolation Valves	<p>— IF using the Primary Sample Path THEN NOTIFY Operations CLOSE the following: 1. — CAV-433 2. — CAV-435</p> <p>— IF using the Alternate Sample Path, THEN NOTIFY Operations CLOSE the following: 1. — CAV-434 2. — CAV-436</p> <p><b>NOTE: CAV-500 is in the Intermediate Building.</b></p> <p>— CLOSE CAV-500</p> <p style="text-align: right;">_____ Initial/Date</p>

**NOTE: Refer to Section 5.0 if a HI-HI alarm occurs at CAT-8.**

4.6.2	ESTABLISH Demineralized Water Flow	<p>1. — CLOSE CAV-624 2. — OPEN DWV-337 3. — OPEN CAV-471 4. — START CAP-8 5. — THROTTLE CAV-624 to obtain flow, between 0.35-0.50 gpm on CA-74-FI</p> <p><b>NOTE: While flushing you may continue with Steps 4.6.3 and 4.6.4.</b></p> <p>— FLUSH system for at least 10 minutes</p> <p style="text-align: right;">_____ Initial/Date</p>
-------	------------------------------------	---

#### 4.6 DEMINERALIZED WATER FLUSH (Cont'd)

ACTIONS		DETAILS
4.6.3	A.I.M.S. Flushing Pre-Requisites	<ol style="list-style-type: none"> <li>1. — VERIFY greater than 50 pounds of liquid nitrogen at PASS liquid nitrogen monitor</li> <li>2. — ENSURE high voltage applied to the PASS detector at value specified in PASS AND RANGE AIMS Equipment Logbook</li> </ol> <p>*****  <b>CAUTION: Do not reset liquid nitrogen monitor until high voltage bias has been lowered to zero.</b>  *****</p> <ol style="list-style-type: none"> <li>3. — ENSURE weekly calibration check performed within past seven days per CH-234 as indicated on weekly Count Room QC log sheet in Count Room Task Logbook</li> </ol>
		_____ Initial/Date

**NOTE: ERASE cannot be performed from a remote terminal**

4.6.4	PERFORM A.I.M.S. Flush	<ol style="list-style-type: none"> <li>1. — LOG ON the VAX computer as Username: PASS</li> <li>2. — SELECT PASS MENU</li> <li>3. — ENTER NO to DO YOU WANT A SPECTRAL DISPLAY WINDOW? (Default)</li> <li>4. — SELECT FLUSH SAMPLE LINES</li> <li>5. — SELECT SUMP DEMIN FLUSH</li> <li>6. — MAXIMIZE MCA Display 1 and toggle through ADC's until RCS CONFIGURATION shown</li> <li>7. — SELECT the ERASE function on MCA Display to re-acquire spectrum</li> <li>8. — When a low stable count rate is indicated MINIMIZE MCA Display 1</li> <li>9. — SELECT RETURN</li> <li>10. — DEPRESS PF4 to QUIT</li> <li>11. — ENTER LO to log off</li> </ol>
-------	------------------------	---

\_\_\_\_\_  
Initial/Date

4.6 DEMINERALIZED WATER FLUSH (Cont'd)

ACTIONS		DETAILS
4.6.5	SECURE Demineralized Water Flush	1. <input type="checkbox"/> STOP CAP-8 2. <input type="checkbox"/> CLOSE DWV-337 3. <input type="checkbox"/> CLOSE CAV-471  ENSURE CLOSED the following: 4. <input type="checkbox"/> CAV-519 5. <input type="checkbox"/> CAV-447 6. <input type="checkbox"/> CAV-623 7. <input type="checkbox"/> CAV-624 8. <input type="checkbox"/> CAV-625 9. <input type="checkbox"/> CAV-626
		_____ Initial/Date

4.6.6	CLOSE Containment Isolation Valves	NOTIFY Operations CLOSE the following:  1. <input type="checkbox"/> CAV-436 2. <input type="checkbox"/> CAV-434  <b>NOTE: CAV-500 is in the Intermediate Building</b>  3. <input type="checkbox"/> <u>IF</u> Alternate Sample Path was used, <u>THEN</u> CLOSE CAV-439  4. ENSURE CLOSED: <input type="checkbox"/> CAV-448 <input type="checkbox"/> CAV-500
		_____ Initial/Date

#### 4.7 SYSTEM RESTORATION

ACTIONS		DETAILS
4.7.1	SECURE flow	ENSURE CLOSED the following:  1.   ___ CAV-471 2.   ___ CAV-447 3.   ___ CAV-448 4.   ___ CAV-484 5.   ___ CAV-623 6.   ___ CAV-624 7.   ___ CAV-625 8.   ___ CAV-626 9.   ___ CAV-627 10.  ___ CAV-519 11.  ___ CAV-500  <div>_____ Initial/Date</div>



## 5.0 CONTINGENCIES

### 5.1 SUSPECTED SAMPLE LINE BLOCKAGE

<u>ACTIONS</u>		<u>DETAILS</u>
5.1.1	FLUSH sample line	<u>IF</u> sample flow can not be initiated due to suspected sample line blockage, <u>THEN</u> PERFORM demineralized water flush per Section 4.6. <div style="text-align: right;">_____ Initial/Date</div>

### 5.2 HIGH RADIATION LEVELS IN SAMPLE LINES

5.2.1	FLUSH sample line	<u>IF</u> undesired radiation levels are reached in sample lines, <u>THEN</u> PERFORM demineralized water flush per Section 4.6. <div style="text-align: right;">_____ Initial/Date</div>
-------	-------------------	---

### 5.3 CAT-8 HI-HI LEVEL ALARM

5.3.1	PERFORM lineup	ENSURE the following: 1. ____ CAP-10 OFF 2. ____ CAV-623 CLOSED 3. ____ CAV-627 CLOSED 4. ____ CONCURRENTLY PERFORM the HI-HI following until CAT-8 HI level alarm light clears: o DEPRESS and hold RESET button on Drain Tank level indicator o SELECT CAP-10 to ON 5. ____ OPEN CAV-623 6. ____ SELECT CAP-10 to AUTO 7. ____ RETURN to the step in the procedure which was in progress when the CAT-8 HI-HI level alarm occurred <div style="text-align: right;">_____ Initial/Date</div>
-------	----------------	--

## 5.0 CONTINGENCIES (Cont'd)

### 5.4 NOTIFICATIONS AND SHIPMENT

ACTIONS	DETAILS
---------	---------

NOTE: The Emergency 24 hour access phone number is (800)-335-9264.

NOTE: Spare grab sample bombs are stored in the Oil Tank warehouse FIMIS # 1400513.

#### 5.4.1 PERFORM notifications

— NOTIFY the Manager, Nuclear Operations Materials Controls, that a grab sample has been taken and to initiate acquisition process for shielded sample cask

— NOTIFY the BWX Technologies Emergency Sample Coordinator when a grab sample has been collected that will require offsite analysis

— Required information to be made available:

- o Utility and plant name
- o Name and phone of ChemRad Specialist to whom follow-up communication should be addressed
- o Number and type of samples to be shipped (i.e., liquid, gaseous, or iodine cartridge)
- o Measured radiation levels at the surface and three feet from the shipping container
- o Estimated shipping time, mode of transportation, carrier, and estimated arrival at BWX Technologies site in Lynchburg, VA

#### Shipping Address:

BWX Technologies  
Lynchburg Technology Center  
Route 726, Mt. Athos Road  
Lynchburg, VA 24506  
Attn: Kenneth D. Long  
(804) 522-5982

— All data accumulated per this procedure is to be summarized on Enclosure 1 and forwarded to the Emergency Coordinator via Chemistry Supervision

\_\_\_\_\_  
Initial/Date

## TECHNICAL SUPPORT CENTER DATA SHEET

REACTOR BUILDING SUMPGamma Isotopic and/or Boron Analysis Results

Boron \_\_\_\_\_ ppm \_\_\_\_\_/\_\_\_\_\_/\_\_\_\_\_  
Initial/ Date /Time

Boron \_\_\_\_\_ ppm \_\_\_\_\_/\_\_\_\_\_/\_\_\_\_\_  
Initial/ Date /Time

Boron \_\_\_\_\_ ppm \_\_\_\_\_/\_\_\_\_\_/\_\_\_\_\_  
Initial/ Date /Time

Boron \_\_\_\_\_ ppm \_\_\_\_\_/\_\_\_\_\_/\_\_\_\_\_  
Initial/ Date /Time

Total Activity \_\_\_\_\_ uCi/cc

Major Contributing Isotopes

_____	_____	uCi/cc
_____	_____	uCi/cc
_____	_____	uCi/cc
_____	_____	uCi/cc
_____	_____	uCi/cc
_____	_____	uCi/cc
_____	_____	uCi/cc
_____	_____	uCi/cc
_____	_____	uCi/cc
_____	_____	uCi/cc
_____	_____	uCi/cc

\_\_\_\_\_/\_\_\_\_\_/\_\_\_\_\_  
Initial/ Date /Time

## ASSESSMENT OF CORE DAMAGE BASED ON REACTOR BUILDING SUMP SAMPLE

1. This method of confirming core damage assumes that releases from the core are uniformly mixed in the Reactor Building Sump Sample.
2. The baseline coolant concentrations in Table 1 are for 0.5 hour after shutdown of a core that has been through at least one refueling cycle.
3. The half-life of the fission products should be considered in analyzing samples.
4. Estimate a dilution factor based on the dilution volume from injection the Reactor Building Sump sample has been subjected to.

\_\_\_\_\_ estimated dilution factor

5. Multiply the PASS Reactor Building Sump sample activities from Enclosure 1 by the estimated dilution factor from Step 4.
6. Compare these adjusted activities with the baseline coolant concentrations in Table 1. This table overestimates the concentration of the long-lived fission products (Cs and Sr) in a new core.
7. Determine the extent of core damage as indicated by Table 1 (i.e., normal, gas gap, core melt).

TABLE 1

## BASELINE REACTOR COOLANT CONCENTRATION

Nuclide	Normal Concentration (uCi/g)	Concentration After Gap Release (uCi/g)	Concentration After Core Melt (uCi/g)	TMI Concentration + 48 Hours (uCi/g)
I-131	4E-2	2E4	1E5	1.3E4
I-133	1E-1	3E4	2E5	6.5E3
I-135	2E-1	3E4	2E5	No Data
Cs-134	7E-3	2E3	8E3	6.3E1
Cs-137	9E-3	9E2	5E3	2.8E2
Ba-140	No Data	No Data	3E4	No Data
Sr-90	1E-5	No Data	1E4	5.3

8. Report determination to Dose Assessment Coordinator.

\_\_\_\_\_  
Initial/Date

## PROCEDURE DEVELOPMENT AND REVISION RECORD

---

Procedure: CH0632D    New Rev: 4    PRR#: 17342

Title: POST ACCIDENT SAMPLING AND ANALYSIS OF THE REACTOR BUILDING SUMP

---

### MINOR CHANGES

If Minor Changes are included, check the applicable box(es) and provide a list of affected steps.  
The following corrections are incorporated throughout:

- |   |   |
|---|---|
| <input type="checkbox"/> Sentence Structure   | <input type="checkbox"/> Redundant words or phrases                 |
| <input type="checkbox"/> Punctuation  | <input type="checkbox"/> Abbreviations                              |
| <input type="checkbox"/> Capitalization   | <input type="checkbox"/> Obviously incorrect units of measure       |
| <input type="checkbox"/> Spelling   | <input type="checkbox"/> Inadvertently omitted symbols (#, %, etc.) |
| <input type="checkbox"/> Organizational Changes: position titles,<br>department names, or telephone numbers | <input type="checkbox"/> Obvious step numbering discrepancies       |
| <input type="checkbox"/> Format   |   |

The following corrections are incorporated in the step(s) indicated: "Throughout" is used in lieu of Step# if a specific change affects a large number of steps.

---

Correcting equipment nomenclature that does not agree  
with field labels or balance of procedure

---

---

Changing information that is obviously incorrect and  
referenced correctly elsewhere

---

---

Misplaced decimals that are neither setpoint values nor  
tolerances

---

---

Reference to a procedure when an approved procedure  
has taken the place of another procedure

---

---

Fixing branching points when it is clear the branching  
steps were originally intended but were overlooked or  
incorrectly stated due to step number changes

---

---

Adding clarifying information such as NOTES and CAUTIONS

---

---

Adding words to clarify steps, NOTES, or CAUTIONS which  
clearly do not change the methodology or intent of the  
steps

---

## PROCEDURE DEVELOPMENT AND REVISION RECORD

Procedure: CH0632D New Rev: 4 PRR#: 17342

Title: POST ACCIDENT SAMPLING AND ANALYSIS OF THE REACTOR BUILDING SUMP

### MINOR CHANGES

If Minor Changes are included, check the applicable box(es) and provide a list of affected steps.  
The following corrections are incorporated throughout:

- |  |  |
|--|--|
| <input type="checkbox"/> Sentence Structure  | <input type="checkbox"/> Redundant words or phrases                      |
| <input type="checkbox"/> Punctuation   | <input type="checkbox"/> Abbreviations                                   |
| <input type="checkbox"/> Capitalization  | <input type="checkbox"/> Obviously incorrect units of measure            |
| <input type="checkbox"/> Spelling  | <input type="checkbox"/> Inadvertently omitted symbols (#, %, etc.)      |
| <input checked="" type="checkbox"/> Organizational Changes: position titles,<br>department names, or telephone numbers | <input checked="" type="checkbox"/> Obvious step numbering discrepancies |
| <input checked="" type="checkbox"/> Format   |  |

The following corrections are incorporated in the step(s) indicated: "Throughout" is used in lieu of Step# if a specific change affects a large number of steps.

Correcting equipment nomenclature that does not agree  
with field labels or balance of procedure

Changing information that is obviously incorrect and  
referenced correctly elsewhere

Misplaced decimals that are neither setpoint values nor  
tolerances

Reference to a procedure when an approved procedure  
has taken the place of another procedure

Fixing branching points when it is clear the branching  
steps were originally intended but were overlooked or  
incorrectly stated due to step number changes

5.4, 4.5 Adding clarifying information such as NOTES and CAUTIONS

Adding words to clarify steps, NOTES, or CAUTIONS which  
clearly do not change the methodology or intent of the  
steps

## PROCEDURE DEVELOPMENT AND REVISION RECORD

---

Procedure: CH0632D    New Rev: 4    PRR#: 17342

Title: POST ACCIDENT SAMPLING AND ANALYSIS OF THE REACTOR BUILDING SUMP

---

### NON-INTENT CHANGES

Changes are incorporated for the reasons provided. "Throughout" is used in lieu of Step # if a specific change affects a large number of steps. For new or cancelled procedures the reason is provided.

---

3.2.1, 3.2.2, 4.1.1, 4.1.5, Clarify instructions.  
4.1.3, 4.1.4

---

Title Page    Add ID as EP implementing procedure

---

3.2.4    Correct dose limits to agree with pre-job briefing.

---