



72-1004

**RECEIPT ACKNOWLEDGMENT TRANSMITTAL**

Date: 12/7/99  
Control No.: 001

To: Document Control Desk  
U.S. Nuclear Regulatory Commission

The following replacement page for Section 14.0, Page 1 of 1 is enclosed:

Please replace attached page for Section 14.0, page 1 of 1. The original issue of Section 14.0, page 1 of 1 was inadvertently missing the President's signature. There is no other change on this page.

Please complete the following:

- Sign and date below, then return the original to:

**TRANSNUCLEAR WEST INC.**  
**39300 CIVIC CENTER DRIVE, SUITE 280**  
**FREMONT, CA 94538**  
  
**ATTENTION: SHANNON CHRISTENSEN**  
**PHONE: (510) 744-6058      FAX: (510) 744-6002**

Signature: \_\_\_\_\_




Date: \_\_\_\_\_

Original: Document Control

Yellow: Recipient's Copy

NFO6

PDL ADDA 07201004

 <b>TRANSNUCLEAR WEST</b>	<b>QUALITY ASSURANCE MANUAL</b>	<b>SECTION: 14.0</b> <b>REVISION: 0</b> <b>PAGE 1 OF 1</b>
<b>QUALITY ASSURANCE MANAGER</b> 	<b>PRESIDENT</b> 	<b>DATE</b> 12/7/99 <b>7/28/98</b>

## 14.0 INSPECTION AND TEST STATUS

### 14.0 SCOPE

This section defines the requirements and assigns the responsibilities for the control of inspection and test status indicators, including the authority for application and removal of inspection and test status indicators.

#### 14.1 General

- 14.1.1 Procedures shall be established to indicate the inspection and test status of materials, items, structures, systems and components throughout fabrication, installation, operation and test.
- 14.1.2 Procedures shall be established to control the application and removal of inspection and welding stamps (when used) and status indicators such as tags markings, labels and stamps.
- 14.1.3 The status of non-conforming, inoperative or malfunctioning structures, systems and components shall be documented and identified to prevent inadvertent use, in accordance with Section 15.0 of this Quality Assurance Manual. However, prescribed duties, as defined in this Manual and related implementing procedures, are specifically designated to certain individuals.
- 14.1.4 Procedures shall be established to assure that items accepted and released are identified as to their inspection status prior to forwarding them to a controlled storage area or releasing them for installation, operation or further work.

#### 14.2 Responsibilities

- 14.2.1 The Quality Assurance Manager is responsible for approving procedures that provide for the identification of inspection and test status indicators, including the application and removal of status indicators such as tags and labels.
- 14.2.2 The Quality Assurance Manager is responsible for assuring that the status of non-conforming, inoperative or malfunctioning structures, systems or components is indicated.
- 14.2.3 Production, test and operations personnel are responsible for compliance with indicated inspection and test status indicators.