

Mr. A. Alan Blind
Vice President, Nuclear Power
Consolidated Edison Company
New York, Inc.
Broadway and Bleakley Avenue
Buchanan, NY 10511

April 27, 1999

SUBJECT: ISSUANCE OF AMENDMENT AND BASES CHANGE FOR INDIAN POINT
NUCLEAR GENERATING UNIT NO. 2 (TAC NO. M96475)

Dear Mr. Blind:

The Commission has issued the enclosed Amendment No. 200 to Facility Operating License No. DPR-26 for Indian Point Nuclear Generating Unit No. 2. The amendment consist of changes to Technical Specifications (TSs) in response to your application transmitted by letter dated August 21, 1996, as supplemented May 2, 1997.

The amendment revised Section 3.3.G (Hydrogen Recombiner System and Post-Accident Containment Venting System), the basis for Section 3.3.G, and Section 4.4, Table 4.4-1 (Containment Isolation Valves). This change permits removal of the existing flame-type hydrogen recombiners, its supporting equipment, and replacement with passive autocatalytic recombiners.

A copy of the related Safety Evaluation is enclosed. A Notice of Issuance will be included in the Commission's next regular biweekly Federal Register notice.

Sincerely,

ORIGINAL SIGNED BY:

Jefferey F. Harold, Project Manager, Section 1
Project Directorate I
Division of Licensing Project Management
Office of Nuclear Reactor Regulation

Docket No. 50-247

Enclosures: 1. Amendment No. 200 to DPR-26
2. Safety Evaluation

cc w/encs: See next page

DISTRIBUTION:

See next page

DOCUMENT NAME: G:\P2\AMD3865.WPD

NRC FILE CENTER COPY

DF0111

To receive a copy of this document, indicate in the box: "C" = Copy without attachment/enclosure "E" = Copy with attachment/enclosure "N" = No copy

OFFICE	PH: PDI	E	LA: PDI	SC: PDI	OGC
NAME	JHarold/rs		SLittle	SBajwa	R Bachmann
DATE	03/5/99		03/5/99	04/17/99	03/199 4/8/99

Official Record Copy

040038

change to SE, p.1
re May 2, 1997
supplement

9905040105 990427
PDR ADOCK 05000247
PDR



UNITED STATES
NUCLEAR REGULATORY COMMISSION
WASHINGTON, D.C. 20555-0001

April 27, 1999

Mr. A. Alan Blind
Vice President, Nuclear Power
Consolidated Edison Company
of New York, Inc.
Broadway and Bleakley Avenue
Buchanan, NY 10511

SUBJECT: ISSUANCE OF AMENDMENT AND BASES CHANGE FOR INDIAN POINT
NUCLEAR GENERATING UNIT NO. 2 (TAC NO. M96475)

Dear Mr. Blind:

The Commission has issued the enclosed Amendment No. 200 to Facility Operating License No. DPR-26 for Indian Point Nuclear Generating Unit No. 2. The amendment consist of changes to Technical Specifications (TSs) in response to your application transmitted by letter dated August 21, 1996, as supplemented May 2, 1997.

The amendment revised Section 3.3.G (Hydrogen Recombiner System and Post-Accident Containment Venting System), the basis for Section 3.3.G, and Section 4.4, Table 4.4-1 (Containment Isolation Valves). This change permits removal of the existing flame-type hydrogen recombiners, its supporting equipment, and replacement with passive autocatalytic recombiners.

A copy of the related Safety Evaluation is enclosed. A Notice of Issuance will be included in the Commission's next regular biweekly Federal Register notice.

Sincerely,

A handwritten signature in cursive script, reading "Jeffrey F. Harold", is written over a horizontal line.

Jeffrey F. Harold, Project Manager, Section 1
Project Directorate I
Division of Licensing Project Management
Office of Nuclear Reactor Regulation

Docket No. 50-247

Enclosures: 1. Amendment No. 200 to DPR-26
2. Safety Evaluation

cc w/encls: See next page

A. Alan Blind
Consolidated Edison Company
of New York, Inc.

cc:

Mayor, Village of Buchanan
236 Tate Avenue
Buchanan, NY 10511

Mr. F. William Valentino, President
New York State Energy, Research,
and Development Authority
Corporate Plaza West
286 Washington Ave. Extension
Albany, NY 12203-6399

Mr. Charles W. Jackson
Manager of Nuclear Safety and
Licensing
Consolidated Edison Company
of New York, Inc.
Broadway and Bleakley Avenue
Buchanan, NY 10511

Senior Resident Inspector
U. S. Nuclear Regulatory Commission
P.O. Box 38
Buchanan, NY 10511

Mr. Brent L. Brandenburg
Assistant General Counsel
Consolidated Edison Company
of New York, Inc.
4 Irving Place - 1822
New York, NY 10003

Indian Point Nuclear Generating
Station Units 1/2

Charles Donaldson, Esquire
Assistant Attorney General
New York Department of Law
120 Broadway
New York, NY 10271

Ms. Charlene D. Faison, Director
Nuclear Licensing
Power Authority of the State
of New York
123 Main Street
White Plains, NY 10601

Mr. Walter Stein
Secretary - NFSC
Consolidated Edison Company
of New York, Inc.
4 Irving Place - 1822
New York, NY 10003

Regional Administrator, Region I
U. S. Nuclear Regulatory Commission
475 Allendale Road
King of Prussia, PA 19406

Mr. Paul Eddy
New York State Department of
Public Service
3 Empire State Plaza, 10th Floor
Albany, NY 12223



UNITED STATES
NUCLEAR REGULATORY COMMISSION
WASHINGTON, D.C. 20555-0001

CONSOLIDATED EDISON COMPANY OF NEW YORK, INC.

DOCKET NO. 50-247

INDIAN POINT NUCLEAR GENERATING UNIT NO. 2

AMENDMENT TO FACILITY OPERATING LICENSE

Amendment No. 200
License No. DPR-26

1. The Nuclear Regulatory Commission (the Commission) has found that:

- A. The application for amendment by Consolidated Edison Company of New York, Inc. (the licensee) dated August 21, 1996, as supplemented May 2, 1997, complies with the standards and requirements of the Atomic Energy Act of 1954, as amended (the Act) and the Commission's rules and regulations set forth in 10 CFR Chapter I;
- B. The facility will operate in conformity with the application, the provisions of the Act, and the rules and regulations of the Commission;
- C. There is reasonable assurance (i) that the activities authorized by this amendment can be conducted without endangering the health and safety of the public, and (ii) that such activities will be conducted in compliance with the Commission's regulations;
- D. The issuance of this amendment will not be inimical to the common defense and security or to the health and safety of the public; and
- E. The issuance of this amendment is in accordance with 10 CFR Part 51 of the Commission's regulations and all applicable requirements have been satisfied.

2. Accordingly, the license is amended by changes to the Technical Specifications as indicated in the attachment to this license amendment, and paragraph 2.C.(2) of Facility Operating License No. DPR-26 is hereby amended to read as follows:

9905040108 990427
PDR ADOCK 05000247
P PDR

(2) Technical Specifications

The Technical Specifications contained in Appendices A and B, as revised through Amendment No. 200 , are hereby incorporated in the license. The licensee shall operate the facility in accordance with the Technical Specifications.

3. This license amendment is effective as of the date of its issuance. Sections 3.0 and 4.5 to be implemented within 90 days and Table 4.4 to be implemented in June 2000 or the next refueling outage.

FOR THE NUCLEAR REGULATORY COMMISSION



S. Singh Bajwa, Section Chief, Section 1
Project Directorate I
Division of Licensing Project Management
Office of Nuclear Reactor Regulation

Attachment:
Changes to the Technical
Specifications

Date of Issuance: April 27, 1999

ATTACHMENT TO LICENSE AMENDMENT NO. 200

FACILITY OPERATING LICENSE NO. DPR-26

DOCKET NO. 50-247

Revise Appendix A as follows:

Remove Pages

3.3-1 through 3.3-18

4.5-1 through 4.5-11

Table 4.4-1 (page 1 of 10)

Table 4.4-1 (page 2 of 10)

Table 4.4-1 (page 3 of 10)

Table 4.4-1 (page 4 of 10)

Table 4.4-1 (page 5 of 10)

Table 4.4-1 (page 6 of 10)

Table 4.4-1 (page 7 of 10)

Table 4.4-1 (page 8 of 10)

Table 4.4-1 (page 9 of 10)

Table 4.4-1 (page 10 of 10)

Insert Pages

3.3-1 through 3.3-17

4.5-1 through 4.5-11

Table 4.4-1 (page 1 of 9)

Table 4.4-1 (page 2 of 9)

Table 4.4-1 (page 3 of 9)

Table 4.4-1 (page 4 of 9)

Table 4.4-1 (page 5 of 9)

Table 4.4-1 (page 6 of 9)

Table 4.4-1 (page 7 of 9)

Table 4.4-1 (page 8 of 9)

Table 4.4-1 (page 9 of 9)

3.3 ENGINEERED SAFETY FEATURES

Applicability

Applies to the operating status of the Engineered Safety Features.

Objective

To define those limiting conditions for operation that are necessary (1) to remove decay heat from the core in emergency or normal shutdown situations, (2) to remove heat from containment in normal operating and emergency situations, (3) to remove airborne iodine from the containment atmosphere following a Design Basis Accident, (4) to minimize containment leakage to the environment subsequent to a Design Basis Accident.

Specifications

The following specifications apply except during low-temperature physics tests.

A. SAFETY INJECTION AND RESIDUAL HEAT REMOVAL SYSTEMS

1. The reactor shall not be made critical except for low-temperature physics tests, unless the following conditions are met:
 - a. The refueling water storage tank contains not less than 345,000 gallons of water with a boron concentration of at least 2000 ppm.
 - b. Deleted
 - c. The four accumulators are pressurized to a minimum of 598 psig and a maximum of 685 psig and each contains a minimum of 723 ft³ and a maximum of 875 ft³ of water with a boron concentration of at least 2000 ppm. None of these four accumulators may be isolated.
 - d. Three safety injection pumps together with their associated piping and valves are operable.
 - e. Two residual heat removal pumps and heat exchangers together with their associated piping and valves are operable.
 - f. Two recirculation pumps together with the associated piping and valves are operable.

- g. Valves 842 and 843 in the mini-flow return line from the discharge of the safety injection pumps to the RWST are de-energized in the open position.
 - h. Valves 856A, C, D and E, in the discharge header of the safety injection header, are in the open position. Valves 856B and F, in the discharge header of the safety injection header, are in the closed position. The hot-leg valves (856B and F) shall be closed with their motor operators de-energized by locking out the circuit breakers at the Motor Control Centers.
 - i. The four accumulator isolation valves shall be open with their motor operators de-energized by locking out the circuit breakers at the Motor Control Centers.
 - j. Valve 1810 on the suction line of the high-head SI pumps and valves 882 and 744, respectively on the suction and discharge line of the residual heat removal pumps, shall be blocked open by de-energizing the valve-motor operators.
 - k. The refueling water storage tank low-level alarms are operable and set to alarm between 74,200 gallons and 99,000 gallons of water in the tank.
- 2. During power operation, the requirements of 3.3.A.1 may be modified to allow any one of the following components to be inoperable at any one time. If the system is not restored to meet the requirements of 3.3.A.1 within the time period specified, the reactor shall be placed in the hot shutdown condition utilizing normal operating procedures. If the requirements of 3.3.A.1 are not satisfied within an additional 48 hours, the reactor shall be placed in the cold shutdown condition utilizing normal operating procedures.
 - a. One safety injection pump may be out of service, provided the pump is restored to operable status within 24 hours and the remaining two pumps are operable.
 - b. One residual heat removal pump may be out of service, provided the pump is restored to operable status within 24 hours and the other residual heat removal pump is operable.
 - c. One residual heat removal heat exchanger may be out of service provided that it is restored to operable status within 48 hours.

- d. Any valve required for the functioning of the system during and following accident conditions may be inoperable provided that it is restored to operable status within 24 hours and all valves in the system that provide the duplicate function are operable.
 - e. Deleted
 - f. One refueling water storage tank low-level alarm may be inoperable for up to 7 days provided the other low-level alarm is operable.
3. When RCS temperature is less than or equal to 305°F, the requirements of Table 3.1.A-2 regarding the number of safety injection (SI) pumps allowed to be energized shall be adhered to.

B. CONTAINMENT COOLING AND IODINE REMOVAL SYSTEMS

1. The reactor shall not be made critical unless the following conditions are met:
- a. The recirculation fluid pH control system shall be operable with ≥ 8000 lbs. (148 cu. ft.) of trisodium phosphate (w/12 hydrates), or equivalent, available in storage baskets in the containment.
 - b. The five fan cooler-charcoal filter units and the two spray pumps, with their associated valves and piping, are operable.
2. During power operation, the requirements of 3.3.B.1 may be modified to allow any one of the following components to be inoperable. If the system is not restored to meet the requirements of 3.3.B.1 within the time period specified, the reactor shall be placed in the hot shutdown condition utilizing normal operating procedures. If the requirements of 3.3.B.1 are not satisfied within an additional 48 hours, the reactor shall be placed in the cold shutdown condition utilizing normal operating procedures.
- a. One fan cooler unit may be inoperable during normal reactor operation for a period not to exceed 7 days provided both containment spray pumps are operable.
 - b. One containment spray pump may be inoperable during normal reactor operation, for a period not to exceed 72 hours, provided the five fan cooler units and the remaining containment spray pump are operable.

- c. Any valve required for the functioning of the system during and following accident conditions may be inoperable provided it is restored to operable status within 7 days or 72 hours for the fan cooler or containment spray systems respectively, and all valves in the system that provide the duplicate function are operable.
- d. The storage baskets in the containment may contain less than the required amount of trisodium phosphate during normal reactor operation for a period not to exceed 72 hours.

C. ISOLATION VALVE SEAL WATER SYSTEM (IVSWS)

- 1. The reactor shall not be brought above cold shutdown unless the following requirements are met:
 - a. The IVSWS shall be operable.
 - b. The IVSW tank shall be maintained at a minimum pressure of 52 psig and contain a minimum of 144 gallons of water.
- 2. The requirements of 3.3.C.1 may be modified to allow any one of the following components to be inoperable at any one time:
 - a. Any one header of the IVSWS may be inoperable for a period not to exceed seven consecutive days.
 - b. Any valve required for the functioning of the system during and following accident conditions may be inoperable provided it is restored to an operable status within seven days and all valves in the system that provide a duplicate function are operable.

3. If the IVSWS System is not restored to an operable status within the time period specified, then:

- a. If the reactor is critical, it shall be brought to the hot shutdown condition utilizing normal operating procedures. The shutdown shall start not later than at the end of the specified time period.
- b. If the reactor is subcritical, the reactor coolant system temperature and pressure shall not be increased more than 25°F and 100 psi, respectively, over existing values.
- c. In either case, if the IVSW System is not restored to an operable status within an additional 48 hours, the reactor shall be brought to the cold shutdown condition utilizing normal operating procedures. The shutdown shall start no later than the end of the 48-hour period.

D. WELD CHANNEL AND PENETRATION PRESSURIZATION SYSTEM (WC & PPS)

- 1. The reactor shall not be brought above cold shutdown unless:
 - a. All required portions of the four WC & PPS zones are pressurized at or above 47 psig.
 - b. The uncorrected air consumption for the WC & PPS is less than or equal to 0.2% of the containment volume per day.
- 2. The requirements of 3.3.D.1 may be modified as follows:
 - a. Any one zone of the WC & PPS may be inoperable for a period not to exceed seven consecutive days.
 - b. The uncorrected air consumption for the WC & PPS may be in excess of 0.2% of the containment volume per day for a period not to exceed seven consecutive days.

- c. With the portion of the weld channel pressurization system inoperable, and it is determined that it is not repairable by any practicable means, then that portion may be disconnected from the system.
- 3. If the WC & PP System is not restored to an operable status within the time period specified, then:
 - a. If the reactor is critical, it shall be brought to the hot shutdown condition utilizing normal operating procedures. The shutdown shall start no later than at the end of the specified time period.
 - b. If the reactor is subcritical, the reactor coolant system temperature and pressure shall not be increased more than 25°F and 100 psi, respectively, over existing values.
 - c. In either case, if the WC & PP System is not restored to an operable status within an additional 48 hours, the reactor shall be brought to the cold shutdown condition utilizing normal operating procedures. The shutdown shall start no later than the end of the 48-hour period.

E. COMPONENT COOLING SYSTEM

- 1. The reactor shall not be made critical unless the following conditions are met:
 - a. Three component cooling pumps together with their associated piping and valves are operable.
 - b. Two auxiliary component cooling pumps together with their associated piping and valves are operable.
 - c. Two component cooling heat exchangers together with their associated piping and valves are operable.
- 2. During power operation, the requirements of 3.3.E.1 may be modified to allow one of the following components to be inoperable at any one time. If the system is not restored to meet the conditions of 3.3.E.1 within the time period specified, the reactor shall be placed in the hot shutdown condition utilizing normal

operating procedures. If the requirements of 3.3.E.1 are not satisfied within an additional 48 hours, the reactor shall be placed in the cold shutdown condition utilizing normal operating procedures.

- a. One of the three operable component cooling pumps may be out of service provided the pump is restored to operable status within 14 days. Component Cooling Pump 22 may be out of service if Emergency Diesel Generator 22 is out of service or if no emergency diesel generator is out of service.
- b. An additional component cooling pump may be out of service provided a second pump is restored to operable status within 24 hours.
- c. One auxiliary component cooling pump may be out of service provided the pump is restored to operable status within 24 hours and the other pump is operable.
- d. One component cooling heat exchanger or other passive component may be out of service for a period not to exceed 48 hours provided the system may still operate at design accident capability.

F. SERVICE WATER SYSTEM

1. DESIGNATED ESSENTIAL HEADER

- a. The reactor shall not be above 350°F unless three service water pumps with their associated piping and valves are operable on the designated essential header.
- b. When the reactor is above 350°F and one of the three service water pumps or any of its associated piping or valves is found inoperable, and an essential service water header that meets the requirements of 3.3.F.1.a. cannot be restored within 12 hours, the reactor shall be placed in the hot shutdown condition within the next 6 hours and subsequently cooled below 350°F using normal operating procedures.

2. DESIGNATED NON-ESSENTIAL HEADER

- a. The reactor shall not be above 350°F unless two service water pumps with their associated piping and valves are operable on the designated non-essential header.
- b. When the reactor is above 350°F and one of the two service water pumps or any of its associated piping or valves is found inoperable, and a non-essential service water header that meets the requirements of 3.3.F.2.a cannot be restored within 24 hours, the reactor shall be placed in the hot shutdown condition within the next 6 hours and subsequently cooled below 350°F using normal operating procedures.

3. INTERCONNECTION OF HEADERS

Isolation shall be maintained between the essential and non-essential headers at all times when the reactor is above 350°F except for a period of up to 8 hours when the header may be connected to facilitate safety-related activities.

4. SERVICE WATER INLET TEMPERATURE

- a. The reactor shall not be above 350°F unless the service water inlet temperature is less than or equal to 95°F, or
- b. When the reactor is above 350°F and the service water inlet temperature exceeds 95°F, the reactor shall be placed in the hot shutdown condition within the next 7 hours and subsequently cooled below 350°F using normal operating procedures.
- c. The provisions of Specification 3.0.1 do not apply.

5. SERVICE WATER INLET TEMPERATURE MONITORING INSTRUMENTATION

- a. The service water inlet temperature monitoring instrumentation shall measure the Hudson River water temperature at the Indian Point Unit No. 2 intake structure,
- b. The service water inlet temperature monitoring instrumentation shall be operable when intake water temperature, averaged over a 24 hour period, reaches 80°F, and when the reactor is above 350°F,

- c. When the requirements of Specification 3.3.F.5.b apply, temperature measurements shall be taken every 4 hours up to and including a service water inlet temperature of 90°F; when the service water inlet temperature exceeds 90°F, temperature measurements shall be taken once an hour,
- d. If the service water inlet temperature monitoring instrumentation is declared inoperable, it shall be either restored to operable status or alternative measurements shall be taken with a calibrated portable instrument within the applicable measurement time frame requirements of Specification 3.3.F.5.c, and
- e. If the requirements of Specification 3.3.F.5.d cannot be met, the reactor shall be placed in the hot shutdown condition within the next 7 hours and subsequently cooled below 350°F using normal operating procedures.

G. HYDROGEN RECOMBINER SYSTEM AND POST-ACCIDENT CONTAINMENT VENTING SYSTEM

- 1. The reactor shall not be made critical unless the following conditions are met:
 - a. Both hydrogen recombiner units are operable.
 - b. The post-accident containment venting system is operable.
- 2. During power operation, the requirements of 3.3.G.1 may be modified to allow any one of the following components to be inoperable. If the system is not restored to meet the requirements of 3.3.G.1 within the time specified, the reactor shall be placed in the hot shutdown condition utilizing normal operating procedures.
 - a. One hydrogen recombiner unit may be inoperable for a period not to exceed thirty days, provided the other recombiner unit and the post-accident containment venting system are operable.
 - b. The post-accident containment venting system may be inoperable for a period not to exceed thirty days provided that both hydrogen recombiners are operable.

H. CONTROL ROOM AIR FILTRATION SYSTEM

1. The control room air filtration system shall be operable at all times when containment integrity is required.
2. From the date that the control room air filtration system becomes and remains inoperable for any reason, operations requiring containment integrity are permissible only during the succeeding 3.5 days. At the end of this 3.5 days period, if the conditions for the control room air filtration system cannot be met, the reactor shall be placed in the hot shutdown condition utilizing normal operating procedures. If the conditions are not satisfied within an additional 48 hours, the reactor shall be placed in the cold shutdown condition utilizing normal operating procedures.
3. Two independent toxic gas detection systems, each capable of detecting chlorine and anhydrous ammonia shall be operable at all times except as specified in 3.a, 3.b, or 3.c below. The alarm/trip setpoints for the chlorine and anhydrous ammonia gas detection systems shall be adjusted to actuate at a toxic gas concentration of less than or equal to 3.5 ppm and 25 ppm, respectively.
 - a. With one toxic gas detection system inoperable, restore the inoperable detection system to operable status within 7 days.
 - b. If 3.a above cannot be satisfied within the specified time, then, within the next 6 hours, initiate and maintain operation of the control room ventilation system in the recirculation mode of operation.
 - c. With both toxic gas detection systems inoperable for any one toxic gas, within one hour initiate and maintain operation of the control room ventilation in the recirculation mode of operation.

I. CABLE TUNNEL VENTILATION FANS

1. The reactor shall not be made critical unless the two cable tunnel ventilation fans are operable.
2. During power operation, the requirement of 3.3.I.1 may be modified to allow one cable tunnel ventilation fan to be inoperable for seven days, provided the other fan is operable.

Basis

The normal procedure for starting the reactor is, first, to heat the reactor coolant to near operating temperature by running the reactor coolant pumps. The reactor is then made critical by withdrawing control rods and/or diluting boron in the coolant⁽¹⁾. With this mode of start-up, the energy stored in the reactor coolant during the approach to criticality is substantially equal to that during power operation, and therefore the minimum required engineered safeguards and auxiliary cooling systems are required to be operable. During low-temperature physics tests there is a negligible amount of stored energy in the reactor coolant; therefore, an accident comparable in severity to the Design Basis Accident is not possible, and the engineered safeguards systems are not required.

When the reactor is critical, the probability of sustaining both a major accident and a simultaneous failure of a safeguards component to operate as designed is necessarily very small. Thus operation with the reactor critical with minimum safeguards operable for a limited period does not significantly increase the probability of an accident having consequences which are more severe than the Design Basis Accident.

The operable status of the various systems and components is to be demonstrated by periodic tests, defined by Specification 4.5. A large fraction of these tests will be performed while the reactor is operating in the power range. If a component is found to be inoperable, it will be possible in most cases to effect repairs and restore the system to full operability within a relatively short time. Inoperability of a single component does not negate the ability of the system to perform its function⁽²⁾, but it reduces the redundancy provided in the reactor design and thereby limits the ability to tolerate additional equipment failures. To provide maximum assurance that the redundant component(s) will operate if required to do so, the redundant component(s) are to be tested prior to initiating repair of the inoperable component. If it develops that (1) the inoperable component is not repaired within the specified allowable time period, or (2) a second component in the same or related system is found to be inoperable, the reactor will initially be put in the hot shutdown condition to provide for reduction of the decay heat from the fuel and consequent reduction of cooling requirements after a postulated loss-of-coolant accident. This will also permit improved access for repairs in some cases. After a limited time in hot shutdown, if the malfunction(s) are not corrected, the reactor will be placed in the cold shutdown condition, utilizing normal shutdown and cooldown procedures. In the cold shutdown condition there is no possibility of an accident that would release fission products or damage the fuel elements.

The plant operating procedures require immediate action to effect repairs of an inoperable component, and therefore in most cases repairs will be completed in less than the specified allowable repair times. The specified repair times do not apply to regularly scheduled maintenance of the engineered safeguards systems, which is normally to be performed during refueling shutdowns. The limiting times to repair are based on two considerations:

1. assurance with high reliability that the safeguard system will function properly if required to do so, and
2. allowance of sufficient time to effect repairs using safe and proper procedures.

Assuming the reactor has been operating at full-rated power for at least 100 days, the magnitude of the decay heat decreases after initiating hot shutdown. Thus the requirement for core cooling in case of a postulated loss-of-coolant accident while in the hot shutdown condition is significantly reduced below the requirements for a postulated loss-of-coolant accident during power operation. Putting the reactor in the hot shutdown condition significantly reduces the potential consequences of a loss-of-coolant accident, and also allows more free access to some of the engineered safeguards components in order to effect repairs.

Failure to complete repairs within 48 hours of going to the hot shutdown condition is considered indicative of a requirement for major maintenance, and therefore in such a case the reactor is to be put into the cold shutdown condition.

Valves 1810, 744 and 882 are kept in the open position during plant operation to assure that flow passage from the refueling water storage tank will be available during the injection phase of a loss-of-coolant accident. As an additional assurance of flow passage availability, the valve motor operators are de-energized to prevent an extremely unlikely spurious closure of these valves to take place. This additional precaution is acceptable since failure to manually re-establish power to close valves 1810 and 882, following the injection phase, is tolerable as a single failure. Valve 744 will not need to be closed following the injection phase. The accumulator isolation valve motor operators are de-energized to prevent an extremely unlikely spurious closure of these valves from occurring when accumulator core cooling flow is required.

With respect to the core cooling function, there is some functional redundancy for certain ranges of break sizes. The measure of effectiveness of the Safety Injection System is the ability of the pumps and accumulators to keep the core flooded or to reflood the core rapidly where the core has been uncovered for postulated large area ruptures. The result of the performance is to sufficiently limit any increase in clad temperature below a value where emergency core cooling objectives are met⁽⁹⁾. The range of core protection as a function of break diameter provided by the various components of the Safety Injection System is presented in Figure 6.2-9 of the UFSAR.

The requirement regarding the maximum number of SI pumps that can be energized when RCS temperature is less than or equal to 305°F is discussed under Specification 3.1.A.

The containment cooling function is provided by two independent systems: (1) fan-coolers plus charcoal filters and (2) containment spray. During normal power operation, the five fan-coolers are required to remove heat lost from equipment and piping within containment at design conditions (with a cooling water temperature of 95°F)⁽¹²⁾. In the event of a Design Basis Accident, sufficient cooling to reduce containment pressure at a rate consistent with limiting offsite doses to acceptable values is provided by three fan-cooler units and one spray pump. These constitute the minimum safeguards and are capable of being operated on emergency power with one diesel generator inoperable.

The iodine removal function is provided by two independent operating trains of the containment spray system. In the event of a Design Basis Accident, one containment spray pump provides sufficient flow to remove air borne elemental and particulate iodine at a rate consistent with limiting offsite doses to acceptable values.

Adequate power for operation of the redundant containment heat removal systems (i.e., five fan-cooler units or two containment spray pumps) is assured by the availability of offsite power or operation of all emergency diesel generators.

The operability of the recirculation fluid pH control system ensures that there is sufficient trisodium phosphate (TSP) available in containment to guarantee a sump pH ≥ 7.0 during the recirculation phase of a postulated LOCA. This pH level is required to reduce the potential for chloride induced stress corrosion of austenitic stainless steel and assure the retention of iodine in the recirculating fluid. The specified amounts of TSP will result in a recirculation fluid pH between 7.0 and 9.5.

One of the five fan cooler units is permitted to be inoperable during power operation. This is an abnormal operating situation, in that the normal plant operating procedures require that an inoperable fan-cooler be repaired as soon as practical.

However, because of the difficulty of gaining access to make repairs, it is important on occasion to be able to operate temporarily without at least one fan-cooler. Compensation for this mode of operation is provided by the high degree of redundancy of containment cooling systems during a Design Basis Accident.

The Component Cooling System is different from the system discussed above in that the pumps are so located in the Auxiliary Building as to be accessible for repair after a loss-of-coolant accident⁽⁶⁾. During the recirculation phase following a loss-of-coolant accident, only one of the three component cooling pumps is required for minimum safeguards⁽⁷⁾. With two operable component cooling pumps, 100% redundancy will be provided. A total of three operable component cooling pumps will provide 200% redundancy. The 14 day out of service period for the third component cooling pump is allowed since this is the 200% redundant pump.

A total of six service water pumps are installed. Only two of the set of three service water pumps on the header designated the essential header are required immediately following a postulated loss-of-coolant accident⁽⁸⁾. The limit on the service water maximum inlet temperature assures that the service water and component cooling water systems will be able to dissipate the heat loads generated in the limiting design basis accident.⁽¹²⁾

During the second phase of the accident, one additional service water pump on the non-essential header will be manually started to supply the minimum cooling water requirements for the component cooling loop.

The limits for the accumulators and their pressure and volume assure the required amount of water injection following a loss-of-coolant accident, and are based on the values used for the accident analysis⁽⁹⁾.

Two independent diverse systems are provided for removal of combustible hydrogen from the containment building atmosphere: (1) the hydrogen recombiners, and (2) the post-accident containment venting system. Either of the two (2) hydrogen recombiners or the post-accident containment venting system are capable of wholly providing this function in the event of a design basis accident.

Two full-rated hydrogen recombination systems are provided in order to control the hydrogen evolved in the containment following a loss-of-coolant accident. Either system is capable of preventing the hydrogen concentration from exceeding 4% by volume within the containment. Each system is separate from the other. The containment atmosphere sampling system consists of a sample line which originates in each of the containment fan cooler units. The fan and sampling pump head together are sufficient to pump containment air in a loop from the fan cooler through a containment penetration to a sample vessel outside the containment, and then through a second penetration to the sample termination inside the containment. The recombiner will operate at hydrogen concentration above 0.25% by volume. Conservative calculations indicate that the hydrogen content within the containment will not reach 4% by volume.

The Post-Accident Containment Venting System consists of a common penetration line which acts as a supply line through which hydrogen-free air can be admitted to the containment, and an exhaust line, with parallel valving and piping, through which hydrogen-bearing gases from containment may be vented through a filtration system.

The supply flow path makes use of instrument air to feed containment. The nominal flow rate from either of the two instrument air compressors is 200 scfm. If the instrument air system is not available, the station air system is available as a backup.

The exhaust line penetrates the containment and then is divided into two parallel lines. Each parallel line contains a pressure sensor and all the valves necessary for controlling the venting operation. The two lines then rejoin and the exhaust passes through a flow sensor and a temperature sensor before passing through roughing, HEPA and charcoal filters. The exhaust is then directed to the plant vent.

The post-accident containment venting system is a passive system in the sense that a differential pressure between the containment and the outside atmosphere provides the driving force for the venting process to take place. The system is designed such that a minimum internal containment pressure of 2.14 psig is required for the system to operate properly. The flow rate and the duration of venting required to maintain the hydrogen concentration at or below 3 percent of the containment volume are determined from the containment hydrogen concentration measurements and the hydrogen generation rate. The containment pressure necessary to obtain the required vent flow is then determined. Using one of the air compressors, hydrogen-free air is pumped into the containment until the required containment pressure is reached. The air supply is then stopped and the supply/exhaust line is isolated by valves outside the containment. The addition of air to pressurize the containment dilutes the hydrogen; therefore, the containment will remain isolated until analysis of samples indicates that the concentration is again approaching 3 percent by volume. Venting will then be started. This process of containment pressurization followed by venting is repeated as may be necessary to maintain the hydrogen concentration at or below 3 volume percent.

The post-accident venting system is used only in the absence of hydrogen recombiners and only when absolutely necessary. From the standpoint of minimizing offsite radiation doses, the optimum starting time for the venting system, if needed, is the latest possible time after the accident. Consistent with this philosophy, the selected venting initiation point of 3 percent hydrogen maximizes the time period before venting is required while at the same time allows a sufficient margin of safety below the lower flammability limit of hydrogen.

The control room air filtration system is designed to filter the control room atmosphere for intake air and/or for recirculation during control room isolation conditions. The control room system is designed to automatically start upon control room isolation. Control room isolation is initiated either by a safety injection signal or by detection of high radioactivity in the control room. If the control room air filtration system is found to be inoperable, there is no immediate threat to the control room and reactor operation may continue for a limited period of time while repairs are being made. If the system cannot be repaired within 3.5 days, the reactor is placed in the hot shutdown condition.

The control room ventilation system is equipped with toxic gas detection systems consisting of redundant monitors capable of detecting chlorine and anhydrous ammonia. These toxic gas detection systems are designed to isolate the control room from outside air upon detection of

toxic concentration of the monitored gases in the control room ventilation system. The operability of the toxic gas detection systems provides assurance that the control room operators

will have adequate time to take protective action in the event of an accidental toxic gas release.

Selection of the gases to be monitored and the setpoint established for the monitors are based on the results described in the Indian Point Unit No. 2 Control Room Habitability Study dated June 10, 1991.

The cable tunnel is equipped with two temperature-controlled ventilation fans. Each fan has a capacity of 21,000 cfm and is connected to a 480v bus. One fan will start automatically when the temperature in the tunnel reaches 100°F. Under the worst conditions, i.e., loss of outside power and all the Engineered Safety Features in operation, one ventilation fan is capable of maintaining the tunnel temperature below 104°F. Under the same worst conditions, if no ventilation fans were operating, the natural air circulation through the tunnel would be sufficient to limit the gross tunnel temperature to below the tolerable value of 140°F. However, in order to provide for ample tunnel ventilation capacity, the two ventilation fans are required to be operable when the reactor is made critical. If one ventilation fan is found inoperable, the other fan will ensure that cable tunnel ventilation is available.

Valves 856A, C, D and E are maintained in the open position during plant operation to assure a flow path for high-head safety injection during the injection phase of a loss-of-coolant accident. Valves 856B and F are maintained in the closed position during plant operation to prevent hot-leg injection during the injection phase of a loss-of-coolant accident. As an additional assurance of preventing hot-leg injection, the valve motor operators are de-energized to prevent spurious opening of these valves. Power will be restored to these valves at an appropriate time in accordance with plant operating procedures after a loss-of-coolant accident in order to establish hot-leg recirculation.

Valves 842 and 843 in the mini-flow return line from the discharge of the safety injection pumps to the refueling water storage tank are de-energized in the open position to prevent an extremely unlikely spurious closure which would cause the safety injection pumps to overheat if the reactor coolant system pressure is above the shutoff head of the pumps.

The specified quantities of water for the RWST include unavailable water (4687 gals) in the tank bottom, inaccuracies (24,800 gals) in the alarm setpoints, the minimum quantity required during the injection (246,000 gals)⁽¹²⁾ for accident mitigation and the minimum quantity required during the recirculation phase (60,000 gals) for accident mitigation. The minimum RWST inventory (i.e., 345,000 gals) provides approximately 9,500 gallons margin.

The seven-day out-of-service period for the Weld Channel and Penetration Pressurization System and the Isolation Valve Seal Water System is allowed because no credit has been taken for operation of these systems in the calculation of offsite accident doses should an accident occur. No other safeguards systems are dependent on operation of these systems⁽¹¹⁾. The minimum pressure settings for the IVSWS and WC & PPS during operation assures effective performance of these systems and assures that the containment design pressure of 47 psig is not exceeded. Portions of the Weld Channel Pressurization System are in areas that are not accessible, such as below the concrete floor of containment or in high radiation areas. If it is determined that it is not practicable to repair an inoperable portion of the system, then that portion may be disconnected.

References

- (1) UFSAR Section 9
- (2) UFSAR Section 6.2
- (3) DELETED
- (4) UFSAR Section 6.4
- (5) Reference Deleted
- (6) UFSAR Section 9.3
- (7) UFSAR Section 9.3
- (8) UFSAR Section 9.6.1
- (9) UFSAR Section 14.3
- (10) Indian Point Unit No. 2, UFSAR Sections 6.2 and 6.3 and the Safety Evaluation accompanying "Application for Amendment to Operating License" sworn to by Mr. William J. Cahill, Jr. on March 28, 1977.
- (11) UFSAR Sections 6.5 and 6.6
- (12) WCAP-12312, "Safety Evaluation for An Ultimate Heat Sink Temperature to 95°F at Indian Point Unit 2", July, 1989.

4.5 ENGINEERED SAFETY FEATURES

Applicability

Applies to testing of the Safety Injection System, the Containment Spray System, the Hydrogen Recombiner System, and the Air Filtration System.

Objective

To verify that the subject systems will respond promptly and perform their design functions, if required.

Specifications

A. SYSTEM TESTS

1. Safety Injection System

- a. System tests shall be performed at each reactor Refueling Interval (#). With the Reactor Coolant System pressure less than or equal to 350 psig and temperature less than or equal to 350°F, a test safety injection signal will be applied to initiate operation of the system. The safety injection pumps are made inoperable for this test.
- b. The test will be considered satisfactory if control board indication and visual observations indicate that all components have received the safety injection signal in the proper sequence and timing; that is, the appropriate pump breakers shall have opened and closed, and the appropriate valves shall have completed their travel.
- c. Conduct a flow test of the high head safety injection system after any modification is made to either its piping and/or valve arrangement.
- d. Verify that the mechanical stops on Valves 856 A, C, D and E are set at the position measured and recorded during the most recent ECCS operational flow test or flow tests performed in accordance with (c) above. This surveillance procedure shall be performed

following any maintenance on these valves or their associated motor operators and at a convenient outage if the position of the mechanical stops has not been verified in the preceding three months.

B. CONTAINMENT SPRAY SYSTEM

1. System tests shall be performed at each reactor Refueling Interval (#). The tests shall be performed with the isolation valves in the spray supply lines at the containment blocked closed. Operation of the system is initiated by tripping the normal actuation instrumentation.
2. The spray nozzles shall be tested for proper functioning at least every five years.
3. The test will be considered satisfactory if visual observations indicate all components have operated satisfactorily.

C. HYDROGEN RECOMBINER SYSTEM

1. Visual Inspection of both PARs at each refueling outage(#) shall be done to verify that there is no significant fouling by foreign materials.
2. A sample plate from each PAR shall be removed at each refueling outage and tested to verify response to a hydrogen mixture test gas.

D. CONTAINMENT AIR FILTRATION SYSTEM

Each air filtration unit specified in Specification 3.3.B shall be demonstrated to be operable:

1. At least once per 31 days by initiating, from the control room, flow through the HEPA filters and charcoal adsorbers and verifying that the unit operates for at least 15 minutes.
2. At least once every Refueling Interval (#), or (1) after any structural maintenance on the HEPA filters or charcoal adsorber housings, or (2) at any time painting, fire or chemical releases could alter filter integrity by:
 - a. verifying a system flow rate at ambient conditions of 65,600 cfm $\pm$ 10% during filtration unit operation when tested in accordance with ANSI N510-1975. Verify that the flow rate through the charcoal adsorbers is $\geq$ 8,000 cfm.

- b. verifying that the HEPA filters and/or charcoal adsorbers satisfy the in-place testing acceptance criteria and uses the test procedures of Regulatory Positions C.5.a and C.5.c of Regulatory Guide 1.52, Revision 2, March 1978, at ambient conditions and at a flow rate of 65,600 cfm $\pm 10\%$ for the HEPA filters.
 - c. verifying within 31 days after removal that a laboratory analysis of a representative carbon sample obtained in accordance with Regulatory Position C.6.b of Regulatory Guide 1.52, Revision 2, March 1978, meets the laboratory testing criteria of Regulatory Position C.6.a (except for Position C.6.a(1)) of Regulatory Guide 1.52, Revision 2, March 1978.
- 3. After every 720 hours of charcoal adsorber operation, by verifying within 31 days after removal that a laboratory analysis of a representative carbon sample obtained in accordance with Regulatory Position C.6.b of Regulatory Guide 1.52, Revision 2, March 1978, meets the laboratory testing criteria of Regulatory Position C.6.a (except for Position C.6.a(1)) of Regulatory Guide 1.52, Revision 2, March 1978.
- 4. At least once every Refueling Interval (#) by:
 - a. Verifying that the pressure drop across the moisture separator and HEPA filters is less than 6 inches Water Gauge while operating the filtration unit at ambient conditions and at a flow rate of 65,600 cfm $\pm 10\%$.
 - b. Verifying that the unit starts automatically on a Safety Injection Test Signal.
- 5. After each complete or partial replacement of a HEPA filter bank, by verifying that the HEPA filter banks remove greater than or equal to 99% of the DOP when they are tested in-place in accordance with ANSI N510-1975 while operating the unit at ambient conditions and at a flow rate of 65,600 cfm $\pm 10\%$.
- 6. After each complete or partial replacement of a charcoal adsorber bank, verify that the flow rate through the charcoal adsorbers is $\geq 8,000$ cfm when the system is operating at ambient conditions and a flow rate of 65,600 cfm $\pm 10\%$ when tested in accordance with ANSI N510-1975.

E. CONTROL ROOM AIR FILTRATION SYSTEM

The control room air filtration system specified in Specification 3.3.H shall be demonstrated to be operable:

1. At least once per 31 days by initiating, from the control room, flow through the HEPA filters and charcoal adsorbers and verifying that the system operates for at least 15 minutes.
2. At least once every Refueling Interval(#) or (1) after any structural maintenance on the HEPA filter or charcoal adsorber housings, or (2) at any time painting, fire or chemical releases could alter filter integrity by:
 - a. verifying a system flow rate, at ambient conditions, of 1840 cfm $\pm 10\%$ during system operation when tested in accordance with ANSI N510-1975.
 - b. verifying that, with the system operating at ambient conditions and at a flow rate of 1840 CFM $\pm 10\%$ and exhausting through the HEPA filters and charcoal adsorbers, the total bypass flow of the system to the facility vent, including leakage through the system diverting valves, is less than or equal to 1% when the system is tested by admitting cold DOP at the system intake.
 - c. verifying that the system satisfies the in-place testing acceptance criteria and uses the test procedures of Regulatory Positions C.5.a, C.5.c and C.5.d of Regulatory Guide 1.52, Revision 2, March 1978, at ambient conditions and at a flow rate of 1840 cfm $\pm 10\%$.
 - d. verifying, within 31 days after removal, that a laboratory analysis of a representative carbon sample obtained in accordance with Regulatory Position C.6.b of Regulatory Guide 1.52, Revision 2, March 1978, meets the laboratory testing criteria of Regulatory Position C.6.a of Regulatory Guide 1.52, Revision 2, March 1978.
3. After every 720 hours of charcoal adsorber operation, by verifying within 31 days after removal that a laboratory analysis of a representative carbon sample obtained in accordance with Regulatory Position C.6.b of Regulatory Guide 1.52, Revision 2, March 1973, meets the laboratory testing criteria of Regulatory Position C.6.a of Regulatory Guide 1.52, Revision 2, March 1978.

4. At least once every Refueling Interval(#) by:
 - a. verifying that the pressure drop across the combined HEPA filters and charcoal adsorber banks is less than 6 inches water gauge while operating the system at ambient conditions and at a flow rate of 1840 cfm $\pm 10\%$.
 - b. verifying that, on a Safety Injection Test Signal or a high radiation signal in the control room, the system automatically switches into a recirculation mode of operation with flow through the HEPA filters and charcoal adsorber banks. ¹
 - c. verifying that the system maintains the control room at a neutral or positive pressure relative to the outside atmosphere during system operation.
5. After each complete or partial replacement of an HEPA filter bank, by verifying that the HEPA filter banks remove greater than or equal to 99% of the DOP when they are tested in-place in accordance with ANSI N510-1975 while operating the system at ambient conditions and at a flow rate of 1840 cfm $\pm 10\%$.
6. After each complete or partial replacement of a charcoal adsorber bank, by verifying that the charcoal adsorbers remove greater than or equal to 99.95% of a halogenated hydrocarbon refrigerant test gas when they are tested in-place in accordance with ANSI N510-1975 while operating the system at ambient conditions and at a flow rate of 1840 cfm $\pm 10\%$.
7. Each toxic gas detection system shall be demonstrated operable by performance of a channel check at least once per day, a channel test at least once per 31 days and a channel calibration at least once each Refueling Interval(#).

F. FUEL STORAGE BUILDING AIR FILTRATION SYSTEM

The fuel storage building air filtration system specified in Specification 3.8 shall be demonstrated operable:

1. At least once per 31 days by initiating, from the control room, flow through the HEPA filters and charcoal adsorbers and verifying that the system operates for at least 15 minutes.

2. At each refueling, prior to refueling operations, or (1) after any structural maintenance on the HEPA filter or charcoal adsorber housings, or (2) at any time painting, fire or chemical releases could alter filter integrity by:
 - a. verifying a system flow rate at ambient conditions of 20,000 cfm $\pm 10\%$ during system operation when tested in accordance with ANSI N510-1975.
 - b. verifying that the system satisfies the in-place testing acceptance criteria and uses the test procedures of Regulatory Positions C.5.a, C.5.c and C.5.d of Regulatory Guide 1.52, Revision 2, March 1978, at ambient conditions and at a flow rate of 20,000 cfm $\pm 10\%$.
 - c. verifying within 31 days after removal that a laboratory analysis of a representative carbon sample obtained in accordance with Regulatory Position C.6.b of Regulatory Guide 1.52, Revision 2, March 1978, meets the laboratory testing criteria of Regulatory Position C.6.a of Regulatory Guide 1.52, Revision 2, March 1978.
3. Prior to handling spent fuel which has decayed for less than 35 days, verify within 31 days after removal that a laboratory analysis of a representative carbon sample obtained in accordance with Regulatory Position C.6.b of Regulatory Guide 1.52, Revision 2, March 1978, meets the laboratory testing criteria of Regulatory Position C.6.a of Regulatory Guide 1.52, Revision 2, March 1978. Such an analysis is good for 720 hours of charcoal adsorber operation. After 720 hours of operation, if spent fuel with a decay time of less than 35 days is still being handled, a new sample is required along with a new analysis.
4. At each refueling prior to refueling operations by:
 - a. verifying that the pressure drop across the combined HEPA filters and charcoal adsorber banks is less than 6 inches water gauge while operating the system at ambient conditions and at a flow rate of 20,000 cfm $\pm 10\%$.
 - b. verifying that the system maintains the spent fuel storage pool area at a pressure less than that of the outside atmosphere during system operation.

5. After each complete or partial replacement of a HEPA filter bank, by verifying that the HEPA filter banks remove greater than or equal to 99% of the DOP when they are tested in-place in accordance with ANSI N510-1975 while operating the system at ambient conditions and at a flow rate of 20,000 cfm $\pm 10\%$.
6. After each complete or partial replacement of a charcoal adsorber bank, by verifying that the charcoal adsorbers remove greater than or equal to 99.95% of a halogenated hydrocarbon refrigerant test gas when they are tested in-place in accordance with ANSI N510-1975 while operating the system at ambient conditions and at a flow rate of 20,000 cfm $\pm 10\%$.

G. POST-ACCIDENT CONTAINMENT VENTING SYSTEM

The post-accident containment venting system shall be demonstrated operable:

1. At least once every Refueling Interval(#), or (1) after any structural maintenance on the HEPA filter or charcoal adsorber housings, or (2) at any time painting, fire or chemical releases could alter filter integrity by:
 - a. verifying no flow blockage by passing flow through the filter system.
 - b. verifying that the system satisfies the in-place testing acceptance criteria and uses the test procedures of Regulatory Positions C.5.a, C.5.c and C.5.d of Regulatory Guide 1.52, Revision 2, March 1978, at ambient conditions and at a flow rate of 200 cfm $\pm 10\%$.
 - c. at Refueling Intervals (#), verify within 31 days after removal that a laboratory analysis of a representative carbon sample obtained in accordance with Regulatory Position C.6.b of Regulatory Guide 1.52, Revision 2, March 1978, meets the laboratory testing criteria of Regulatory Position C.6.a of Regulatory Guide 1.52, Revision 2, March 1978.
2. After every 720 hours of charcoal adsorber operation, by verifying within 31 days after removal that a laboratory analysis of a representative carbon sample obtained in accordance with Regulatory Position C.6.b of Regulatory Guide 1.52, Revision 2, March 1978, meets the laboratory testing criteria of Regulatory Position C.6.a of Regulatory Guide 1.52, Revision 2, March 1978.

3. At least once every Refueling Interval(#) by:
 - a. verifying that the pressure drop across the combined HEPA filters and charcoal adsorber banks is less than 6 inches water gauge while

operating the system at ambient conditions and at a flow rate of 200 cfm $\pm 10\%$.
 - b. verifying that the system valves can be manually opened.
4. After each complete or partial replacement of a HEPA filter bank, by verifying that the HEPA filter banks remove greater than or equal to 99% of the DOP when they are tested in-place in accordance with ANSI N510-1975 while operating the system at ambient conditions and at a flow rate of 200 cfm $\pm 10\%$.
5. After each complete or partial replacement of a charcoal adsorber bank, by verifying that the charcoal adsorbers remove greater than or equal to 99.95% of a halogenated hydrocarbon refrigerant test gas when they are tested in-place in accordance with ANSI N510-1975 while operating the system at ambient conditions and at a flow rate of 200 cfm $\pm 10\%$.

H. RECIRCULATION FLUID PH CONTROL SYSTEM

1. The recirculation fluid pH control system shall be demonstrated operable each Refueling Interval (#) by visually verifying that:
 - a. The trisodium phosphate storage baskets are in place, and
 - b. they have maintained their integrity, and
 - c. they contain at least the minimum amount of trisodium phosphate.

Basis

The Safety Injection System and the Containment Spray System are principal plant safeguards that are normally inoperative during reactor operation. Complete systems tests cannot be performed when the reactor is operating because a safety injection signal causes reactor trip, main feedwater isolation and containment isolation, and a Containment Spray System test requires the system to be temporarily disabled. The method of assuring operability of these systems is, therefore, to combine systems tests to be performed during plant refueling shutdowns, with more frequent component tests, which can be performed during reactor

operation.

The refueling systems tests demonstrate proper automatic operation of the Safety Injection and Containment Spray Systems. With the pumps blocked from starting, a test signal is applied to initiate automatic action and verification made that the components receive the safety injection signal in the proper sequence. The test demonstrates the operation of the valves, pump circuit breakers, and automatic circuitry⁽¹⁾.

During reactor operation, the instrumentation which is depended on to initiate safety injection and containment spray is generally checked daily and the initiating circuits are tested monthly (in accordance with Specification 4.1). The testing of the analog channel input is accomplished in the same manner as for the reactor protection system. The engineered safety features logic system is tested by means of test switches to simulate inputs from the analog channels. Test switches are also provided down stream of the master relay output contacts. The purpose of these test switches is to prevent actuation of engineered safety features equipment during testing. Verification that the logic is accomplished is indicated by the matrix test light and/or master relay operation.

Other systems that are also important to the emergency cooling function are the accumulators, the Component Cooling System, the Service Water System and the containment fan coolers. The accumulators are a passive safeguard. In accordance with Specification 4.1, the water volume and pressure in the accumulators are checked periodically. The other systems mentioned operate when the reactor is in operation and, by these means, are continuously monitored for satisfactory performance.

For the four flow distribution valves (856 A, C, D and E), verification of the valve mechanical stop adjustments is performed periodically to provide assurance that the high head safety injection flow distribution is in accordance with flow values assumed in the core cooling analysis.

The hydrogen recombiner system is an engineered safety feature which would function following a loss-of-coolant accident to control the hydrogen evolved in the containment. The passive autocatalytic recombiners (PARs) contain no control or support equipment which would require surveillance. No specific degradation mechanism has yet been identified for the catalysts plates in standby service. Periodic visual examination and cleaning if necessary is done to prevent significant gas blockage by dust or debris. Representative plates are periodically removed and their response to a nominal 1% hydrogen gas mixture is evaluated for evidence of unexpected degradation.

The biannual testing of the containment atmosphere sampling system will demonstrate the availability of this system.

The recirculation fluid pH control system is a passive safeguard with the baskets of trisodium phosphate located in the containment sump area. Periodic visual inspections are required (Refueling#) to verify the storage baskets are in place, have maintained their integrity, and filled with trisodium phosphate.

The charcoal portion of the in-containment air recirculation system is a passive safeguard which is isolated from the cooling air flow during normal reactor operation. Hence the charcoal should have a long useful lifetime. The filter frames that house the charcoal are stainless steel and should also last indefinitely. However, the required periodic visual inspections will verify that this is the case. The iodine removal efficiency cannot be measured with the filter cells in place. Therefore, at periodic intervals a representative sample of charcoal is to be removed and tested to verify that the efficiency for removal of methyl iodide is obtained⁽²⁾. Such laboratory charcoal sample testing together with the specified in-place testing of the HEPA filters will provide further assurance that the criteria of 10 CFR 100 continue to be met.

The control room air filtration system is designed to filter the control room atmosphere for intake air and/or for recirculation during control room isolation conditions. The control room air filtration system is designed to automatically start upon control room isolation. High-efficiency particulate absolute (HEPA) filters are installed upstream of the charcoal adsorbers to prevent clogging of these adsorbers. The charcoal adsorbers are installed to reduce the potential intake of radioiodine by control room personnel. The required in-place testing and the laboratory charcoal sample testing of the HEPA filters and charcoal adsorbers will provide assurance that Criterion 19 of the General Design Criteria for Nuclear Power Plants, Appendix A to 10 CFR Part 50 continues to be met.

The fuel storage building air filtration system is designed to filter the discharge of the fuel storage building atmosphere to the plant vent. This air filtration system is designed to start automatically upon a high radiation signal. Upon initiation, isolation dampers in the ventilation system are designed to close to redirect air flow through the air treatment system. HEPA filters and charcoal adsorbers are installed to reduce potential releases of radioactive material to the

atmosphere. Nevertheless, as required by Specification 3.8.B.6, the fuel storage building air filtration system must be operating whenever spent fuel is being moved unless the spent fuel has had a continuous 35-day decay period. The required in-place testing and the laboratory charcoal sample testing of the HEPA filters and charcoal adsorbers will provide added assurance that the criteria of 10 CFR 100 continue to be met.

The post-accident containment venting system may be used in lieu of hydrogen recombiners for removal of combustible hydrogen from the containment building atmosphere following a design basis accident. As was the case for hydrogen recombiner use, this system is not expected to

be needed until approximately 13 days have elapsed following the accident. Use of the system will be based upon containment atmosphere sample analysis and availability of the hydrogen recombiners. When in use, HEPA filters and charcoal adsorbers will filter the containment atmosphere discharge prior to release to the plant vent. The required in-place testing and laboratory charcoal sample testing will verify operability of this venting system and provide further assurance that releases to the environment will be minimized.

As indicated for the previously mentioned engineered safety feature (ESF) air filtration systems, high-efficiency particulate absolute (HEPA) filters are installed upstream of the charcoal adsorbers to prevent clogging of these adsorbers. The charcoal adsorbers are installed to reduce the potential release of radioiodine to the environment. The laboratory charcoal sample testing periodically verifies that the charcoal meets the iodine removal efficiency requirements of Regulatory Guide 1.52, Revision 2. Should the charcoal of any of these filtration systems fail to

satisfy the specified test acceptance criteria, the charcoal will be replaced with new charcoal which satisfies the requirements for new charcoal outlined in Regulatory Guide 1.52, Revision 2.

References

- (1) UFSAR Section 6.2
- (2) UFSAR Section 6.4

1. In this instance Refueling Interval is defined by R#.

Table 4.4-1

Containment Isolation Valves

Valve No.	System ⁽¹⁾	Test Fluid ⁽²⁾	Minimum Test Pressure (PSIG)
549	PRT to Gas Analyzer	Water ⁽⁴⁾	52
548	• • • •	Water ⁽⁴⁾	52
518	PRT N ₂ Supply	Gas	47
3418	• • •	Gas	47
3419	• • •	Gas	47
4136	• • •	Gas	47
552	PRT Makeup Water	Water ⁽⁴⁾	52
519	• • •	Water ⁽⁴⁾	52
741A	RHR return to RCS	Water ⁽⁵⁾	52 ⁽³⁾
744	• • • •	Nitrogen ⁽⁴⁾	47 ⁽³⁾
888A	RHR to S.I. Pumps	Nitrogen ⁽⁴⁾	47
888B	• • • •	Nitrogen ⁽⁴⁾	47
958	RHR to Sample System	Nitrogen ⁽⁴⁾	47
959	• • • •	Nitrogen ⁽⁴⁾	47
990D	• • • •	Nitrogen ⁽⁴⁾	47
1870	RHR from RCS	Nitrogen ⁽⁴⁾	47
743	• • •	Nitrogen ⁽⁴⁾	47
732	• • •	Nitrogen ⁽⁴⁾	47 ⁽³⁾
885A	Cont. Sump Recirc. Line	Water ⁽⁵⁾	52
885B	• • • •	Water ⁽⁵⁾	52
201	Letdown Line (CVCS)	Water ⁽⁴⁾	52
202	• • •	Water ⁽⁴⁾	52

Table 4.4-1

Containment Isolation Valves

Valve No.	System ⁽¹⁾	Test Fluid ⁽²⁾	Minimum Test Pressure (PSIG)
205	Charging Line (CVCS)	Water ⁽⁴⁾	52
226	Charging Line (CVCS)	Water ⁽⁴⁾	52
227	• • •	Water ⁽⁴⁾	52
250A	RCP Seal Water (CVCS)	Water ⁽⁴⁾	52
4925	• • • •	Water ⁽⁴⁾	52
250B	• • • •	Water ⁽⁴⁾	52
4926	• • • •	Water ⁽⁴⁾	52
250C	• • • •	Water ⁽⁴⁾	52
4927	• • • •	Water ⁽⁴⁾	52
250D	• • • •	Water ⁽⁴⁾	52
4928	• • • •	Water ⁽⁴⁾	52
222	• • • •	Water ⁽⁴⁾	52
956E	RCS to Sample System	Water ⁽⁴⁾	52
956F	• • • •	Water ⁽⁴⁾	52
869A	Cont. Spray System	Water ⁽⁴⁾	52
867A	• • •	Gas	47
878A	• • •	Gas	47
869B	• • •	Water ⁽⁴⁾	52
867B	• • •	Gas	47
851A	Safety Inj. System	Water ⁽⁴⁾	52
850A	• • •	Water ⁽⁴⁾	52
851B	• • •	Water ⁽⁴⁾	52

Table 4.4-1

Containment Isolation Valves

Valve No.	System ⁽¹⁾	Test Fluid ⁽²⁾	Minimum Test Pressure (PSIG)
850B	Safety Inj. System	Water ⁽⁴⁾	52
859A	S.I. Test Line	Water ⁽⁴⁾	52
859C	S.I. Test Line	Water ⁽⁴⁾	52
4312	Acc. & OPS N ₂ Supply	Gas	47
863	" " " "	Gas	47
956G	Acc. to Sample System	Water ⁽⁴⁾	52
956H	" " " "	Water ⁽⁴⁾	52
1786	RCDT to Vent Header	Water ⁽⁴⁾	52
1787	" " " "	Water ⁽⁴⁾	52
3416	RCDT N ₂ Supply	Gas	47
3417	" " "	Gas	47
5459	" " "	Gas	47
1616	" " "	Gas	47
1788	RCDT to Gas Analyzer	Water ⁽⁴⁾	52
1789	" " " "	Water ⁽⁴⁾	52
1702	RCDT to WHT (WDS)	Water ⁽⁴⁾	52
1705	" " " "	Water ⁽⁴⁾	52
797	RCP Comp. Cooling (CCS)	Water ⁽⁴⁾	52
784	" " " "	Water ⁽⁴⁾	52
FCV-625	" " " "	Water ⁽⁴⁾	52
791	Excess Letdown Cool. (CCS)	Water ⁽⁴⁾	52
798	" " " "	Water ⁽⁴⁾	52

Table 4.4-1

Containment Isolation Valves

Valve No.	System ⁽¹⁾	Test Fluid ⁽²⁾	Minimum Test Pressure (PSIG)
796	Excess Letdown Cool. (CCS)	Water ⁽⁴⁾	52
793	▪ ▪ ▪ ▪	Water ⁽⁴⁾	52
1728	Cont. Sump to WHT (WDS)	Water ⁽⁴⁾	52
1723	Cont. Sump to WHT (WDS)	Water ⁽⁴⁾	52
1234	Cont. Air Sample	Gas ⁽⁷⁾	47
1235	▪ ▪ ▪	Gas ⁽⁷⁾	47
1236	▪ ▪ ▪	Gas ⁽⁷⁾	47
1237	▪ ▪ ▪	Gas ⁽⁷⁾	47
PCV-1229	Air Ejector to Cont.	Gas ⁽⁷⁾	47
PCV-1230	▪ ▪ ▪ ▪	Gas ⁽⁷⁾	47
PCV-1214	S.G. Blowdown/Sample	Water ⁽⁴⁾	52
PCV-1214A	▪ ▪ ▪	Water ⁽⁴⁾	52
PCV-1215	▪ ▪ ▪	Water ⁽⁴⁾	52
PCV-1215A	▪ ▪ ▪	Water ⁽⁴⁾	52
PCV-1216	▪ ▪ ▪	Water ⁽⁴⁾	52
PCV-1216A	▪ ▪ ▪	Water ⁽⁴⁾	52
PCV-1217	▪ ▪ ▪	Water ⁽⁴⁾	52
PCV-1217A	▪ ▪ ▪	Water ⁽⁴⁾	52
SWN-41-5-A	Cont. Fan Cooler-Ser. Wtr.	Water ⁽⁶⁾	52
SWN-41-5-B	▪ ▪ ▪ ▪ ▪	Water ⁽⁶⁾	52
SWN-43-5	▪ ▪ ▪ ▪ ▪	Water ⁽⁶⁾	52
SWN-42-5	▪ ▪ ▪ ▪ ▪	Water ⁽⁶⁾	52

Table 4.4-1

Containment Isolation Valves

Valve No.	System ⁽¹⁾	Test Fluid ⁽²⁾	Minimum Test Pressure (PSIG)
SWN-41-1-A	" " " "	Water ⁽⁶⁾	52
SWN-41-1-B	" " " "	Water ⁽⁶⁾	52
SWN-43-1	" " " "	Water ⁽⁶⁾	52
SWN-42-1	" " " "	Water ⁽⁶⁾	52
SWN-41-2-A	Cont. Fan Cooler-Ser. Wtr.	Water ⁽⁶⁾	52
SWN-41-2-B	" " " "	Water ⁽⁶⁾	52
SWN-43-2	" " " "	Water ⁽⁶⁾	52
SWN-42-2	" " " "	Water ⁽⁶⁾	52
SWN-41-3-A	" " " "	Water ⁽⁶⁾	52
SWN-41-3-B	" " " "	Water ⁽⁶⁾	52
SWN-43-3	" " " "	Water ⁽⁶⁾	52
SWN-42-3	" " " "	Water ⁽⁶⁾	52
SWN-41-4-A	" " " "	Water ⁽⁶⁾	52
SWN-41-4-B	" " " "	Water ⁽⁶⁾	52
SWN-43-4	" " " "	Water ⁽⁶⁾	52
SWN-42-4	" " " "	Water ⁽⁶⁾	52
SWN-44-5-A	" " " "	Water ⁽⁶⁾	52
SWN-44-5-B	" " " "	Water ⁽⁶⁾	52
SWN-51-5	" " " "	Water ⁽⁶⁾	52
SWN-44-1-A	" " " "	Water ⁽⁶⁾	52
SWN-44-1-B	" " " "	Water ⁽⁶⁾	52
SWN-51-1	" " " "	Water ⁽⁶⁾	52

Table 4.4-1

Containment Isolation Valves

Valve No.	System ⁽¹⁾	Test Fluid ⁽²⁾	Minimum Test Pressure (PSIG)
SWN-44-2-A	Cont. Fan Cooler-Ser. Wtr.	Water ⁽⁶⁾	52
SWN-44-2-B	" " " " "	Water ⁽⁶⁾	52
SWN-51-2	" " " " "	Water ⁽⁶⁾	52
SWN-44-3-A	" " " " "	Water ⁽⁶⁾	52
SWN-44-3-B	" " " " "	Water ⁽⁶⁾	52
SWN-51-3	Cont. Fan Cooler-Ser. Wtr.	Water ⁽⁶⁾	52
SWN-44-4-A	" " " " "	Water ⁽⁶⁾	52
SWN-44-4-B	" " " " "	Water ⁽⁶⁾	52
SWN-51-4	" " " " "	Water ⁽⁶⁾	52
SWN-71-5-A	" " " " "	Water ⁽⁶⁾	52
SWN-71-5-B	" " " " "	Water ⁽⁶⁾	52
SWN-71-1-A	" " " " "	Water ⁽⁶⁾	52
SWN-71-1-B	" " " " "	Water ⁽⁶⁾	52
SWN-71-2-A	" " " " "	Water ⁽⁶⁾	52
SWN-71-2-B	" " " " "	Water ⁽⁶⁾	52
SWN-71-3-A	" " " " "	Water ⁽⁶⁾	52
SWN-71-3-B	" " " " "	Water ⁽⁶⁾	52
SWN-71-4-A	" " " " "	Water ⁽⁶⁾	52
SWN-71-4-B	Cont. Fan Cooler-Ser. Wtr.	Water ⁽⁶⁾	52
SA-24	Service Air to Cont.	Water ⁽⁴⁾	52
SA-24-1	" " "	Water ⁽⁴⁾	52
580A	Dead Weight Tester	Gas	47

Table 4.4-1

Containment Isolation Valves

Valve No.	System ⁽¹⁾	Test Fluid ⁽²⁾	Minimum Test Pressure (PSIG)
580B	Dead Weight Tester	Gas	47
UH-43	Auxiliary Steam System	Water ⁽⁴⁾	52
UH-44	" " "	Water ⁽⁴⁾	52
MW-17	City Wtr. to Cont.	Water ⁽⁴⁾	52
MW-17-1	" " " "	Water ⁽⁴⁾	52
1170	Cont. Purge System	Gas ⁽⁷⁾	47
1171	Cont. Purge System	Gas ⁽⁷⁾	47
1172	" " "	Gas ⁽⁷⁾	47
1173	" " "	Gas ⁽⁷⁾	47
1190	Cont. Pressure Relief	Gas ⁽⁷⁾	47
1191	" " "	Gas ⁽⁷⁾	47
1192	" " "	Gas ⁽⁷⁾	47
990A	Recirc. Pump to Samp. Sys.	Nitrogen ⁽⁴⁾	47
990B	" " " " "	Nitrogen ⁽⁴⁾	47
956A	Pressurizer to Samp. Sys.	Water ⁽⁴⁾	52
956B	" " " "	Water ⁽⁴⁾	52
956C	" " " "	Water ⁽⁴⁾	52
956D	Pressurizer to Samp. Sys.	Water ⁽⁴⁾	52
1814A	Cont. Pressure Instr.	Gas	47
1814B	" " "	Gas	47
1814C	" " "	Gas	47
5018	Post Acc. Cont. Sampling	Gas	47

Table 4.4-1

Containment Isolation Valves

Valve No.	System ⁽¹⁾	Test Fluid ⁽²⁾	Minimum Test Pressure (PSIG)
5019	▪ ▪ ▪ ▪	Gas	47
5020	▪ ▪ ▪ ▪	Gas	47
5021	▪ ▪ ▪ ▪	Gas	47
5022	▪ ▪ ▪ ▪	Gas	47
5023	▪ ▪ ▪ ▪	Gas	47
5024	▪ ▪ ▪ ▪	Gas	47
5025	▪ ▪ ▪ ▪	Gas	47
IA-39	Inst. Air to Cont.	Gas	47
PCV-1228	▪ ▪ ▪ ▪	Gas	47
E-2	Post Acc. Vent Exh.	Gas ⁽⁷⁾	47
E-1	▪ ▪ ▪ ▪	Gas ⁽⁷⁾	47
E-3	▪ ▪ ▪ ▪	Gas ⁽⁷⁾	47
E-5	▪ ▪ ▪ ▪	Gas ⁽⁷⁾	47
85A	Personnel Airlock	Gas	47
85B	▪ ▪	Gas	47
85C	▪ ▪	Gas ⁽⁷⁾	47
85D	▪ ▪	Gas ⁽⁷⁾	47
95A	Equipment Airlock	Gas	47
95B	Equipment Airlock	Gas	47
95C	▪ ▪	Gas ⁽⁷⁾	47
95D	▪ ▪	Gas ⁽⁷⁾	47

Table 4.4-1

Containment Isolation Valves

Valve No.	System ⁽¹⁾	Test Fluid ⁽²⁾	Minimum Test Pressure (PSIG)
4399	Sample Return to Cont. Sump.	Water ⁽⁴⁾	52
5132	" " "	Water ⁽⁴⁾	52

Notes:

1. System in which valve is located.
2. Gas test fluid indicates either nitrogen or air as test medium.
3. Testable only when at cold shutdown.
4. Isolation Valve Seal Water System.
5. Sealed by Residual Heat Removal System fluid.
6. Sealed by Service Water System. Either A or B valve(s) may serve as the required containment isolation valve(s) for the SWN-41, SWN-44 and SWN-71 series. Designation of the B valve(s) in the SWN-44 series requires the codesignation of the SWN-51 valve(s) associated with the penetration(s) as an additional required containment isolation valve(s).
7. Sealed by Weld Channel and Penetration Pressurization System.



UNITED STATES
NUCLEAR REGULATORY COMMISSION
WASHINGTON, D.C. 20555-0001

SAFETY EVALUATION BY THE OFFICE OF NUCLEAR REACTOR REGULATION
RELATED TO AMENDMENT NO. 200 TO FACILITY OPERATING LICENSE NO. DPR-26
CONSOLIDATED EDISON COMPANY OF NEW YORK, INC.
INDIAN POINT NUCLEAR GENERATING UNIT NO. 2
DOCKET NO. 50-247

1.0 INTRODUCTION

By letter dated August 21, 1996, as supplemented May 2, 1997, Consolidated Edison Company of New York, Inc., (the licensee) submitted a request to revise Section 3.3.G (Hydrogen Recombiner System (HRS) and Post-Accident Containment Venting System), the bases for Section 3.3.G, and Section 4.4, Table 4.4-1 (Containment Isolation Valves). This proposed change would allow removal of the existing flame-type hydrogen recombiners, its supporting equipment, and replacement with passive autocatalytic recombiners (PARs). Combustible gas within the Indian Point Nuclear Generating Unit No. 2 (IP2) containment is controlled by the HRS and the Post-Accident Containment Venting System. The HRS is designed to meet the requirements of GDC-41, 42, 43, and 10 CFR 50.44. These requirements define the design-basis case. For this case, there is an initial release of hydrogen caused by the reaction of the metal in the outside surfaces of the cladding cylinders surrounding the fuel with water and the hydrogen contained in the reactor coolant system. This initial hydrogen release to containment is not sufficient to approach the flammability limit of 4 volume percent. However, hydrogen generation continues because of radiolysis of water and the corrosion of materials in containment. The HRS is designed to prevent the hydrogen concentration from reaching the flammability limit. The supplemental letter provided additional information that was within the scope of the original application and did not change the staff's proposed no significant hazards consideration determination.

2.0 DISCUSSION AND EVALUATION

The HRS uses two redundant safety-related PARs to prevent the hydrogen concentration inside containment from reaching the flammability limit. PARs use palladium as a catalyst to combine hydrogen and oxygen molecules into water vapor. The PARs are passive in nature, with no moving parts, and are independent of the need for electrical power or any other support system. The recombiners are self-actuated in the presence of the reactants (hydrogen and oxygen). The PARs are designated Class A seismic.

In meeting the requirements of 10 CFR 50.44 to provide the capability for ensuring a mixed atmosphere in the containment, and the requirements of GDC-41 to provide systems as necessary to ensure that containment integrity is maintained, a system should be provided to mix the combustible gases within the containment. Mixing is ensured through the use of the

fancooler system. The IP2 Updated Final Safety Analysis Report (UFSAR), Section 6.4, describes the containment air recirculation cooling and filtration system. As shown in UFSAR Figure 6.4-1, flow is directed to various locations including locations high in the containment. Three to five fan-coolers operate in the post-accident environment. Each fan is rated at 65,000 cfm at accident conditions. Based on this, the UFSAR notes in 6.4.2.1.2, "The recirculation rate with five fans operating is approximately 7.5 containment volumes per hour." The recirculation rate with three fans is approximately 4.5 volumes per hour. The staff finds the capability of the containment air recirculation cooling and filtration system as described in Section 6.4 of the IP2 UFSAR to be sufficient for ensuring a mixed atmosphere in the containment.

The hydrogen release to containment is graphically presented in Figure 1 of Attachment B to the licensee's submittal, dated August 21, 1996. Table 1 of RG 1.7 defines values and assumptions that may be used to evaluate the production of combustible gases following a loss-of-coolant accident (LOCA). The assumptions used by the licensee in calculating the hydrogen release to containment are listed in Table 2 of Attachment B to the August 1996 submittal and are consistent with Table 1 of RG 1.7. The licensee stated, in a May 2, 1997, reply to the staff's request for additional information, that the COGAP hydrogen generation model was used which is the staff's confirmatory model. Therefore, the staff finds the assumptions and models used by the licensee to analyze hydrogen production to be acceptable.

The HRS consists of qualified passive devices that are not susceptible to single failures. However, to provide margin and increased containment coverage, two full-size PARs are provided and credit for only a single unit is assumed in the hydrogen analysis.

The depletion rate assumed in the analysis is based on testing conducted by Battelle Frankfurt and is described in the EPRI reports, "Qualification of Passive Autocatalytic Recombiners for Combustible Gas Control in ALWR Containments," dated April 8, 1993, and, "NIS Passive Autocatalytic Recombiner Depletion Rate Equation for Evaluation of Hydrogen Recombination During AP600 Design-Basis Accident," dated November 15, 1995. Subsequent testing conducted by EPRI and Electricite de France supports the conclusion of the Battelle testing as documented in EPRI Report TR-107517, Volumes I, 2, and 3, "Generic Model Tests of Passive Autocatalytic Recombiners (PARs) for Combustible Gas Control in Nuclear Power Plants," dated June 1997.

This testing was not conducted by IP2 or in accordance with IP2's quality assurance program. To address this condition, IP2 conducted confirmatory performance testing under its Appendix B quality assurance program at Wyle Laboratories. The test results are documented in Wyle Laboratory Report No. 45971-1, "Functional Testing and Radiation Exposure Test Report," which was forwarded to the staff via letter dated May 16, 1997. The test report supported the depletion rate assumed by IP2.

Hydrogen depletion tests of a scaled PAR were performed at Sandia National Laboratories, under the sponsorship and direction of the staff. The experiments were to confirm the hydrogen depletion rate of a PAR in the presence of steam and also to evaluate the effect of scale on the PAR performance for a variety of hydrogen concentrations. The results of these experiments are documented in NUREG/CR-6580, "Performance Testing of Passive Autocatalytic Recombiners," dated June 1998 and show that the depletion rate assumed by IP2 is acceptable.

The PARs are included in the IP2 Environmental Qualification (EQ) program and have been tested in accordance with IEEE 627 and 344. In a letter dated March 26, 1997, to the NRC, the staff concluded that the fission products that make up the post accident radiation environment must be addressed as possible catalytic poisons. Specifically, the fission products listed in Table 3.13 of NUREG-1465 should be addressed as possible poisons to the PAR catalyst. IP2's response to the staff's request, dated May 2, 1997, referenced the EPRI report, "The Effects of Inhibitors and Poisons on the Performance of Passive Autocatalytic Recombiners for Combustible Gas Control in ALWRs," dated April 30, 1997. The report combines qualitative information based on established chemical and physical principles with quantitative information from testing of catalysts systems subjected to a wide range of inhibitors and poisons. The report concludes that, "Even if the accident were to progress to beyond a DBA to substantial in-vessel damage, PAR recombination capacity would be reduced by no more than 25 percent."

The response also described a PAR test program being conducted in the "H2PAR" facility at the Cadarache Research Center by the French Nuclear Regulatory Agency IPSN 10. These tests attempt to subject a PAR to a severe accident atmosphere. Simulated fission product aerosols are released into the test facility by an induction furnace. Within the furnace oven, two dozen elements are being used to simulate a reactor core inventory. Among these elements are all of the elements in Groups 2, 3, and 4 of the radionuclide groups in NUREG-1465 (Group 1, the stable noble gases xenon and krypton, are not included because they are not chemically active). The testing supports the above EPRI conclusion that recombination capacity would be reduced by no more than 25%.

As part of the IP2 EQ testing, PAR cartridges were exposed to prototypic LOCA temperature, pressure and spray chemicals (2,000 ppm boron, buffered with trisodium phosphate to a pH of 8). This exposure caused the PAR to be initially slow to respond. However, the impact was temporary and functional acceptance criteria were met. It is noted in the qualification summary report that functional acceptance criteria were not met when the spray chemicals were buffered to a pH of 10. This is a much higher loading of trisodium phosphate than would be the case at IP2.

The post-accident radiation load on the containment may decompose polyvinyl chloride insulation and yield vapor phase sulfur species and halogen compounds capable of poisoning palladium surfaces. Sulfur oxides, sulfurous acid and hydrogen sulfide are expected in the containment post-accident environment. IP2 responded to this issue in the May 2, 1997, reply to the staff's request for additional information. The response stated that sulfur oxides and hydrogen sulfide were addressed in the EPRI report but sulfurous acid was not. IP2 noted that the use of polyvinyl chloride in containment is discouraged and the only cables containing polyvinyl chloride insulation inside containment are for two radiation monitors and motor bearing thermocouples for five fan coolers. This amount of cabling is not likely to be a significant source of potential poisons.

A more likely source is polymer chlorosulfonated polyethylene (CSPE) which is commonly used as a jacket material over electrical cables. To assess such effects, the EPRI report documented a test in which the recombination rate of a PAR model was measured after being exposed to the fumes from burning a length of CSPE jacketed cable beneath the PAR model. The PAR model was soaked in water prior to the fire exposure so that moisture needed to

produce acids such as hydrochloric and sulfurous acid would be present. The test showed a decrease in recombination rate of at most 10% but did not verify the amount or presence of acid. In order for the PAR to be exposed to acid created by the decomposition of cable jacketing it would most likely have to be washed from the cable trays by the containment sprays to the sump. Once in the sump it would be diluted and buffered by trisodium phosphate with the rest of the containment sump inventory. This solution may be steamed back into containment but at this point it would possess much less of a poisoning threat.

Based on the above reports, testing and substantial margin provided (the 4% flammability limit is not calculated to be exceeded even if the effectiveness of one PAR is reduced to 10% and the second installed PAR is not considered at all) the staff considers the issue of potential catalytic poisoning sufficiently addressed.

The PARs are located on the operating deck at an approximate elevation of 29 m (95 feet) outside the missile shield wall. This location is away from the reactor coolant piping and possible impingement from high flows due to line breaks.

IP2 described, in a May 2, 1997, reply to the staff's request for additional information, the surveillance performance testing for the HRS. A surveillance bench test is performed on a sample plate from each PAR every refueling outage to confirm continued satisfactory performance in accordance with Technical Specification 4.5.C.2. An individual plate is inserted into a test chamber and a known flow of 1 %-hydrogen-in-air is injected into the chamber. The plate outlet temperature is measured and compared with measurements on new plates. The plate is judged to be undegraded if the temperature developed is within the acceptance criteria. The staff finds the proposed technical specifications and surveillance testing acceptable.

The staff evaluated the HRS to determine if the design conformed to the regulations and standards in Section 6.2.5 of the SRP. IP2 calculates the design-basis LOCA hydrogen production rate in accordance with RG 1.7. The HRS design meets the standards for independence, redundancy, inspection, and quality as given in GDC 41, 42 and 43. IP2's analysis of design-basis LOCA containment hydrogen concentration with a single failure of the HRS shows that the hydrogen concentration will not reach its 4 percent flammability limit. Based on its review, the staff finds that the design conforms to the regulations and standards in SRP Section 6.2.5.

3.0 STATE CONSULTATION

In accordance with the Commission's regulations, the New York State official was notified of the proposed issuance of the amendment. The State official had no comments.

4.0 ENVIRONMENTAL CONSIDERATION

The amendment changes a requirement with respect to installation or use of a facility component located within the restricted area as defined in 10 CFR Part 20 and changes surveillance requirements. The NRC staff has determined that the amendment involves no significant increase in the amounts, and no significant change in the type, of any effluents that may be released offsite, and that there is no significant increase in individual or cumulative

occupational radiation exposure. The Commission has previously issued a proposed finding that the amendment involves no significant hazards consideration (62 FR 4345), and there has been no public comment on such finding. Accordingly, the amendment meets the eligibility criteria for categorical exclusion set forth in 10 CFR 51.22(c)(9). Pursuant to 10 CFR 51.22(b), no environmental impact statement or environmental assessment need be prepared in connection with the issuance of the amendment.

5.0 CONCLUSION

The Commission has concluded, based on the considerations discussed above, that: (1) there is reasonable assurance that the health and safety of the public will not be endangered by operation in the proposed manner, (2) such activities will be conducted in compliance with the Commission's regulations, and (3) the issuance of the amendment will not be inimical to the common defense and security or to the health and safety of the public.

Principal Contributor: M. Snodderly

Date: April 27, 1999

DATED: April 27, 1999

AMENDMENT NO. 200 TO FACILITY OPERATING LICENSE NO. DPR-26-INDIAN POINT
UNIT 2

~~Docket File~~

PUBLIC

PDI Reading

J. Zwolinski/S. Black

S. Bajwa

S. Little

J. Harold

C. Berlinger

M. Snodderly

OGC

G. Hill (2), T-5 C3

W. Beckner, 013/H15

ACRS

R. Norsworthy (e-mail SE, only)

J. Rogge, Region I

cc: Plant Service list