

21
300
REC.

21
300
REC.

21
300
REC.



SOUTHWEST RESEARCH INSTITUTE

P. O. DRAWER 28510
SAN ANTONIO, TEXAS 78228-0510

IWPE LAB NOTEBOOK 019

LOCALIZED CORROSION EXPTS.

11/90 - 3/92



SOUTHWEST RESEARCH INSTITUTE

6220 CULEBRA ROAD
POSTAL DRAWER 28510
SAN ANTONIO, TEXAS 78228-0510

MAGNETIC STORAGE

MEDIA INSIDE

**CNWRA
CONTROLLED
COPY 019**

page	9	Cyclic Polarization of 316L SS; $Cl=1000$; $NO_3=10,000$; $F=2$; $SO_4=20$	STMX 17
11	"	" " " " ; $Cl=6$; $NO_3=10$; $F=2$; $SO_4=20$	STMX 18
13	"	" " " " ; " " " " " "	STMX 19
15	"	" " " " ; $Cl=20$; $NO_3=10$; $F=2$; $SO_4=20$	STMX 20
17	"	" " " " " " " "	STMX 21
19	"	" " " " " " " "	STMX 22
21	"	" " " " ; $Cl=100$; $NO_3=10$; $F=2$; $SO_4=20$	STMX 23
23	"	" " " " ; " " " " " "	STMX 24
25	"	" " " " ; " " " " " "	STMX 25
27	"	" " " " ; $Cl=300$; $NO_3=10$; $F=2$; $SO_4=20$	STMX 26
29	"	" " " " ; " " " " " "	STMX 27
31	"	" " " " ; " " " " " "	STMX 28
33	Cyclic Polarization of Inc 825; $Cl=1000$; $HCO_3=1000$; $NO_3=10$; $SO_4=20$; $F=2$	STMX 29	
35	"	" " " " ; $Cl=1000$; $HCO_3=2000$; $NO_3=10$; $SO_4=20$; $F=2$	STMX 30
37	"	" " " " ; $Cl=1000$; $SO_4=20,000$; $NO_3=10$; $F=2$; $HCO_3=85$	STMX 31
39	Cyclic Polarization of 316L SS; $Cl=1000$; $NO_3=10$; $SO_4=20$; $F=2$; $HCO_3=85$	STMX 32	
41	"	" " " " ; $Cl=1000$; $NO_3=1000$; $SO_4=20$; $F=2$; $HCO_3=85$	STMX 33
43	"	" " " " ; $Cl=1000$; $SO_4=20,000$; $NO_3=10$; $F=2$; $HCO_3=85$	STMX 34
45	"	" " " " ; " " " " " " " " 60°C	STMX 35
47	"	" " " " ; $Cl=1000$; $HCO_3=2000$; $SO_4=20$; $NO_3=10$; $F=2$	STMX 36
51	49	" " " " ; $Cl=1000$; $NO_3=10$; $SO_4=20$; $F=2$; $HCO_3=85$; $CO_2=1atm$ 60°C	STMX 37
49	"	" " " " ; $Cl=1000$; $NO_3=1000$; $SO_4=20$; $F=2$; $HCO_3=85$ 60°C	STMX 38
53	"	" " " " ; $Cl=1000$; $NO_3=10$; $SO_4=20$; $F=2$; $HCO_3=85$; 95°C; $CO_2=1atm$	STMX 39
55	"	" " " " ; $Cl=1000$; $NO_3=10$; $F=2$; $SO_4=20$; $HCO_3=85$; 95°C; CO_2	STMX 39
57	"	" " " " Inc 825; $Cl=6$; $NO_3=10$; $F=2$; $SO_4=20$; $HCO_3=85$; 95°C; CO_2	STMX 40
59	"	" " " " Inc 825; $Cl=1000$; $NO_3=10$; $F=2$; $SO_4=20$; $HCO_3=85$; 95°C; CO_2	STMX 41
61	"	" " " " Inc 825; $Cl=1000$; $NO_3=10$; $F=2$; $SO_4=20$; $HCO_3=2000$; 95°C	STMX 42
65	63	" " " " CDA 102; $Cl=6$; $NO_3=10$; $F=2$; $SO_4=20$; $HCO_3=85$; 60°C	STMX 43
67	65	" " " " CDA 102; $Cl=6$; $NO_3=10$; $F=2$; $SO_4=20$; $HCO_3=8500$; 60°C	STMX 44
63	Preparation of NO_3 stock solution 1000 ppm SN CARIWA 019-63		
69	Cyclic Polarization of CDA 102; $Cl=1000$; $HCO_3=85$; $NO_3=10$; $SO_4=20$; $F=2$ 95°C	STMX 45	
71	"	" " " " ; $SO_4=1000$; $Cl=6$; $NO_3=10$; $SO_4=20$; $F=2$; $HCO_3=85$ 60°C	STMX 46
73	"	" " " " ; $Cl=6$; $NO_3=10$; $SO_4=20$; $F=2$; $HCO_3=85$; 60°C	STMX 47
75	"	CDA 715; $Cl=6$; $NO_3=10$; $SO_4=20$; $F=2$; $HCO_3=85$ 60°C	STMX 48
77	"	CDA 715; $HCO_3=8500$; $Cl=6$; $NO_3=10$; $SO_4=20$; $F=2$ 60°C	STMX 49
79	"	" " " " ; $SO_4=1000$; $Cl=6$; $NO_3=10$; $F=2$; $HCO_3=85$ 60°C	STMX 50

Potentiostat/Galvanostat used in these experiments are PARC Model 273 Potentiostat, S/N

Also, PARC 173 Potentiostat w/276 interface, S/N 62101
Calibrated 25 Oct 90, due 25 Oct 91.

For reference voltage checks + other electronic measurements a Keithley 602 electrometer (S/N 19831), cal'd 11/21/89 due 11/21/90 was used. Also a Keithley 614 electrometer (S/N 467374) cal'd 6/6/90 due 12/6/90.
Two fluke DVM's, Model 8050A S/N 5005110 cal'd 30 May 90, due 30 May 91, and S/N 5005078 cal'd 29 May 90, due 29 May 91.

For pH + specific ion measurements: Orion EA 920 meter S/N TV64A, cal'd vs standards prior to each use.

For weights: Mettler AE 240 electronic balance S/N 10237 cal'd 7/15/90, due 1/91.

Also for pH/ion: Orion 720A S/N 003368

Calomel Reference Electrodes: Fisher #13-620-51

pH electrode combo-Ag/AgCl: " #13-620-90

" " Orion 8103 Ross: Fisher #13-641-817


Orion chloride electrode: Fisher #13-641-875

Orion double JCT reference: " #13-641-900

Dimensional checks: Fisher micrometer S/N 20-M-1 cal'd 10/19/90, due 4/19/91. Fowler caliper S/N 20-8C-1, cal'd 5/30/90, due 11/30/90.

Fisher Buffer Solution	{	pH 1	lot # 890199-18
NBS traceable - certified		pH 7	" 891429-24
		pH 10	" 890043-24
		pH 4	" 890174-24

STMX 17
CYCLIC POLN



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
STMX 17
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.059
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-495
4
5592.51
.0123183
.0123183
5592.51

LEGEND

STATISTICAL MATRIX ON 316L SS
INTERMEDIATE RUN 95C 1ST REP'N
CL=1000;NO3=10000;F=2;S04=20
DE-AERATE W/ARGON
DONE ON PARC 173/276

21 NOV 1990

Cyclic Polarization of 316L SS
Model Solution: $CL=1000$; $NO_3=10,000$; $F=2$; $S04=20$
STMX 17

Purpose: To collect data for evaluation of effects of various selected ionic species on the corrosion of 316L SS using a factorial experiment.

The test specimen was a cylindrical one fabricated from 316L SS (heat no: P 80746) at SWRT machine shop. Procedures generally followed ASTM G-61 for these cyclic polarization tests. The specimen was wet polished w/220 grit followed by 600 grit. It was then degreased & cleaned according to G-61. The test cell was as described in TOP-009. A long salt bridge filled with 0.5N NaCl & having a Vycor tip was used to connect the SCE reference electrode which was in a separate beaker. All surfaces of the specimen were polished to get a uniform surface in an attempt to minimize crevice corrosion. Test follows TOP-008 guidelines. Test solution prep: To 500 ml of 17MΩ water in a 1-liter volumetric add 0.1224 g NaHCO₃, 1.6464 g NaCl, 1.4789 g Na₂SO₄, and 13.7927 g NaNO₃ (Fisher lot #1S 886728, 885407, 901213, & 897183 respectively). Pipet 2.0 ml of F stock solution #013-107. Dilute to the mark.

Reference SCE #4 was used & checked vs. another before & after the test, difference was less than 1.0 mV.


Spec. Dim: $\phi = 0.627$ cm $l = 1.904$ cm $A = 4.059$ cm²

- ① Spec pre-passivated per TOP-009; all surfaces polished to 600 grit
- ② Spec held at open circuit for one hour before start.
- ③ E can at start -495 mV vs SCE
- ④ E Pt 10 min. before start -300 mV
- ⑤ Initial Temp. 95.4°C Final Temp 95.0°C
- ⑥ Initial pH 2.94 @ 25°C Final pH 9.68 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge (99.999%)
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 $\mu A/cm^2$

Specimen had no pitting or crevice corrosion - still retained its metallic luster. Solution remained water clear.

Stored on disk EDA #3.

Walter J. Machowski
11/21/90

STMX 18
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (MV)
VERTEX E (MV)
FINAL E (MV)
SCAN RATE (MV/S)
THRESHOLD I (UA/CM²)
CONDITION E (MV)
CONDITION T (S)
INIT DELAY (MV/S OR S)

CYCLIC POLN
STMX 18
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA (CMS²)
EQ WT (GM)
DENSITY (GM/CM³)
CATHODIC TAFEL (MV)
ANODIC TAFEL (MV)

4.114
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-454
4
2887.701
-1.458435E-02
4.861449E-03
2887.701

LEGEND

STATISTICAL MATRIX ON 316L SS
INTERMEDIATE RUN 95C 1ST REP'N
CL=6; NO3=10; F=2; SO4=20
DE-AERATE W/ARGON
DONE ON PARC 173/276

CL=3.6 ←
actual conc.
due to pipetting error
4/17/91 WJM

26 NOV 1990

Cyclic Voltammetry of 316L SS
Model Solution: CL=6; NO₃=10; F=2; SO₄=20
STMX 18 CL=3.6 wjm 4/17/91

Purpose: Same as STMX 17 (p. 9)

The test specimen, procedures, etc were as described on p. 9 in STMX 17. Ref SCE #4 was used and checked before & after the test, difference was less than 1.0 mV.

Test Solution Prep: To 500 ml of 17M₂ water in a 1-liter volumetric add 0.1221 g of NaHCO₃ (lot # 886728 - Fisher). Also pipet 6.0 ml of CL stock, 10.0 ml of NO₃ stock, and 2.0 ml of F stock solutions #013-107. Pipet 20.0 ml of SO₄ stock solution #013-269. Dilute to the mark.


Spec. Dim: $\phi = 0.634$ cm $l = 1.907$ cm $A = 4.114$ cm²

- ① Spec pre-passivated per 102-009; all surfaces polished to 600 grit
- ② Spec held at open circuit for one hour before start
- ③ E corr at start -456 mV vs SCE
- ④ E Pt 10 min before start -155 mV.
- ⑤ Initial Temp. 95.2°C Final Temp. 95.0°C
- ⑥ Initial pH 8.42 @ 25°C Final pH 10.10 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/-hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Manual reverse @ 11, 350 μ A / +1652 mV

Specimen was not pitted or discolored. Still retained its metallic luster. Solution remained water clear.

Stored on disk ECR #3.

Walter J. Mochnowski
11/26/90



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	STMX 19
INITIAL E (MV)	0 VS E
VERTEX E (MV)	100 VS E
FINAL E (MV)	100 VS E
SCAN RATE (MV/S)	.17
THRESHOLD I (UA/CM^2)	5000
CONDITION E (MV)	PASS
CONDITION T (S)	PASS
INIT DELAY (MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA (CMS^2)	4.091
EQ WT (GM)	PASS
DENSITY (GM/CM^3)	PASS
CATHODIC TAFEL (MV)	PASS
ANODIC TAFEL (MV)	PASS

DATA SCALE

ECORR	-625
MV/PT	4
DATA MAX	2813.493
DATA MIN	-50.06111
ABS MIN	2.199951E-02
ABS MAX	2813.493

LEGEND

STATISTICAL MATRIX ON 316L SS
INTERMEDIATE RUN 95 C 2ND REP'N
CL=6; NO3=10; F=2; SO4=20
DE-AERATE W/ARGON
DONE ON PARC 173/276

CL=3.6 ←
(see STMX 18)

27 NOV 1990

Cyclic Polarization of 316L SS
Model Solution: $Cl=6$; $NO_3=10$; $F=2$; $SO_4=20$
STMX 19 CL=3.6 w/SM 4/17/91

Purpose: Same as STMX 17 (p. 9)

The test specimen, procedures, etc were as described in STMX 17 (p. 9). Ref SCE #4 was used and checked vs. another before & after test, difference was less than 1.0 mV.

Test Solution prep: Prep was as described in STMX 18 (p. 11) except weight of $NaHCO_3$ was 0.1225 g.

Spec. dim: $\phi = 0.633$ cm $l = 1.899$ cm $A = 4.091$ cm²


- ① Spec. pre-passivated per 708-009; all surfaces polished to 600 grit
- ② Spec. held at open circuit for one hour before start
- ③ E scan at start -626 mV vs SCE
- ④ E Pt 10 min before start -192 mV
- ⑤ Initial Temp. 95.0°C Final Temp 95.5°C
- ⑥ Initial pH 8.24 @ 25°C Final pH 9.90 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Manually reversed @ 11,700 μA / +1653 mV

Specimen was not pitted or discolored. Still retained its metallic luster. Solution remained water clear.

Stored on disk EA+C #3.

Walter J. Machowski
11/27/90

STMX 20
CYCLIC POLN



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	STMX 20
INITIAL E(MV)	0 VS E
VERTEX E(MV)	100 VS E
FINAL E(MV)	100 VS E
SCAN RATE(MV/S)	.17
THRESHOLD I(UA/CM^2)	5000
CONDITION E(MV)	PASS
CONDITION T(S)	PASS
INIT DELAY(MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA(CMS^2)	4.081
EQ WT(GM)	PASS
DENSITY(GM/CM^3)	PASS
CATHODIC TAFEL(MV)	PASS
ANODIC TAFEL(MV)	PASS

DATA SCALE

ECORR	-647
MV/PT	4
DATA MAX	2984.563
DATA MIN	-3.185494E-02
ABS MIN	7.35114E-03
ABS MAX	2984.563

LEGEND

STATISTICAL MATRIX ON 316L SS
INTERMEDIATE RUN; TRIAL #3; REP'N #1
CL=20; NO3=10; F=2; SO4=20; T=95C
DE-AERATE W/ARGON
DONE ON PARC 173/276

28 NOV 1990

Cyclic Polarization of 316L SS
Model Solution: CL=20; NO₃=10; F=2; SO₄=20

STMX 20

Purpose: Same as STMX 17 (p.9)

The test specimen, procedures, etc. were as described in STMX 17 (p.9). Ref SCE #4 was used and checked before & after test, difference was less than 1.5 mV.

Test Solution Prep: Prep was as in STMX 18 (p.11) except that 20.0 ml of CL stock was used, and the actual wt. of NaHCO₃ was 0.1222 g.

Spec. Dim: $\phi = 0.633 \text{ cm}$ $l = 1.894 \text{ cm}$ $A = 4.081 \text{ cm}^2$


- ① Spec pre-passivated per TOS-009; all surfaces polished to 600 grit
- ② Spec held at open circuit for one hour before start
- ③ E_{corr} at start -647 mV vs SCE
- ④ E_{pt} 10 min before start -123 mV
- ⑤ Initial Temp. 95°C Final Temp. 95.0°C
- ⑥ Initial pH 8.42 @ 25°C Final pH 9.84 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Manually Reversed 12,180 μA / +1677 mV

Specimen was not pitted or discolored - still retained its 'metallic luster'. Solution remained water clear.

Stored on disk EC+G #3.

Walter J. Macrowski
11/28/90

STMX 21
CYCLIC POLN



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	STMX 21
INITIAL E(MV)	0 VS E
VERTEX E(MV)	100 VS E
FINAL E(MV)	100 VS E
SCAN RATE(MV/S)	.17
THRESHOLD I(UA/CM^2)	5000
CONDITION E(MV)	PASS
CONDITION T(S)	PASS
INIT DELAY(MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA(CMS^2)	4.099
EQ WT(GM)	PASS
DENSITY(GM/CM^3)	PASS
CATHODIC TAFEL(MV)	PASS
ANODIC TAFEL(MV)	PASS

DATA SCALE

ECORR	-652
MV/PT	4
DATA MAX	2173.701
DATA MIN	-1.463772E-02
ABS MIN	1.463772E-02
ABS MAX	2173.701

LEGEND

STATISTICAL MATRIX ON 316L SS
INTERMEDIATE RUN; TRIAL #3; REP 'N #2
CL=20; NO3=10; F=2; SO4=20; T=95C
DE-AERATE W/ARGON
DONE ON PARC 173/276

29 NOV 1990

Cyclic Polarization of 316L SS
Model Solution: CL=20; NO₃=10; F=2; SO₄=20

STMX 21

Purpose: Same as STMX 17(p.9)

The test specimen, procedures, etc. were as described in STMX 17(p.9). Ref SCE #4 was used, a check vs another both before & after test showed a difference less than 1.0 mV.

Test Solution Prep: Solution was prepared as in STMX 20, except actual amt. of NaHCO₃ added was 0.1330 g.


Spec. Dim: $\phi = 0.633 \text{ cm}$ $l = 1.903 \text{ cm}$ $A = 4.099 \text{ cm}^2$

- ① Spec pre-passivated per 708-009; all surfaces polished to 600 grit.
- ② Spec held at open circuit for one hour before starting.
- ③ E corr at start -650 mV vs SCE
- ④ E Pt 10 min. before start -150 mV.
- ⑤ Initial Temp. 95.5°C Final Temp. 95.2°C
- ⑥ Initial pH 8.24 @ 25°C Final pH 9.72 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Manually reversed @ 8400 μA / +1650 mV

Specimen was not pitted & had only very slight coloration. Solution remained water clear.

Stored on disk EP+6 #3.

Walter J. MacKowski
11/29/90



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	STMX 22
INITIAL E(MV)	0 VS E
VERTEX E(MV)	100 VS E
FINAL E(MV)	100 VS E
SCAN RATE(MV/S)	.17
THRESHOLD I(UA/CM^2)	5000
CONDITION E(MV)	PASS
CONDITION T(S)	PASS
INIT DELAY(MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA(CMS^2)	4.086
EQ WT(GM)	PASS
DENSITY(GM/CM^3)	PASS
CATHODIC TAFEL(MV)	PASS
ANODIC TAFEL(MV)	PASS

DATA SCALE

ECORR	-622
MV/PT	4
DATA MAX	1529.613
DATA MIN	-1.1468429
ABS MIN	1.223691E-02
ABS MAX	1529.613

LEGEND

STATISTICAL MATRIX ON 316L SS
INTERMEDIATE RUN; TRIAL #3; REP'N #3
CL=20; NO3=10; F=2; SO4=20; T=95C
DE-AERATE W/ARGON
DONE ON PARC 173/276

Cyclic Polarization of 316L SS
Model Solution: CL=20; NO3=10; F=2; SO4=20

STMX 22

Purpose: Same as STMX 17(p.9).

The test specimens, procedures, etc were as described in STMX 17(p.9). Ref SCE #4 was used, and checked w/another before & after test; difference was less than 10mV.

Test Solution Prep: Solution was prepared as in STMX 20, except actual wt. of NaHCO₃ added was 0.1221 g.

Spec Dim: $\phi = 0.632 \text{ cm}$ $l = 1.900 \text{ cm}$ $A = 4.086 \text{ cm}^2$


- ① Spec pre-passivated per 709-009; all surfaces polished to 600 grit
- ② Spec held at open circuit for one hour before starting
- ③ E can at start -620 mV vs SCE
- ④ E Pt 10 min before start -193 mV
- ⑤ Initial Temp 95.2°C Final Temp 95.2°C
- ⑥ Initial pH 8.27 @ 25°C Final pH 10.02
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Manually reversed @ +1650 mV / current unknown - display went out

Reverse scan cut off too soon - no intersection obtained.

Specimen had two pits - one at each edge (bottom + top)
Solution was essentially water clear.

Stored on disk E6+C # 3.

Walter J. Machowski
12/3/90



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
STMX 23
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.083
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-656
4
5682.096
-4.898359E-02
4.898359E-02
5682.096

LEGEND

STATISTICAL MATRIX ON 316L SS
INTERMEDIATE RUN; TRIAL #4; REP'N #1
CL=100; NO3=10; F=2; SO4=20; 95 C
DE-AERATE W/ARGON
DONE ON PARC 173/276

Aplic Polairization of 316L SS
Model Solution: CL=100; NO₃=10; F=2; SO₄=20

STMX 23

Purpose: Same as STMX 17 (p.9).

The test specimen, procedures, etc were as described in STMX 17 (p.9). Ref SCE #4 was used & checked as another before & after test, difference was less than 0.5 mV.

Test Solution Prep: To 500 ml of 17M de water in a 1-liter volumetric add 0.1220 g NaHCO₃ and 0.1646 g NaCl (Fisher Dist #1's 886728 + 885407). Pipet 10.0 ml of NO₃ stock & 20 ml of F stock solutions #013-107. Pipet 20.0 ml of SO₄ stock solution #013-269, dilute to the mark.

Spec. Dim: $\Phi = 0.633 \text{ cm}$ $l = 1.895 \text{ cm}$ $A = 4.083 \text{ cm}^2$


- ① Spec pre-passivated per TOP-009; all surfaces polished to 600 grit
- ② Spec held at open circuit for one hour before starting
- ③ E cor at start -659 mV vs SCE
- ④ E Pt 10 min. before start -122 mV
- ⑤ Initial Temp 95.2°C Final Temp 94.8°C
- ⑥ Initial pH 8.29 @ 25°C Final pH 9.72 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 $\mu\text{A/cm}^2$

Specimen had shallow, small pits (evident when probed) and some crevice corrosion. During test, specimen was covered w/ green fuzzy material. Solution had a hazy greenish cast.

Stored on disk ECR # 3

Walter J. Macfowick
12/4/90

STMX 24
CYCLIC POLN



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	STMX 24
INITIAL E (MV)	0 VS E
VERTEX E (MV)	100 VS E
FINAL E (MV)	100 VS E
SCAN RATE (MV/S)	.17
THRESHOLD I (UA/CM^2)	5000
CONDITION E (MV)	PASS
CONDITION T (S)	PASS
INIT DELAY (MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA (CMS^2)	4.006
EQ WT (GM)	PASS
DENSITY (GM/CM^3)	PASS
CATHODIC TAFEL (MV)	PASS
ANODIC TAFEL (MV)	PASS

DATA SCALE

ECORR	-657
MV/PT	4
DATA MAX	6590.115
DATA MIN	-1.127309
ABS MIN	6.490265E-02
ABS MAX	6590.115

LEGEND

STATISTICAL MATRIX ON 316L SS
INTERMEDIATE RUN; TRIAL #4; REP'N #2
CL=100; NO3=10; F=2; SO4=20; 95 C
DE-AERATE W/ARGON
DONE ON PARC 173/276

Cyclic Polarization of 316L SS

Model Solution: CL=100; NO₃=10; F=2; SO₄=20

STMX 24

Purpose: Same as STMX 17 (p. 9).

The test specimen, procedures, etc. were as described in STMX 17 (p. 9). Ref SCE #4 was used; a check before & after test vs. another SCE showed a difference less than 0.5 mV.

Test Solution Prep: The test solution was prepared as described in STMX 23 (p. 21), except actual weights were 0.1223 g NaHCO₃ and 0.1648 g NaCl. The same lot #'s were used.


Spec. Dim: $\phi = 0.627$ cm $l = 1.891$ cm $A = 4.006$ cm²

- ① Spec pre-passivated per 100-009; all surfaces polished to 600 grit
- ② Spec held at open circuit for one hour before starting.
- ③ E scan at start -659 mV vs SCE
- ④ E Pt 10 min before start -115 mV
- ⑤ Initial Temp. 95.2°C Final Temp. 95.0°C
- ⑥ Initial pH 8.27 @ 25°C Final Temp. pH 9.79 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr) 12/5/90 WJM
- ⑧ Argon purge
- ⑨ done on PARC 173/276
- ⑩ Auto reverse @ 5000 μ A/cm²

Specimen and solution were exactly like STMX 23 (p. 21).

Stored on disk EPOD #3.

Walter J. Macpherson
12/5/90



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	STMX 25
INITIAL E(MV)	0 VS E
VERTEX E(MV)	100 VS E
FINAL E(MV)	100 VS E
SCAN RATE(MV/S)	.17
THRESHOLD I(UA/CM^2)	5000
CONDITION E(MV)	PASS
CONDITION T(S)	PASS
INIT DELAY(MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA(CMS^2)	4.078
EQ WT(GM)	PASS
DENSITY(GM/CM^3)	PASS
CATHODIC TAFEL(MV)	PASS
ANODIC TAFEL(MV)	PASS

DATA SCALE

ECORR	-638
MV/PT	4
DATA MAX	6375.674
DATA MIN	.2403139
ABS MIN	.2403139
ABS MAX	6375.674

LEGEND

STATISTICAL MATRIX ON 316L SS
INTERMEDIATE RUN; TRIAL #4; REP'N #3
CL=100; NO3=10; F=2; SO4=20; 95 C
DE-AERATE W/ARGON
DONE ON PARC 173/276

Cyclic Polarization of 316L SS

Model Solution: CL=100; NO₃=10; F=2; SO₄=20

STMX 25

Purpose: Same as STMX 17 (p.9).

The test specimen, procedures, etc were as described in STMX 17 (p.9). Ref SCE #4 was used; a check vs. another before & after the test showed a difference of less than 0.5 mV.

Test Solution Prep: The test solution was prepared as described in STMX 23 (p.21) using the same chemicals & solutions. Actual weight of NaHCO₃ was 0.1222 g and of NaCl was 0.1649 g.


Spec. Dim: $\phi = 0.632 \text{ cm}$ $l = 1.896 \text{ cm}$ $A = 4.078 \text{ cm}^2$

- ① Spec. pre-passivated per TOS-009; all surfaces polished to 600 grit.
- ② Spec. held at open circuit for one hour before starting
- ③ E can at start -639 mV vs SCE
- ④ E Pt 10 min. before start -214 mV
- ⑤ Initial Temp. 95.5°C Final Temp. 95.5°C
- ⑥ Initial pH 8.14 @ 55°C Final pH 9.76 @ 55°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$

Specimen and solution appeared similar to STMX 23 (p.21).

Stored on disk ECH #3.

Walter J. Macrowski
12/6/90



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	STMX 26
INITIAL E (MV)	0 VS E
VERTEX E (MV)	100 VS E
FINAL E (MV)	100 VS E
SCAN RATE (MV/S)	.17
THRESHOLD I (UA/CM²)	5000
CONDITION E (MV)	PASS
CONDITION T (S)	PASS
INIT DELAY (MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA (CMS²)	4.103
EQ WT (GM)	PASS
DENSITY (GM/CM³)	PASS
CATHODIC TAFEL (MV)	PASS
ANODIC TAFEL (MV)	PASS

DATA SCALE

ECORR	-661
MV/PT	4
DATA MAX	7214.233
DATA MIN	-499.1469
ABS MIN	.131611
ABS MAX	7214.233

LEGEND

STATISTICAL MATRIX ON 316L SS
INTERMEDIATE RUN; TRIAL #5; REP'N #1
CL=300; NO3=10; F=2; SO4=20; 95 C
DE-AERATE W/ARGON
DONE ON PARC 173/276

Cyclic Polarization of 316L SS
Model solution: CL=300; NO₃=10; F=2; SO₄=20

STMX 26

Purpose: Same as STMX 17 (p.9).

The test specimen, procedures, etc. were as described in STMX 17 (p.9). Ref. SCE #4 was used, a check vs another before & after the test showed a difference of 0.5 mV.

Test solution prep: The test solution was prepared as described in STMX 23 (p.21) except that 0.4947 g of NaCl was added to achieve a 300 ppm Cl⁻ concentration. 0.1233 g of NaHCO₃ were used. Same chemical and solution lot #'s and solution #'s were used.


Spec. Dim: $\phi = 0.633 \text{ cm}$ $l = 1.905 \text{ cm}$ $A = 4.103 \text{ cm}^2$

- ① Spec. pre-passivated per T08-009; all surfaces polished to 600 grit
- ② Spec. held at open circuit for one hour before start
- ③ E corr at start -660 mV vs SCE
- ④ E Pt 10 min before start -116 mV
- ⑤ Initial Temp. 95.0°C Final Temp. 95.0°C
- ⑥ Initial pH 8.12 @ 35°C Final pH 9.70 @ 35°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$

Specimen had some shallow, small pits which were made evident by probing. Some crevice corrosion had occurred. Solution was tinged green w/ a greenish gelatinous precipitate.

Stored on disk E04A #3.

Walter J. Machowski
12/7/90



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	STMX 27
INITIAL E(MV)	0 VS E
VERTEX E(MV)	100 VS E
FINAL E(MV)	100 VS E
SCAN RATE(MV/S)	.17
THRESHOLD I(UA/CM^2)	5000
CONDITION E(MV)	PASS
CONDITION T(S)	PASS
INIT DELAY(MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA(CMS^2)	4.072
EQ WT(GM)	PASS
DENSITY(GM/CM^3)	PASS
CATHODIC TAFEL(MV)	PASS
ANODIC TAFEL(MV)	PASS

DATA SCALE

ECORR	-607
MV/PT	4
DATA MAX	6213.163
DATA MIN	-5.029469
ABS MIN	1.473477E-02
ABS MAX	6213.163

LEGEND

STATISTICAL MATRIX ON 316L SS
INTERMEDIATE RUN; TRIAL #5; REP'N #2
CL=300; NO3=10; F=2; SO4=20; 95 C
DE-AERATE W/ARGON
DONE ON PARC 173/276

Cyclic Polarization of 316L SS
Model Solution: CL=300; NO₃=10; F=2; SO₄=20
STMX 27

Purpose: Same as STMX 17(p.9).

The test specimen, procedures, etc were as described in STMX 17(p.9). Ref SCE #4 was used & checked before & after test, difference vs. another SCE was less than 10 mV.

Test Solution Prep: The test solution was prepared as described in STMX 26(p.27). Actual salt weights were 0.1226g NaHCO₃ and 0.4944g NaCl. Same lot #'s and solution #'s used.


Spec. Dim: $\phi = 0.630$ cm $l = 1.900$ cm $A = 4.072$ cm²

- ① Spec pre-passivated per 008-009; all surfaces polished to 600 grit
- ② Spec held at open circuit for one hour before start
- ③ E corr at start -608 mV vs SCE
- ④ E Pt 10 min before start -180 mV
- ⑤ Initial Temp 95.5°C Final Temp 95.0°C
- ⑥ Initial pH 8.20 @ 25°C Final pH 9.73 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 μ A/cm²

Specimen had small, shallow pits as in STMX 26. Some crevice corrosion had occurred. Solution had a greenish tinge with a small amount of greenish precipitate.

Stored on disk EPD #3.

Walter J. MacKowski
12/10/90



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	STMX 28
INITIAL E (MV)	0 VS E
VERTEX E (MV)	100 VS E
FINAL E (MV)	100 VS E
SCAN RATE (MV/S)	.17
THRESHOLD I (UA/CM ²)	5000
CONDITION E (MV)	PASS
CONDITION T (S)	PASS
INIT DELAY (MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA (CMS ²)	4.061
EQ WT (GM)	PASS
DENSITY (GM/CM ³)	PASS
CATHODIC TAFEL (MV)	PASS
ANODIC TAFEL (MV)	PASS

DATA SCALE

ECORR	-578
MV/PT	4
DATA MAX	6008.373
DATA MIN	-.1674464
ABS MIN	2.462448E-03
ABS MAX	6008.373

LEGEND

STATISTICAL MATRIX ON 316L SS
INTERMEDIATE RUN; TRIAL #5; RUN #3
CL=300; NO3=10; F=2; SO4=20; 95 C
DE-AERATE W/ARGON
DONE ON PARC 173/276

Cyclic Polarization of 316L SS
Model Solution: CL = 300; NO₃ = 10; F = 2; SO₄ = 20

STMX 28

Purpose: same as STMX 17(p.9).

The test specimen, procedures, etc. were as described in STMX 17(p.9). Ref SCE #4 was used & checked vs. another before & after test; difference was less than 1.0 mV.

Test Solution Prep: The test solution was prepared as described in STMX 26(p.27). Actual salt weights were 0.1230g NaHCO₃ and 0.4944g NaCl. Same lot #'s and solution #'s were used.


Specimen: $\phi = 0.629$ cm $l = 1.898$ cm $A = 4.061$ cm²

- ① Spec. pre-passivated per VOP-009; all surface polished to 600 grit
- ② Spec held at open circuit for one hour before start
- ③ E cor at start -578 mV vs SCE
- ④ E PT 10 min before start -198 mV
- ⑤ Initial Temp 95.0°C Final Temp 95.0°C
- ⑥ Initial pH 8.13 @ 55°C Final pH 9.65 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 μ A/cm²

Specimen & solution were similar to STMX 27.

Stored on disk EA+C-#3.

Walter J. MacKwarth
12/12/90

STMX 29
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
STMX 29
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.144
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-512
4
6008.687
-.2775097
1.930502E-03
6008.687

LEGEND

STATISTICAL MATRIX ON INC 825
NO3=10; F=2; SO4=20; T=95 C
CL=1000; HCO3=1000
DE-AERATE W/ARGON
DONE ON PARC 273

27 FEB 1991

Cyclic Volatization of 825 ^{2/26/91}
Model Solution: CL = 1000; HCO₃ = ¹⁰⁰⁰~~2000~~, NO₃ = 10; SO₄ = 20, F = 2

STMX 29

Purpose: To collect data for evaluation of effects of various selected ionic species on the corrosion of Inc 825.

The test specimen was a cylindrical specimen from heat # HH 4371 FC of Incalay 825 fabricated at Sw RT. Procedure generally followed ASTM C-61 for cyclic polarization test. Specimen was wet polished w/220 grit followed by 600 grit. It was then cleaned & degreased per ASTM C-61. Test cell was as described in STMX 12a p. 9. Test follows VOR-008 guidelines. Ref difference less than 1.0mV.

Test Solution Prep: To 500ml of 17 M₂ water in a 1-liter volumetric add 1.6484 g NaCl and 1.3771 g of NaHCO₃ (same lot #s as ~~was~~ used previously). Pipet 20.0ml of 504 stock, 2.0ml of F stock, and 10.0ml of NO₃ stock solution of same # as used in STMX 23 (p. 21), dilute to volume. Lot #s on p. 9


Spec. Dim: $\phi = 6.38 \text{ cm}$ $l = 1.908 \text{ cm}$ $A = 4.144 \text{ cm}^2$

- ① Spec. pre-passivated per VOR-009; cell surface polished to 600 grit.
- ② Spec held at open circuit for one hour before start
- ③ E_{scan} at start -512 mV vs SCE
- ④ E_{PT} 10 min. before start -210 mV
- ⑤ Initial Temp 95.2°C Final Temp 94.5°C
- ⑥ Initial pH 8.27 @ 25°C Final pH 10.16 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 273
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$
- ⑪ Conductivity @ 25°C 412 μmho

Specimen had pits & some crevice corrosion; solution had a heavy greenish cast to it.

Stored on disk E606 #3

Walter J. Mochowski
2/27/91

STMX 30
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
STMX 30
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
2760 S

NOTE: SPEC. HAZD FOR 3600 S
AUTO START WAS MODIFIED DUE TO
DELAY IN STARTING PROGRAM AFTER
SPECIMEN WAS IMMERSSED

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.125
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-537
4
5430.303
-1.044848
4.848485E-04
5430.303

LEGEND

STATISTICAL MATRIX ON INC 825
N03=10;F=2;S04=20;T=95 C
CL=1000;HCO3=2000
DE-AERATE W/ARGON
DONE ON PARC 273

28 FEB 1991

Cyclic Polarization of Inc 825
Model solution: CL=1000; HCO₃=2000; N₃=10; F=2; S₀₄=20

STMX 30

Purpose: Same as STMX 29.

The Inc 825 specimen, procedures, test cell were as described in STMX 29 (p. 33). Reference SCE #4 was used & checked vs. another, before & after test, difference was less than 10 mV.

Test solution prep: To 500 ml of 17 MΩ water in a 1-liter volumetric add 1.6486 g NaCl and 2.7540 g of NaHCO₃ (lot #15 on p. 9). Pipet 20.0 ml of SO₄ stock, 2.0 ml of F stock, and 10.0 ml of NO₃ stock solutions #013-107. Dilute to the mark. note: SO₄ stock solution #013-269 was used.


Spec. Dim: $\phi = 0.638$ cm $l = 1.909$ cm $A = 4.125$ cm²

- ① Spec pre-gassed per JOP-009; all surfaces polished to 600 grit.
- ② Spec held at open circuit for one hour before polarizing
- ③ E corr at start -537 mV vs SCE
- ④ E pt 10 min before start -245 mV
- ⑤ Initial Temp. 94.8°C Final Temp. 95.0°C
- ⑥ Initial pH 8.25 @ 25°C Final pH 10.05 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Auto reverse @ 5000 μ A/cm²
- ⑩ Done on PARC 273
- ⑪ Conductivity @ 25°C 4.94 m mho

Specimen had pitting & some crevice corrosion. Solution was fairly clear, only slightly hazy.

Stored on disk EG+C #3.

Walter J. MacKowski
2/28/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (MV)
VERTEX E (MV)
FINAL E (MV)
SCAN RATE (MV/S)
THRESHOLD I (UA/CM²)
CONDITION E (MV)
CONDITION T (S)
INIT DELAY (MV/S OR S)

CYCLIC POLN
STMX 31
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA (CM²)
EQ WT (GM)
DENSITY (GM/CM³)
CATHODIC TAFEL (MV)
ANODIC TAFEL (MV)

4.136
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-445
4
28844.29
-49.51644
4.83559E-03
28844.29

LEGEND

STATISTICAL MATRIX ON INC 825
NO3=10; F=2; HCO3=85; T=95 C
CL=1000; S04=20000
DE-AERATE W/ARGON
DONE ON PARC 173/276

1 MAR 1991

Cyclic Polarization of Inc 825
Model solution: CL=1000; S04=20,000; NO3=10; F=2; HCO3=85

STMX 31

Purpse: Same as STMX 29

The Inc 825 specimen, procedures, test cell were as described in STMX 29 (p. 33). Ref SCE #4 was used & checked vs another before & after test; difference less than 10mV.

Test Solution Prep: To 500ml of 17MΩ water in a 1-liter volumetric add 1.6486g NaCl, 0.1226g NaHCO3 and 29.5729g of Na2SO4 (same lot #'s as p. 9). Pipet 10.0ml of NO3 stock and 2.0 ml of F stock solutions # 013-107. Dilute to the mark.


Spec. dim $\phi = 0.636$ cm $l = 1.911$ cm $A = 4.136$ cm²

- ① Spec pre-passivated per 708-009; all surfaces polished to 600 grit.
- ② Spec held at open circuit for one hour before start
- ③ E cor at start -445mV vs SCE
- ④ E Pt 10 min before start -295mV
- ⑤ Initial Temp. 95.0°C Final Temp. 95.0°C
- ⑥ Initial pH 7.55 @ 25°C Final Temp. pH 9.51 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 $\mu A/cm^2$
- ⑪ Cond'y = 27.1 mmho @ 25°C

Specimen covered w/a "red-rust" product & had some shallow large pitting. Test solution was yellow w/some orange-brown gelatinous precipitate.

Stored on disk EC-#3.

Walter J. MacKowski
3/1/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (MV)
VERTEX E (MV)
FINAL E (MV)
SCAN RATE (MV/S)
THRESHOLD I (UA/CM²)
CONDITION E (MV)
CONDITION T (S)
INIT DELAY (MV/S OR S)

CYCLIC POLN
STMX 32
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA (CMS²)
EQ WT (GM)
DENSITY (GM/CM³)
CATHODIC TAFEL (MV)
ANODIC TAFEL (MV)

4.133
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-403
4
6532.785
-4.955238
4.8391E-04
6532.785

LEGEND

STATISTICAL MATRIX ON 316L SS
NO3=10; SO4=20; F=2; T=60 C
CL=1000; HCO3=85
DE-AERATE W/ARGON
DONE ON PARC 173/276

6 MAR 1991

Cyclic Polarization of 316L SS

Model Solution: CL=1000; NO₃=10; SO₄=20; F=2; HCO₃=85

STMX 32

Purpose: To collect data for evaluation of effects of various selected ionic species on the corrosion of 316L SS.

The cylindrical specimen was 316L SS from heat #P80746. The specimen preparation, test procedures, test cell were as described in STMX 29 (p.33). Ref SCE #4 was used & checked vs. another before & after test, difference was less than 1.5 mV.

Test Solution Prep: To 500 ml of 17MΩ water in a 1-liter volumetric add 1.6487g NaCl and 0.1319g NaHCO₃ (same lot #'s as p.9) Pipet 10.0 ml of NO₃ stock, 2.0 ml of F stock solutions #013-107. Pipet 20.0 ml of SO₄ stock solution #013-269. Dilute to the mark.

Spec. dim: $\phi = 0.635 \text{ cm}$ $l = 1.913 \text{ cm}$ $A = 4.133 \text{ cm}^2$


- ① Spec. pre-passivated per TOP-009; all surfaces polished to 600 grit
- ② Spec. held at open circuit for one hour before start.
- ③ E con at start -403 mV vs SCE
- ④ E pt 10 min before start +96 mV
- ⑤ Initial Temp. 60.0°C Final Temp 59.0°C
- ⑥ Initial pH 8.23 @ 25°C Final pH 9.09 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 $\mu\text{A/cm}^2$
- ⑪ $k = 3.19 \text{ mm}^2/\text{hr}$ @ 25°C

Specimen had some discoloration and many small pits; also had some crevice corrosion. Solution was slightly hazy and slightly yellowish.

Stored on disk ECTD #3.

Walter J. MacKowski
3/6/91

STMX 33
CYCLIC POLN



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
STMX 33
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.163
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-429
4
1309.152
-.3242854
0
1309.152

LEGEND

STATISTICAL MATRIX ON 316L SS
SO4=20;F=2;HCO3=85;T=60 C
CL=1000;NO3=1000
DE-AERATE W/ARGON
DONE ON PARC 173/276

7 MAR 1991

Cyclic Voltammetry of 316L SS
Model Solution: CL=1000; NO₃=1000; SO₄=20; F=2; HCO₃=85 60°C

STMX 33

Purpose same as STMX 32.

The test specimen, heat #, procedures, preparations, etc. were as described in STMX 32 (p. 39). Ref SCE #4 was used & checked before & after test, difference was less than 10mV.

Test Solution Prep: TO 500 ml of 17M₂ water in a 1-liter volumetric add 1.6477g NaCl and 1.3794g NaNO₃ and 0.1221g NaHCO₃ (same lot #1's as p. 9). Pipet 20.0 ml of SO₄ stock solution #013-269 and 2.0 ml of F stock solution #013-107. Dilute to the mark.
Specimen: $\phi = 0.635$ cm $l = 1.928$ cm $A = 4.163$ cm²


- ① Spec. pre-processed per TOP-009; all surfaces polished to 600 grit
- ② Spec. held at open circuit for one hour before start
- ③ E_{corr} at start -429 mV vs SCE
- ④ E_{pt} 10 min before start -45 mV
- ⑤ Initial Temp 61.0°C Final Temp 59.0°C
- ⑥ Initial pH 8.16 @ 25°C Final pH 9.45 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Manual reverse @ 4610 μ A / +1332 mV
- ⑪ K = 4.33 mmho @ 25°C

* NOTE: Temperature overshot to 90°C; increased air flow & allowed to cool down before immersing specimen.

Specimen mostly pit free, small pit and some crevice corrosion at mounted end. The rest free & clear of pits. Solution fairly clear, only a hint of yellowish color.

Stored on disk ECVG #3

Walter J. Macbrack
3/5/91

STMX 34
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (MV)
VERTEX E (MV)
FINAL E (MV)
SCAN RATE (MV/S)
THRESHOLD I (UA/CM²)
CONDITION E (MV)
CONDITION T (S)
INIT DELAY (MV/S OR S)

CYCLIC POLN
STMX 34
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA (CMS²)
EQ WT (GM)
DENSITY (GM/CM³)
CATHODIC TAFEL (MV)
ANODIC TAFEL (MV)

4.092
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-420
4
18841.64
-5.004888
9.775171E-03
18841.64

LEGEND

STATISTICAL MATRIX ON 316L SS
NO3=10; F=2; HCO3=85; T=95 C
CL=1000; S04=20000
DE-AERATE W/ARGON
DONE ON PARC 173/276

8 MAR 1991

Cyclic Polarization of 316L SS
Model Solution: CL=1000, S04=20,000, NO₃=10, F=2, HCO₃=85

STMX 34

Purpose: Same as STMX 32.

The test specimen, heat #, preparation, procedures, etc. were as described in STMX 32 (p. 39). Ref SCE #4 was used and checked w. another before after test, difference less than 1.0 mV.


Test Solution Prep: To 500 ml of 12 M₂ water in a 1-liter volumetric add 1.6487 g NaCl, 0.1226 g NaHCO₃, and 29.5730 g Na₂SO₄ (same lot #'s as p. 9). Pipet 10.0 ml of NO₃ stock + 20 ml of F stock solutions, both #013-107, dilute to the mark.
Spec. dim: $\phi = 0.632$ cm $l = 1.903$ cm $A = 4.092$ cm²

- ① Spec. pre-passivated per 708-009; all surfaces polished to 600 grit
- ② Spec. held at open circuit for one hour before start
- ③ E scan at start -420 mV vs. SCE
- ④ E pt 10 min. before start
- ⑤ Initial Temp. 95.0°C Final Temp. 94.8°C
- ⑥ Initial pH 7.94 @ 25°C
- ⑦ Scan rate 0.12 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 $\mu A/cm^2$
- ⑪ $k = 27.3$ m₂/h @ 25°C

Specimen discolored with areas of localized corrosion + pits. Also had some crevice attack. Solution was a hazy greenish color.

Stored on disk EACC #3.

Walter J. MacKowski
3/8/91

STMX 35
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
STMX 35
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.098
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-341
4
5905.32
-4.392387E-02
1.220107E-03
5905.32

LEGEND

STATISTICAL MATRIX ON 316L SS
NO3=10;F=2;HCO3=85;T=60 C
CL=1000;SD4=20000
DE-AERATE W/ARGON
DONE ON PARC 173/276

11 MAR 1991

Applied Polarization of 316L SS
Model solution: CL=1000, SD4=20,000, NO3=10, F=2; HCO3=85 60°C

STMX 35

Purpose: Same as STMX 32.

The test specimen, heat #, procedures, preparation, etc were as in STMX 32 (p.39). Ref SCE #4 was checked as in STMX 32, difference was less than 1.0 mV

Test solution prep: The same as STMX 34, with same lots
Actual salt weights were 1.6485 g NaCl, 29.5728 g Na2SO4,
and 0.1221 g NaHCO3.


Spec. Dim: $\phi = 0.634 \text{ cm}$ $l = 1.899 \text{ cm}$ $A = 4.098 \text{ cm}^2$

- ① Spec. pre-passivated per 708-009; all surfaces polished to 600 grit
- ② Spec. held at open circuit for one hour before start
- ③ E can at start - 341 mV vs SCE
- ④ E Pt 10 min before start - 130 mV
- ⑤ Initial Temp. 61.0°C Final Temp. 59.2°C
- ⑥ Initial pH 7.99 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 $\mu\text{A/cm}^2$
- ⑪ K = 26.8 mm-hr @ 25°C

Specimen was discolored & had several small pits in various places. Also had quite a bit of crevice corrosion. Solution was slightly hazy w/ a small amount of gelatinous precipitate.

Stored on disk EPTA #3.

Walter J. MacHoush
3/12/91

STMX 36
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (MV)
VERTEX E (MV)
FINAL E (MV)
SCAN RATE (MV/S)
THRESHOLD I (UA/CM²)
CONDITION E (MV)
CONDITION T (S)
INIT DELAY (MV/S OR S)

CYCLIC POLN
STMX 36
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA (CMS²)
EQ WT (GM)
DENSITY (GM/CM³)
CATHODIC TAFEL (MV)
ANODIC TAFEL (MV)

4.092
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-536
4
8699.902
-50.04887
2.688172E-03
8699.902

LEGEND

STATISTICAL MATRIX ON 316L SS
NO3=10; SO4=20; F=2; T=95 C
CL=1000; HCO3=2000
DE-AERATE W/ARGON
DONE ON PARC 173/276

12 MAR 1991

Cyclic Polarization of 316L SS

Model Solution: CL=1000, HCO₃=2000, SO₄=20, NO₃=10, F=2

STMX 36

Purpose: Same as STMX 32.

The test specimen, heat #, preparation, procedures, test cell, etc were as in STMX 32 (p. 39). Ref SCE #4 was used & checked as in STMX 32. Difference less than 1.0 mV.

Test Solution Prep: To 500 ml of 17 MΩ water in a 1-liter volumetric add 1.6485 g NaCl and 2.7551 g NaHCO₃ (same lot #1s as p. 9). Pipet 10.0 ml of NO₃ stock + 2.0 ml of F stock solutions both #10 #013-107. Pipet 20.0 ml of SO₄ stock solution #013-269. 3/12/91 WJ Machowski dilute to the mark.


Specimen: $\phi = 0.634 \text{ cm}$ $l = 1.896 \text{ cm}$ $A = 4.092 \text{ cm}^2$

- ① Spec. pre-passivated per 708-009; all surfaces polished to 600 grit.
- ② Spec held at open circuit for one hour before start
- ③ E can at start -536 mV vs SCE
- ④ E Pt 10 min before start -460 mV
- ⑤ Initial Temp. 94.5°C Final Temp. 96.0°C
- ⑥ Initial pH
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 $\mu\text{A/cm}^2$
- ⑪ $K = 4.82 \text{ mmho cm}^2 \text{ s}^{-1}$ @ 25°C

Specimen pitted and some crevice corrosion. Large green bubbles were on specimen during the test. Solution had a yellowish haze.

Stored on disk EG+C #5.

Walter J. Machowski
3/12/91

STMXR33
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
STMXR33
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.117
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-368
4
5319.407
-1.4104931
1.457372E-02
5319.407

LEGEND

STATISTICAL MATRIX ON 316L SS
SD4=20; F=2; HCO3=85; T=60 C
CL=1000; NO3=1000
DE-AERATE W/ARGON
DONE ON PARC 173/276

THIS IS A RE-RUN OF STMX 33
13 MAR 1991

Cyclic Polarization of 316L SS
Model Solution: CL=1000; NO3=1000; SD4=20; F=2; HCO3=85; T=60°C

STMXR 33

Purpose: This is a re-run of STMX 33, due to odd curve maybe because of overtemp.

Specimen, heat#, preparation, etc were as in STMX 33. Ref SCE #4 was used & checked as before. Diffuse current 1.0ml

Test solution prep was the same as in STMX 33. Actual salt weights were 0.1217g NaHCO3, 1.6486g NaCl, and 1.3794g NaNO3.

Spec. Dim: $\phi = 0.1635 \text{ cm}$ $l = 1.905 \text{ cm}$ $A = 4.117 \text{ cm}^2$


- ① Specimen pre-passivated per 708-009; all surfaces polished to 600 grit
- ② Specimen held at open circuit for one hour before start
- ③ E cor at start -368 mV vs SCE
- ④ E Pt 10 min. before start +78 mV
- ⑤ Initial Temp 60.4°C Final Temp 59.5°C
- ⑥ Initial pH 8.41 @ 25°C Final pH 9.22 @ 55°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$
- ⑪ K=4.20 mmho @ 25°C

Specimen similar to STMX 33. Solution also.

Stored on disk ETR #3.

Walter J. MacKowski
3/13/91

STMX 37
CYCLIC POLN



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (MV)
VERTEX E (MV)
FINAL E (MV)
SCAN RATE (MV/S)
THRESHOLD I (UA/CM²)
CONDITION E (MV)
CONDITION T (S)
INIT DELAY (MV/S OR S)

CYCLIC POLN
STMX 37
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA (CM²)
EQ WT (GM)
DENSITY (GM/CM³)
CATHODIC TAFEL (MV)
ANODIC TAFEL (MV)

4.113
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-321
4
7585.704
-.4254802
0
7585.704

LEGEND

STATISTICAL MATRIX ON 316L SS
NO3=10; SO4=20; HCO3=85; T=60 C
CL=1000
SPARGE CO2 AT 1 ATM
DONE ON PARC 173/276

14 MAR 1991

Cyclic Polarization of 316L SS
Model Solution: CL=1000, NO₃=10, SO₄=20, F=2, HCO₃=85, CO₂ 60°C 51
STMX 37
Purpose: Same as STMX 32.

The specimen, heat #, preparation, procedures, etc. were as in STMX 32. Ref SCE #4 was used & checked as before, difference was less than 10 mV.

Test Solution Prep: To 500 ml of 17 MR water in a 1-liter volumetric add 1.6482 g of NaCl and 0.1225 g NaHCO₃ (same lot #'s as p.9) Pipet 10.0 ml of NO₃ stock and 2.0 ml of F stock solutions #013-107. Pipet 20.0 ml of SO₄ stock solution #013-269, dilute to the mark.


Spec. Dim: $\phi = 0.635$ cm $l = 1.903$ cm $A = 4.113$ cm²

- ① Specimen pre-passivated per TOP-009; all surfaces polished 600 grit.
- ② Specimen held at open circuit for one hour before start
- ③ E con at start -320 mV vs SCE
- ④ E Pt 10 min before start +290 mV
- ⑤ Initial Temp. 60.5°C Final Temp. 59.8°C
- ⑥ Initial pH 5.46 @ 25°C Final pH 5.49 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ CO₂ purge gas (99.99%)
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 μ A/cm²
- ⑪ $K = 2.89$ mm² @ 25°C

Specimen retained its' silvery color, but revealed a few small pits especially when probed. Also had a small amount of crevice corrosion. Test solution remained water clear.

Stored on disk EC + C #3.

Walter J. Macfowleski
3/14/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
STMX 38
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.102
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-510
4
8824.963
-4.992686
6.899073E-02
8824.963

LEGEND

STATISTICAL MATRIX ON 316L SS
NO3=10;SO4=20;F=2;HCO3=85;T=95 C
CL=1000
SPARGE CO2 AT 1 ATM
DONE ON PARC 173/276

15 MAR 1991

Cyclic Polarization of 316L SS
Model Sol'n: CL=1000, NO₃=10, SO₄=20, F=2, HCO₃=85 95°C CO₂

STMX 38

Purpose: Same as STMX 32.

The test specimen, heat #, preparation, procedures, etc were as in STMX 32. Ref SCE #4 was used and checked as before; difference was less than 1.0 mV.

The test solution was prepared as in STMX 37 from the same lot #'s. Actual salt weights were 1.6485 g NaCl and 0.1227 g NaHCO₃.


Specimen dimensions: $\phi = 0.634$ cm $l = 1.901$ cm $A = 4.102$ cm²

- ① Specimen pre-passivated per TOP-009; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start
- ③ E scan at start -510 mV vs SCE
- ④ E Pt 10 min before start -284 mV
- ⑤ Initial Temp 94.8°C Final Temp 95.0°C
- ⑥ Initial pH 5.37 @ 25°C Final pH 5.46 @ 25°C
- ⑦ Scan rate 0.17 mV/s (600 mV/hr)
- ⑧ CO₂ purge (99.99%)
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 μ A/cm²
- ⑪ K = 2.79 mm/hr @ 55°C

Specimen discolored a reddish-brown with many small pits. Small amount of crevice corrosion. Solution had a yellowish haze.

Stored on disk ECT #3

Walter J. Macchowski
3/15/91

STMX 39
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	STMX 39
INITIAL E(MV)	0 VS E
VERTEX E(MV)	100 VS E
FINAL E(MV)	100 VS E
SCAN RATE(MV/S)	.17
THRESHOLD I(UA/CM^2)	5000
CONDITION E(MV)	PASS
CONDITION T(S)	PASS
INIT DELAY(MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA(CMS^2)	4.085
EQ WT(GM)	PASS
DENSITY(GM/CM^3)	PASS
CATHODIC TAFEL(MV)	PASS
ANODIC TAFEL(MV)	PASS

DATA SCALE

ECORR	-560
MV/PT	4
DATA MAX	2073.439
DATA MIN	.2643819
ABS MIN	.2643819
ABS MAX	2073.439

LEGEND

STATISTICAL MATRIX ON 316L SS
 NO3=10; SO4=20; F=2; HCO3=85; T=95 C
 CL=6
 SPARGE CO2 AT 1 ATM
 DONE ON PARC 173/276

CL = 3.6 ←
 (see STMX 18)

18 MAR 1991

Cyclic Polarization of 316L SS
 Model Solution: $Cl=6, NO_3=10, F=2, SO_4=20, HCO_3=85, CO_2$ 95°C
 STMX 39 CL = 3.6 w/m 4/17/91
 Recipe: Same as STMX 32.

The test specimen, heat#, preparation, procedures, etc were as in STMX 32. Ref SCE # 4 was used and checked as before. Difference was less than 1.0 mV.

Test solution prep: To 500 ml of 17 M.2 water in a 1-liter volumetric add 0.1221 g of $NaHCO_3$ (same lot # as p. 9). Pipet 6.0 ml of Cl stock, 2.0 ml of F stock and 2.0 ml of NO_3 stock solutions # 013-107. Pipet 20.0 ml of SO_4 stock solution # 013-269. Dilute to the mark.


Spec. Dim: $\phi = 0.633$ cm $l = 1.896$ cm $A = 4.085$ cm²

- ① Specimen pre-passivated per TOP-009; all surface polished to 600 grit
- ② Specimen held at open circuit for one hour before start
- ③ E corr at start - 560 mV vs SCE
- ④ E Pt 10 min before start - 70 mV
- ⑤ Initial Temp. 95.5°C Final Temp. 95.5°C
- ⑥ Initial pH 5.42 @ 25°C Final pH 5.42 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Cl_2 purge (99.99%)
- ⑨ Done on PARC 173/276
- ⑩ Manual reverse @ 8380 μA / +1650 mV
- ⑪ $K = 0.021$ mm/hr @ 25°C

The specimen retained its metallic luster and was free of both pitting and crevice corrosion. The test solution remained water clear.

Stored on disk ECP-# 3

Walter J. Macfoushi
 3/18/91

STMX 40
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (MV)
VERTEX E (MV)
FINAL E (MV)
SCAN RATE (MV/S)
THRESHOLD I (UA/CM²)
CONDITION E (MV)
CONDITION T (S)
INIT DELAY (MV/S OR S)

CYCLIC POLN
STMX 40
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA (CMS²)
EQ WT (GM)
DENSITY (GM/CM³)
CATHODIC TAFEL (MV)
ANODIC TAFEL (MV)

4.287
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-472
4
3097.737
.1049685
.1049685
3097.737

LEGEND

STATISTICAL MATRIX IN INC 825
NO3=10; SO4=20; F=2; HCO3=85; T=95 C
CL=6
SPARGE CO2 AT 1 ATM
DONE ON PARC 173/276

CL=3.6 ←
(see STMX 16)

19 MAR 1991

Cyclic Polarization of Inc 825
Model solution: CL=6, NO₃=10, F=2, SO₄=20, HCO₃=85 CO₂ 95°C
STMX 40 CL=3.6

Purpose: Same as STMX 29 (p. 33).

The test specimen^①, heat#, preparation, procedures, etc. was as described in STMX 29. Ref SCE#4 was used & checked as before. Difference was less than 1.0 mV.

Test solution prep: The solution was prepared as in STMX 39 with the same chemical & solution lot #'s. Actual salt weight used was 0.1224 g NaHCO₃.

Specimen dim: $\phi = 0.632 \text{ cm}$ $l = 2.001 \text{ cm}$ $A = 4.287 \text{ cm}^2$

- ① Specimen pre-passivated per 708-009; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start.
- ③ E cor at start -472 mV vs SCE
- ④ E Pt 10 min before start -65 mV
- ⑤ Initial Temp. 95.3°C Final Temp. 95.5°C
- ⑥ Initial pH 5.27 @ 25°C Final pH 5.32 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ CO₂ purge (99.99%)
- ⑨ Done on PARC 173/276
- ⑩ Manual reverse @ 12,960 μA / +1650 mV
- ⑪ K = not taken; sample spilled


specimen has slight brownish color, but no pits nor crevice corrosion. Test solution remained water clear.

Stored on disk EC+C #3.

① The specimens were the "long" ones from metal samples; they were cut to the shorter length on a cut-off wheel at S.W.R.T.

Walter J. Macrowan
3/19/91

STMX 41
CYCLIC POLN



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
STMX 41
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.425
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-507
4
18124.29
3.322034E-02
3.322034E-02
18124.29

LEGEND

STATISTICAL MATRIX IN INC 825
NO3=10;SO4=20;F=2;HCO3=85;T=95 C
CL=1000
SPARGE CO2 AT 1 ATM
DONE ON PARC 173/276

20 MAR 1991

Cyclic Polarization of Inc 825
Model solution: CL=1000, NO₃=10, F=2, SO₄=20, HCO₃=85 95°C CO₂

STMX 41

Purpose: Same as STMX 29(p.33).

The test specimen, heat #, preparation, procedures, etc were as described in STMX 40. Ref SCE #4 was used and checked as before. Difference was less than 1.0 mV.

Test solution prep: The test solution was prepared as in STMX 37 (p.51) with the same chemical + solution lot #'s. The actual salt weights used were 1.6478 g NaCl and 0.1226 g of NaHCO₃.


Specimen dimensions: $\phi = 0.634$ cm $l = 2.063$ cm $A = 4.425$ cm²

- ① Specimen pre-passivated per 708-009; all surfaces polished to 600 grit
- ② Specimen held at open circuit for one hour before start.
- ③ E cor at start -507 mV vs SCE
- ④ E Pt 10 min before start -71 mV
- ⑤ Initial Temp. 95.0°C Final Temp. 95.0°C
- ⑥ Initial pH 4.94 @ 25°C Final pH 5.32 @ 55°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ CO₂ purge (99.99%)
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 μ A/cm²
- ⑪ K = 3.13 mmhos @ 55°C

Specimen was discolored and had many small pits which were made evident by probing. Also had quite a bit of crevice corrosion. Test solution was a murky greenish color.

Stored on disk ETC #3.

Walter J. Machowski
3/20/91

STMX 42
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
STMX 42
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.289
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-429
4
5152.716
-47.75006
6.994637E-03
5152.716

LEGEND

STATISTICAL MATRIX IN INC 825
NO3=10;SO4=20;F=2;T=60 C
CL=1000;HCO3=2000
DE-AERATE W/ARGON
DONE ON PARC 173/276

21 MAR 1991

Cyclic Polarization of Inc 825

Model Solution: CL=1000, HCO₃=2000, SO₄=20, NO₃=10, F=2

STMX 42

Purpose: Same as STMX 29(p.33).

The test specimen, heat #, preparation, procedures, etc were as described in STMX 40. Ref SCE #4 was used and checked as before. Difference was less than 1.0 mV.

Test Solution Prep: To 500 ml. of 17 MΩ water in a 1-liter volumetric add 1.6488 g NaCl and 2.7537 g NaHCO₃ (same lot #5 as p.9). Pipet 20.0 ml of SO₄ stock solution #013-269. Pipet 10.0 ml of NO₃ stock solution and 2.0 ml of F stock solution #013-107. Dilute to the mark.

Specimen Dimensions: $\phi = 0.631 \text{ cm}$ $l = 2.006 \text{ cm}$ $A = 4.289 \text{ cm}^2$

- ① Specimen pre-passivated per TOP-009; all surfaces polished to 600 grit
- ② Specimen held at open circuit for one hour before start
- ③ E corr at start - 429 mV vs SCE
- ④ E Pt 10 min. before start - 35 mV
- ⑤ Initial Temp. 95.0°C 60°C Final Temp. 60.0°C
- ⑥ Initial pH 8.52 @ 25°C Final pH 9.51 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge (99.99%)
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$
- ⑪ $K = 4.62 \text{ mm hrs @ } 25^\circ\text{C}$

Specimen was dissolved + pitted - only at "top" end where Ar bubbler tended to collect. Also had moderate crevice corrosion. Solution had a hazy yellowish tinge.

Stored on disk EBTG #3.

Walter J. Machowski
3/21/91


Preparation of NO_3 Stock Solution 1000 ppm

Purpose: Stock solution used in preparation of test solutions.

Weigh out 1.3793 g of NaNO_3 (Fisher Stock# 5343-500 lot# 897183) dissolve in 500 ml of 17 M-Q water in a 1-liter volumetric + dilute to the mark.

Label as SN CNARA 019-63

Walter J. Machowski
3/21/91

STMX 43
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
STMX 43
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.308
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-262
4
2000.928
-4.753946
7.149489E-02
2000.928

LEGEND

STATISTICAL MATRIX ON CDA 102
NO3=10; SO4=20; F=2; T=60 C
CL=6; HCO3=85
DE-AERATE W/ARGON
DONE ON PARC 173/276

22 MAR 1991

Cyclic Polarization of CDA-102
Model Solution: CL=6, NO₃=10, F=2, SO₄=20; HCO₃=85 60°C

STMX ~~43~~ 43 wgmachowski 3/22/91

Purpose: To collect data for evaluation of effects of various selected ionic species on the corrosion of CDA-102 using a factorial experiment.

A cylindrical specimen of CDA-102 (heat # 6681) fabricated at SWRI was used. The preparation, procedures, cell, etc were as described on p. 9 (STMX 17). Ref SCE #4 was used and checked as before. Difference was less than 1.0 mV.


Test Solution Prep: To 500ml of 17M₂ water in a 1-liter volumetric flask add 0.1222 g of NaHCO₃ (same lot # as p. 9). Pipet 10.0ml of Cl stock, 2.0ml of F stock solution #013-107. Pipet 10.0ml of NO₃ stock solution #019-63. Pipet 20.0ml of SO₄ stock solution #013-269. Dilute to the mark.
Spec. dimension: $\phi = 0.638 \text{ cm}$ $L = 1.990 \text{ cm}$ $A = 4.308 \text{ cm}^2$

- ① Specimen not pre-passivated; polished to 600 grit on all surfaces
- ② Specimen held at open circuit for one hour before start
- ③ E can at start -263 mV vs SCE
- ④ E Pt 10 min. before start +5 mV
- ⑤ Initial Temp. 60.2°C Final Temp. 60.0°C
- ⑥ Initial pH 8.36 @ 25°C Final pH 9.50 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Manual reverse @ 8540 μA / +975 mV

Specimen was covered w/a dark scale which easily fell off when dried. Specimen showed that general corrosion had occurred all over; grains could be observed. No attack on mounted end. Solution was slightly murky until corrosion product settled - then it was clear.

Stored on disk EG+G #3.

Walter J. Machowski
3/22/91

STMX 44
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
STMX 44
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.288
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-287
4
5340.485
3.521455E-02
3.521455E-02
5340.485

LEGEND

STATISTICAL MATRIX ON CDA 102
NO3=10;S04=20;F=2;T=60 C
CL=6;HCO3=8500
DE-AERATE W/ARGON
DONE ON PARC 173/276

25 MAR 1991

Cyclic Voltammetry of CDA-102
Model solution: $\text{HCO}_3^- = 8500$, $\alpha = 6$, $\text{NO}_3^- = 10$, $F = 2$, $\text{SA}_1 = 20$ 60°C

STMX 44

Purpose: Same as STMX 43.

The specimen, heat #, preparation, procedures, etc were as described in STMX 43 (p.65). Ref SCE #4 was used and checked as before. Difference was less than 1.0 mV.

Test solution prep: The test solution was prepared as in STMX 43 w/ the same lot #'s, except that 12.201 g of NaHCO_3 were added.

Specimen dimensions: $\phi = 0.633 \text{ cm}$ $l = 1.998 \text{ cm}$ $A = 4.288 \text{ cm}^2$

- ① Specimen not pre-passivated; all surface polished to 600 grit
- ② Specimen held at open circuit for one hour before starting
- ③ E_{cor} at start -288 mV vs SCE
- ④ E pt 10 min before start -7 mV
- ⑤ Initial Temp. 60.5°C Final Temp. 60.0°C
- ⑥ Initial pH 8.39 @ 25°C Final pH 9.35 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge (99.999%)
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$


Specimen had a brownish-purple color. No conversion appeared to have taken place. Test solution was water clear.

Comparison to Thomas & Tiller indicates the film may be a combination of Cu_2O , malachite & cupric hydroxide.

Stored on dish ECR # 3

Walter J. MacKowshi
3/25/91

STMX 45
CYCLIC POLN



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (MV)
VERTEX E (MV)
FINAL E (MV)
SCAN RATE (MV/S)
THRESHOLD I (μA/CM²)
CONDITION E (MV)
CONDITION T (S)
INIT DELAY (MV/S OR S)

CYCLIC POLN
STMX 45
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA (CMS²)
EQ WT (GM)
DENSITY (GM/CM³)
CATHODIC TAFEL (MV)
ANODIC TAFEL (MV)

4.099
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-329
4
5318.371
-499.6341
2.43962E-03
5318.371

LEGEND

STATISTICAL MATRIX ON CDA 102
NO3=10; SO4=20; F=2; T=95 C
CL=1000; HCO3=85
DE-AERATE W/ARGON
DONE ON PARC 173/276

27 MAR 1991

Cyclic Polarization of CDA 102
Model solution: CL=1000, HCO₃=85, NO₃=10, SO₄=20, F=2 95°C

STMX 45

Purpose: Same as STMX 43

The specimen, heat #, preparation, procedures, etc were as described in STMX 43. Ref SCE #4 was used and checked as before, difference was less than 10 mV.

Test solution prep: To 500 ml of 17 M Ω water in a 1-liter volumetric add 1.6486 g NaCl and 0.1221 g of NaHCO₃ (lot #1's on p. 9). Pipet 20.0 ml of SO₄ stock sol'n # 013-269; pipet 10.0 ml of NO₃ stock sol'n # 019-63; pipet 2.0 ml of F stock sol'n # 013-107, dilute to the mark.

Specimen Dimensions: $\phi = 0.633 \text{ cm}$ $l = 1.903 \text{ cm}$ $A = 4.099 \text{ cm}^2$

- ① Specimen not pre-passivated, all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start
- ③ E corr at start -329 mV vs SCE
- ④ E at 10 min before start -158 mV
- ⑤ Initial Temp. 95.4°C Final Temp. 94.0°C
- ⑥ Initial pH 8.13 @ 25°C Final pH 9.69 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 μA/cm²


Specimen had a very, loose, scaly reddish-brown coating which flaked off when dried. Specimen was uniformly corroded all over, grains were easily visible. Test solution was a golden-yellow color.

The curve corresponds reasonably well to that in Thomas & Tiller. No surface film formed is possible concl.

Stored on disk E-C-P #4

Walter J. MacKowski
3/27/91

STMX 46
CYCLIC POLN



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (MV)
VERTEX E (MV)
FINAL E (MV)
SCAN RATE (MV/S)
THRESHOLD I (UA/CM²)
CONDITION E (MV)
CONDITION T (S)
INIT DELAY (MV/S OR S)

CYCLIC POLN
STMX 46
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA (CMS²)
EQ WT (GM)
DENSITY (GM/CM³)
CATHODIC TAFEL (MV)
ANODIC TAFEL (MV)

4.108
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-244
4
5355.404
-498.5395
2.434275E-02
5355.404

LEGEND

STATISTICAL MATRIX ON CDA 102
CL=6; NO3=10; F=2; HCO3=85; T=60 C
S04=1000
DE-AERATE W/ARGON
DONE ON PARC 173/276

28 MAR 1991

Cyclic Polarization of CDA 102
Model Solution: CL=6, NO₃=10, F=2, HCO₃=85, S04=1000 60°C

STMX 46

Purpose: Same as STMX 43.

The test specimen, heat #, preparation, procedures, etc were as described in STMX 43. Ref SCE #4 was used and checked as before, difference was less than 1.0 mV.

Test Solution Prep: To 500 ml of 17 M Ω water in a 1-liter volumetric add 0.1228 g of NaHCO₃ and 1.4787 g of Na₂SO₄ (let #1's on p. 9). Pipet 10.0 ml of Cl stock and 2.0 ml of F stock solutions #013-107. Pipet 10.0 ml of NO₃ stock solution #019-63. dilute to the mark.

Specimen Dimensions: $\phi = 0.634$ cm $l = 1.904$ cm $A = 4.108$ cm²


- ① Specimen not pre-passivated; all surfaces polished to 600 grit
- ② Specimen held at open circuit for one hour before starting
- ③ E corr at start -244 mV vs SCE
- ④ E Pt 10 min before start $+11$ mV
- ⑤ Initial Temp. 60.0°C Final Temp. 59.4°C
- ⑥ Initial pH 8.24 @ 25°C Final pH 9.39 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 μ A/cm²

Specimen covered w/ flaky reddish-brown deposit. General corrosion with grains visible on specimen. Solution mostly clear w/ some of the reddish-brown material present.

stored on disk ECTA #4.

Walter J. Moehowski
3/28/91

STMX 47
CYCLIC POLN



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	STMX 47
INITIAL E(MV)	0 VS E
VERTEX E(MV)	100 VS E
FINAL E(MV)	100 VS E
SCAN RATE(MV/S)	.17
THRESHOLD I(UA/CM^2)	5000
CONDITION E(MV)	PASS
CONDITION T(S)	PASS
INIT DELAY(MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA(CMS^2)	4.115
EQ WT(GM)	PASS
DENSITY(GM/CM^3)	PASS
CATHODIC TAFEL(MV)	PASS
ANODIC TAFEL(MV)	PASS

DATA SCALE

ECORR	-301
MV/PT	4
DATA MAX	8311.058
DATA MIN	-687.7278
ABS MIN	.1793439
ABS MAX	8311.058

LEGEND

STATISTICAL MATRIX ON CDA 102
CL=6; SO4=20; NO3=10; F=2
HCO3=85000; T=60 C
DE-AERATE W/ARGON
DONE ON PARC 173/276

SOL'N SATURATED W/NAHCO3--SOME
SALT REMAINED UNDISSOLVED
29 MAR 1991

Cyclic Polarization of CDA-102

Model Solution: CL=6, SO4=20, NO3=10, F=2 60°C
HCO3=85,000

STMX 47

Purpose: Same as STMX 43.

The test specimen, heat #, preparation, procedure, etc. were as in STMX 43. Ref SCE #4 was used and checked as before, difference was less than 1.0 mV.

Test Solution Prep: To 500 ml of 17 MΩ water in a 1-liter volumetric add 122.00 g of NaHCO3 (lot # on p. 9). Pipet 10.0 ml of Cl stock and 2.0 ml of F stock solutions #013-107. Pipet 20.0 ml of SO4 stock solution #013-269, and 10.0 ml of NO3 stock solution #019-63. Dilute to the mark. Note this was a saturated sol'n w/ respect to NaHCO3; some considerable amount of salt remained undissolved.

Specimen Dimensions: $\phi = 0.635 \text{ cm}$ $l = 1.904 \text{ cm}$ $A = 4.115 \text{ cm}^2$


- ① Specimen not pre-passivated; all surfaces polished to 600 grit
- ② Specimen held at open circuit for one hour before start
- ③ E corr at start -301 mV vs SCE
- ④ E PT 10 min. before start -125 mV
- ⑤ Initial Temp. 60.0°C Final Temp. 59.0°C
- ⑥ Initial pH 8.12 @ 25°C Final pH 8.59 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ done on PARC 173/276
- ⑩ Auto reverse @ 5000 $\mu\text{A/cm}^2$

Specimen had a dark, very adherent coating & appeared not to have corroded. Test solution was water clear & undissolved NaHCO3 had dissolved at end of test period.

Stored on disk E6+A #4.

Walter J. Mochowski
3/29/71

STMX 48
CYCLIC POLN



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
STMX 48
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.142
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-259
4
5287.301
-32.61709
1.617576E-02
5287.301

LEGEND

STATISTICAL MATRIX ON CDA 715
CL=6;SO4=20;NO3=10;F=2
HCO3=85;T=60 C
DE-AERATE W/ARGON
DONE ON PARC 273

29 MAR 1991

Cyclic Polarization of CDA-715
Model solution: CL=6, SO4=20, NO3=10, F=2, HCO3=85 60°C

STMX 48

Purpose: Same as STMX 45, except using CDA 715.

The test specimen was CDA-715, heat # 2037, fabricated at SWRT. Preparation, procedures, test cell were as described on p. 9, except the salt bridge was filled with saturated NaCl solution. Rf SCE #1 was used and checked vs. another, difference was less than 1.0 mV.


Test solution Prep: Test solution was prepared as in STMX 43 with same lot # chemicals and solutions. Actual salt weight used was 0.1222 g of NaHCO3.

Specimen dimensions: $\phi = 0.638 \text{ cm}$ $l = 1.907 \text{ cm}$ $A = 4.142 \text{ cm}^2$

- ① Specimen not pre-polarized; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start.
- ③ E cor at start -259 mV vs SCE
- ④ E Pt 10 min before start -58 mV
- ⑤ Initial Temp. 60.5°C Final Temp. 59.5°C
- ⑥ Initial pH 8.42 @ 25°C Final pH 9.58 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PARC 273
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$

Specimen was covered with a flaky brown film. Some general attack appeared to have occurred all over the specimen. Test solution was slightly murky with a greenish tinge. Some gelatinous precipitate was evident.

Saved on disk ECG #4.

STMX 49
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
STMX 49
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.104
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-281
4
5506.822
-17.37329
5.847953E-02
5506.822

LEGEND

STATISTICAL MATRIX ON CDA 715
CL=6; NO3=10; SO4=20; F=2
HCO3=8500; T=60 C
DE-AERATE W/ARGON
DONE ON 273

1 APR 1991

Cyclic Polarization of CDA 715
Model Solution: HCO₃ = 8500, CL=6, NO₃=10, SO₄=20, F=2 60°C

STMX 49

Purpose: Same as STMX 48.

The test specimen, heat #, procedures, cell, etc were as described in STMX 48. Ref. SCE #1 was used and checked as before, difference was less than 0.5 mV.

Test solution prep: Solution was prepared as in STMX 44 with same lot #s. Actual salt weight added was 12.221g NaHCO₃.

Specimen Dimensions: $\phi = 0.634 \text{ cm}$ $l = 1.902 \text{ cm}$ $A = 4.104 \text{ cm}^2$


- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour prior to start
- ③ E corr at start -281 mV vs SCE
- ④ E Pt 10 min before start -65 mV
- ⑤ Initial Temp. 59.5°C Final Temp. 59.5°C
- ⑥ Initial pH 8.47 @ 25°C Final pH 9.20 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PDR 273
- ⑩ Auto reverse @ 5000 $\mu\text{A/cm}^2$

Specimen had a thin, black, adherent coating. No corrosion was evident. Test solution remained water clear.

Stored on disk ECR #4.

Walter J. Macfowen
4/1/91

STMX 50
CYCLIC POLN



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (MV)
VERTEX E (MV)
FINAL E (MV)
SCAN RATE (MV/S)
THRESHOLD I (UA/CM²)
CONDITION E (MV)
CONDITION T (S)
INIT DELAY (MV/S OR S)

CYCLIC POLN
STMX 50
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA (CMS²)
EQ WT (GM)
DENSITY (GM/CM³)
CATHODIC TAFEL (MV)
ANODIC TAFEL (MV)

4.101
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-244
4
5120.703
3.901488E-03
3.901488E-03
5120.703

LEGEND

STATISTICAL MATRIX ON CDA 715
CL=6; NO3=10; F=2; T=60 C
S04=1000; HCO3=85
DE-AERATE W/ARGON
DONE ON 273

2 APR 1991

Cyclic Polarization of CDA 715

Model solution: CL=6, NO₃=10, F=2, S0₄=1000, HCO₃=85 60°C

STMX 50

Purpose: Same as STMX 48.

The test specimen was CDA 715 (heat #7037) fabricated at SRI. Preparation, procedures, test cell, etc were as described in STMX 48. Ref SCE #1 was used and checked as before, difference was less than 0.5 mV.

Test Solution Prep: The test solution was prepared as in STMX 46 from the same lot no. chemicals. Actual salt weights used were 0.1219 g NaHCO₃ and 1.4789 g Na₂SO₄.


Specimen Dimensions: $\phi = 0.635$ cm $l = 1.897$ cm $A = 4.101$ cm²

- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour prior to start
- ③ E con at start -244 mV vs SCE
- ④ E Pt 10 min before start -15 mV
- ⑤ Initial Temp 59.5°C Final Temp 59.5°C
- ⑥ Initial pH 8.18 @ 55°C Final pH 8.99 @ 55°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PRC 273
- ⑩ Auto reverse @ 5000 μ A/cm²

Specimen covered with a dark deposit which easily flaked off. Specimen was uniformly etched all over, except for one circular spot which remained polished. Solution was fairly clean, with a small amount of greenish gelatinous precipitate.

Stored on ECTD #4

Walter J. MacKosh
4/2/91

STMX 51
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
STMX 51
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.118
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-325
4
5318.116
-497.3288
.1743565
5318.116

LEGEND

STATISTICAL MATRIX ON CDA 102
SO4=20; F=2; HCO3=85; T=95 C
CL=1000; NO3=1000
DE-AERATE W/ARGON
DONE ON PARC 173/276

2 APR 1991

Cyclic Polarization of CDA 102

Model solution: CL=1000, NO3=1000, SO4=20, F=2, HCO3=85 95°C

STMX 51

Purpose: Same as STMX 43.

The test specimen was CDA 102 (heat #6681), fabricated at SRI. Preparation, procedures, cell, etc were as described in STMX 43. Ref SCE #4 was used and checked as before, difference was less than 0.5 mV.

Test Solution Prep: The test solution was prepared as in STMX 45 except 1.3793 g of NaNO3 was added instead of the 10.0 ml of NO3 stock solution. The same chemical & solution lot no's were used. Actual salt weights were 0.1220 g of NaHCO3 and 1.653 g of NaCl.


Specimen Dimensions: $\phi = 0.634$ cm $l = 1.909$ cm $A = 4.118$ cm²

- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before starting
- ③ E corr at start -325 mV vs SCE
- ④ E Pt 10 min before start -130 mV
- ⑤ Initial Temp. 94.5°C Final Temp. 94.0°C
- ⑥ Initial pH 8.06 @ 25°C Final pH 9.52 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 μ A/cm²

Specimen had a reddish brown, flaky deposit which came off easily. Grains were visible, as uniform dissolution occurred all over the specimen. Test solution was a golden yellow color.

Saved on disk EA+G #5.

Walter J. Machowski
4/2/91

STMX 52
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
STMX 52
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.113
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-367
4
6272.794
0
0
6272.794

LEGEND

STATISTICAL MATRIX ON CDA 715
S04=20; NO3=10; F=2; HCO3=85; T=95 C
CL=1000
DE-AERATE W/ARGON
DONE ON 273

3 APR 1991

Cyclic Voltammetry of CDA 715
Model solution: CL=1000, S04=20, NO3=10, F=2, HCO3=85 95°C

STMX 52

Purpose: same as STMX 48.

Test specimen was CDA 715 (heat 7037) fabricated at SRI.
Preparation, procedure, cell, etc were as described in STMX 48.
Ref SCE²⁴ was used and checked as before, difference was less than 0.5 mV.

Test solution prep: solution was prepared as in STMX 45 with the same lot # chemicals & solutions. Actual salt weights were 0.1223 g NaHCO₃ and 1.0488 g NaCl.


Specimen Dimensions: $\phi = 0.635$ cm $l = 1.903$ cm $A = 4.113$ cm²

- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start
- ③ E scan at start -367 mV vs SCE
- ④ E PC 10 min before start -85 mV
- ⑤ Initial Temp. 95.0°C Final Temp 94.5°C
- ⑥ Initial pH 8.12 @ 35°C Final pH 9.83 @ 35°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/ln)
- ⑧ Argon purge
- ⑨ Done on PRC 273
- ⑩ Auto-reverse @ 5000 μ A/cm²

Specimen was covered with a copper colored, loose, flaky, film. Underneath there was general corrosion all over the specimen, except for a few round spots (probably where gas bubbles hung). Solution had a yellowish tinge with some orange-brown gelatinous precipitate.

Stored on disk EGTG #4.

Walter J. MacKowski



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	STMX 53
INITIAL E(MV)	0 VS E
VERTEX E(MV)	100 VS E
FINAL E(MV)	100 VS E
SCAN RATE(MV/S)	.17
THRESHOLD I(UA/CM ²)	5000
CONDITION E(MV)	PASS
CONDITION T(S)	PASS
INIT DELAY(MV/S OR S)	3600 S

SAMPLE PARAMETERS


AREA(CMS ²)	4.106
EQ WT(GM)	PASS
DENSITY(GM/CM ³)	PASS
CATHODIC TAFEL(MV)	PASS
ANODIC TAFEL(MV)	PASS

DATA SCALE

ECORR	-286
MV/PT	4
DATA MAX	5577.204
DATA MIN	-49.87823
ABS MIN	2.873843E-02
ABS MAX	5577.204

LEGEND

STATISTICAL MATRIX ON CDA 102
S04=20;N03=10;F=2;HCO3=85;T=95 C
CL=1000
PURGE W/1ATM CO2
DONE ON PARC 173/276

STMX 53
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
STMX 53
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.106
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-286
4
5577.204
-49.87823
2.873843E-02
5577.204

LEGEND

STATISTICAL MATRIX ON CDA 102
S04=20; N03=10; F=2; HCO3=85; T=95 C
CL=1000
DE-AERATE W/ARGON
DONE ON PARC 173/276

4 APR 1991

Cyclic Polarization of CDA 102
Model Solution: $Cl=1000, SO_4=20, NO_3=10, F=2, HCO_3=85, 95^\circ C, CO_2$ 85

STMX 53

Purpose: Same as STMX 43.

The specimen was CDA 102 (heat #6681). Preparation, procedures, cell, etc were as described in STMX 17(p.9). Ref SCE #4 was used and checked as before, difference was less than 0.5 mV.

Test Solution Prep: The test solution was prepared as in STMX 45 with the same lot # chemicals & solutions. Actual salt weights were 0.1225 g $NaHCO_3$ and 1.6477 g $NaCl$.



Specimen dimensions: $\phi = 0.634 \text{ cm}$ $l = 1.903 \text{ cm}$ $A = 4.106 \text{ cm}^2$

- ① Specimen not pre-passivated, all surfaces polished to 600 grit
- ② Specimen held at open circuit for one hour before start
- ③ E scan at start -288 mV vs SCE
- ④ E Pt 10 min before start +82 mV
- ⑤ Initial Temp. $95.0^\circ C$ Final Temp. $95.0^\circ C$
- ⑥ Initial pH 5.12 @ $25^\circ C$ Final pH 5.20 @ $25^\circ C$
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PARC 173/276
- ⑩ Auto reverse @ 5000 $\mu A/cm^2$

Specimen had flaky, reddish brown deposit. Many visible all over sample as corrosion occurred. Solution remained water clear.

Saved on disk E&A # 4

Walter J. MacKowski
4/4/91



Cyclic Polarization of 316L SS

R7STMX (173/276)
R7RSTMX (273)

Purpose: To run a low chloride solution of J-13 simulated water on both potentiostats to evaluate differences in polarization curves which might be influenced by instrumentation.

Two specimens of 316L SS (heat # P80746) were prepared as in STMX 17. Procedures, etc., were same as in STMX 17. One specimen was run on PARC 273, the other on PARC 173/276. The only difference in set-up was the 273 used a saturated NaCl bridge, and the 173 used a 0.5N NaCl bridge.

One batch of test solution was prepared and used in both test cells. It was prepared as follows: Add 0.2446g of NaHCO_3 (Fisher lot # 886738) to one liter of 17MR water in a 2L volumetric flask. Pipet 20.0ml of Cl stock and 4.0ml of F stock solutions #013-107. Pipet ^{20.0} 40.0ml of NO_3 stock solution #019-63 and 40.0ml of SO₄ stock solution #013-269. Dilute to the mark.


- ① Neither specimen pre-passivated; all surfaces polished to 600 grit
- ② Both held at open circuit for one hour before start
- ③ Argon purge
- ④ Scan rate 0.17 mV/sec

	R7STMX (173/276)	R7RSTMX
① dim.	$\phi = 6.34 \text{ cm}$ $l = 1.905 \text{ cm}$ $A = 4.110 \text{ cm}^2$	$\phi = 6.36 \text{ cm}$ $l = 1.905$ $A = 4.118 \text{ cm}^2$
② E_{can}	-680 mV	-628 mV
③ E_{PT}	-304 mV	-78 mV
④ Temp	$T_i = 95.0^\circ\text{C}$ $T_q = 95.0^\circ\text{C}$	$T_i = 95.0$ $T_q = 95.0^\circ\text{C}$
⑤ pH 8.25	$I_{\text{PH}} = 8.25$ $F_{\text{PH}} = 10.1$ disk $E_{\text{C}} + C \# 5$	$I_{\text{PH}} = 8.25$ $F_{\text{PH}} = 9.91$ $E_{\text{C}} + C \# 4$

R7 solution was water clear; R7R solution had a slight yellowish tinge.

Stored on: R7 → EA+R #5
R7R → EA+R #4

Dante J. MacKoshke
4/5/91

STMX 54
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	STMX 54
INITIAL E (MV)	0 VS E
VERTEX E (MV)	100 VS E
FINAL E (MV)	10 VS E
SCAN RATE (MV/S)	.17
THRESHOLD I (UA/CM^2)	5000
CONDITION E (MV)	PASS
CONDITION T (S)	PASS
INIT DELAY (MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA (CMS^2)	4.097
EQ WT (GM)	PASS
DENSITY (GM/CM^3)	PASS
CATHODIC TAFEL (MV)	PASS
ANODIC TAFEL (MV)	PASS

DATA SCALE

ECORR	-294
MV/PT	4
DATA MAX	7322.431
DATA MIN	2.050281
ABS MIN	2.050281
ABS MAX	7322.431

LEGEND

STATISTICAL MATRIX ON CDA 715
CL=6; S04=20; NO3=10; F=2; T=60 C
CL=85000
DE-AERATE W/ARGON
DONE ON 273
NAHCO3 SOLUTION VIRTUALLY COMPLETE
DUE TO HEATING THE SOL'N WHILE
MIXING
8 APR 1991

Cyclic Polarization of CDA 715
Model Solution: $\text{HCO}_3 = 85,000$, $\text{CL} = 6$, $\text{S04} = 20$, $\text{NO}_3 = 10$, $\text{F} = 2$, 60°C

STMX 54

Purpose: Same as STMX 48.

Test specimen was CDA 715 (heat 7037). Preparation, procedures, cell, etc. were as described in STMX 48. Ref SCE #4 was used and checked as before, difference was less than 0.5 mV.

Test Solution Prep: To 500 ml of 17 M.R. water add 122.12 g of NaHCO_3 (Fisher lot # 897489). Pipet 10.0 ml of CL stock and 2.0 ml of F stock solutions #013-107. Pipet 10.0 ml of NO_3 stock solution #019-63 and 20.0 ml of S04 stock solution number 013-269. Dilute to the mark. Note: This solution was stirred and heated to about 50°C to effect dissolution of the NaHCO_3 , before transferring to the test cell.

Spec. dim 1 $\phi = 0.635$ cm $l = 1.895$ cm $A = 4.097$ cm²


- ① Specimen not pre-passivated; all surfaces polished to 600 grit
- ② Specimen held at open circuit for one hour before start
- ③ E corr at start -294 mV vs SCE
- ④ E Pt 10 min before start - not taken
- ⑤ Initial Temp 60.0°C Final Temp 59.2°C
- ⑥ Initial pH 8.62 @ 25°C Final pH 9.01 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done on PRR 273
- ⑩ Auto reverse @ 5000 $\mu\text{A/cm}^2$

Note: specimen holder had leaked - will re-run this test

Specimen had darkened slightly & had general corrosion all over. Solution was clear w/a slight blue tinge.

Stored on disk EC+G #4

Walter J. Machowski
4/8/91

STMX54R
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (mV)
VERTEX E (mV)
FINAL E (mV)
SCAN RATE (mV/s)
THRESHOLD I (μA/cm²)
CONDITION T (s)
INIT DELAY (mV/s OR s)

CYCLIC POLN
STMX54R
0 VS E
100 VS E
10 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA (cm²)
EQ WT (gm)
DENSITY (gm/cm³)
CATHODIC TAFEL (mV)
ANODIC TAFEL (mV)

4.091
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-346
4
6770.96
.0488878
.0488878
6770.96

LEGEND

STATISTICAL MATRIX ON CDA 715
CL=6; SD4=20; ND3=10; F=2; T=60 C
CL=85000
DE-AERATE W/ARGON
DONE ON 273; THIS IS A RE-RUN OF 54
NAHCO3 SOLUTION VIRTUALLY COMPLETE
DUE TO HEATING THE SOL'N WHILE
MIXING
9 APR 1991

Cyclic Polarization of CDA 715
Solution same as STMX54

STMX54 R

Purpose: Re-run of STMX54 due to leak in specimen holder.

Test specimen, etc were as described in STMX54.
Ref SCE #4 was used and checked as before, difference was less than 0.5 mV.

Test Solution Ref: Same as in STMX54, using same lot # chemicals and solutions. Actual salt weight: 123.02 g NaHCO₃.


Specimen Dim: $\phi = 0.633 \text{ cm}$ $l = 1.899 \text{ cm}$ $A = 4.091 \text{ cm}^2$

- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start.
- ③ E con at start - 346 mV vs SCE
- ④ E Pt 10 min before start - not taken
- ⑤ Initial Temp. 59.5°C Final Temp. 60.0°C
- ⑥ Initial pH 8.27 @ 25°C Final pH 9.06 @ 25°C
- ⑦ Scan rate 0.17 mV/sec (600 mV/hr)
- ⑧ Argon purge
- ⑨ Done in PDR 273
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$

Specimen was slightly darkened with general corrosion all over. Solution was clear.

Stored on disk E-C-#4.

Walter J. MacKowski
4/9/91

STMX 55
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE CYCLIC POLN
STMX 55
O VS E
100 VS E
100 VS E
100 VS E
1.17
5000
PASS
PASS
PASS
3600 S

TECHNIQUE NAME
ORIGINAL E (mV)
VERTICAL E (mV)
FINAL E (mV)
SCAN RATE (mV/s)
THRESHOLD I (μA/cm²)
CONDITION E (mV)
CONDITION T (s)
INIT DELAY (mV/s OR s)

SAMPLE PARAMETERS

AREA (cm²)
EQ WT (gm)
DENSITY (gm/cm³)
CATHODIC TAFEL (mV)
ANODIC TAFEL (mV)

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

LEGEND

STATISTICAL MATRIX ON INC 825
REPEAT OF PREVIOUS CONDITIONS
NO3=10; SO4=20; F=2; HCO3=85
CL=1000; T=95 C
DONE ON PARC 173/276

10 APR 1991

Cyclic Polarization of Inc 825
Model Solution: CL=1000, NO₃=10, SO₄=20, F=2, HCO₃=85 95°C

STMX 55

Purpose: To gather additional data on this condition for purpose of determining variability of the data.

A cylindrical Inc 825 (heat # HH4371FC) was used. Preparation, procedures, cell, etc were as in STMX 17(p.9). Ref SCE #1 was used and checked as before, difference was less than 0.5 mV.

Test Solution Prep: To 500 ml of 17 MΩ water in a 1-liter volumetric add 0.1325 g NaHCO₃ (Fisher lot # 897789) and 1.6487 g of NaCl (Fisher lot # 885407). Pipet 2.0 ml of F stock #013-107; 10.0 ml of NO₃ stock #019-63; and 20.0 ml of SO₄ stock #013-269. dilute to the mark.


Spec. dim: $\phi = 0.631 \text{ cm}$ $l = 1.981 \text{ cm}$ $A = 4.240 \text{ cm}^2$

- ① Specimen not pre-passivated; all surfaces polished to 600 grit
- ② Specimen held at open circuit for one hour before start.
- ③ E was at start -385 mV vs SCE
- ④ E at 10 min before start -308 mV.
- ⑤ Initial Temp. 95.0°C Final Temp. 94.8°C
- ⑥ Initial pH 7.88 @ 25°C Final pH 9.67 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 173/276
- ⑩ Auto reverse @ 5000 μA/cm²

Specimen had many pits, especially evident when probed. Also had moderate crevice attack. Solution was grayish with gelatinous precipitate.

Stored on disk EG+D #5

Walter J. Machowski
4/10/91

STMX 56
CYCLIC POLN

CYCLIC POLN

STMX 56
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (MV)
VERTEX E (MV)
FINAL E (MV)
SCAN RATE (MV/S)
THRESHOLD I (UA/CM^2)
CONDITION E (MV)
CONDITION T (S)
INIT DELAY (MV/S OR S)

SAMPLE PARAMETERS

AREA (CMS^2)
EQ WT (GM)
DENSITY (GM/CM^3)
CATHODIC TAFEL (MV)
ANODIC TAFEL (MV)

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

LEGEND

STATISTICAL MATRIX ON CDA 715
S04=20; F=2; HCO3=85; T=95 C
CL=1000; NO3=1000
DE-AERATE W/ARGON
DONE ON 273

10 APR 1991

Cyclic Polarization of CDA 715

Model Solution: $CL=1000$, $NO_3=1000$, $S04=20$, $F=2$, $HCO_3=85$, $T=95^\circ C$

STMX 56

Purpos: same as STMX 48.

Specimen, preparation, procedures, etc were as in STMX 48. Ref SCE #1 was used & checked as before, difference was less than 0.5 mV.

Test Solution: Add 0.1335 g $NaHCO_3$ (lot #897789), 1.6486 g $NaCl$ and 1.3728 g $NaNO_3$ (same lot #15 as p. 9). Pipet 10.0 ml of Cl^- stock and 2.0 ml of F^- stock solution #013-107, also 20.0 ml of $S04$ stock #013-269. Free "Jm" Add these to 500 ml of 17M H_2O in a 1-liter volumetric & dilute to the mark.

Spec Dim: $\phi = 0.634$ cm $l = 1.893$ cm $A = 4.086$ cm²

- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start
- ③ E_{can} at start -380 mV vs SCE
- ④ E_{Pt} 10 min. before start -190 mV
- ⑤ Initial Temp. $95.0^\circ C$ Final Temp. $95.0^\circ C$
- ⑥ Initial pH $8.10 @ 25^\circ C$ Final pH $9.74 @ 25^\circ C$
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Denson PAR 273
- ⑩ Auto reverse @ $5000 \mu A/cm^2$

Specimen had reddish-brown, flaky film. General corrosion underneath film. Solution had slight yellowish tinge.

Stored on dish E-C #4.

Walter J. Macdonald
4/10/91


Preparation of SO_4 Stock Solution 1000 ppm

Purpose: Stock solution used in preparation of test solutions.

Weigh out 1.4788 g of Na_2SO_4 (Fisher lot # 901213). Dissolve in 500 ml of 17 M H_2O water in a 1-liter volumetric flask & dilute to the mark.

Label as SN CWRRA 019-97

Walter J. Mackowski
4/11/91

STMX 57
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
CYCLIC POLN
STMX 57
O VS E
100 VS E
100 VS E
17
5000
PASS
PASS
PASS
3600 S

INITIAL NAME
ORIGINAL E (MV)
VERTICAL E (MV)
FINAL E (MV)
SCAN RATE (MV/S)
THRESHOLD I (UA/CM^2)
CONDITION E (MV)
CONDITION T (S)
INIT DELAY (MV/S OR S)

SAMPLE PARAMETERS

AREA (CM^2)
EQ WT (GM)
DENSITY (GM/CM^3)
CATHODIC TAFEL (MV)
ANODIC TAFEL (MV)

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

LEGEND

STATISTICAL MATRIX ON INC 825
REPEAT OF PREVIOUS CONDITIONS
CL=6; NO3=10; SO4=20; F=2
HCO3=1000; T=95 C
DONE ON PARC 173/276

11 APR 1991

Cyclic Polarization on Inc 825
Model Solution: $\text{HCO}_3 = 1000$, $\text{Cl} = 6$, $\text{NO}_3 = 10$, $\text{SO}_4 = 20$, $F = 2$ 95°C

STMX 57

Purpose: Same as STMX 55.

The test specimen, preparation, procedures, test cell, etc. were as described in STMX 55. Ref SCE #4 was used and checked as before, difference was less than 0.5 mV.

Test Solution Prep: To 500 ml of 17M Ω water in a 1-liter volumetric add 1.4354 g NaHCO_3 (Lot # 897789). Pipet 10.0 ml of Cl stock + 20 ml of F stock solution #013-107, also 10.0 ml of NO_3 stock solution #019-63, and 20.0 ml of SO_4 stock solution #019-97, dilute to the mark.


Specimen Dimensions: $\phi = 0.633 \text{ cm}$ $l = 2.049 \text{ cm}$ $A = 4.389 \text{ cm}^2$

- ① Specimen not pre-passivated; all surfaces polished to 600 grit
- ② Specimen held at open circuit for one hour before start
- ③ E_{corr} at start -460 mV vs SCE
- ④ E_{PT} 10 min before start -186 mV
- ⑤ Initial Temp. 95.0°C Final Temp. 94.8°C
- ⑥ Initial pH — not taken Final pH — not taken
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 173/276
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$

Specimen had no pits + retained its metallic luster.
Solution was water clear

Stored on EP4 #5

Walter J. MacKowski
4/11/91

STMX 58
CYCLIC POLNCYCLIC POLN
STMX 58
0 VS E
100 VS E
100 VS E
-17SCAN RATE (MV/S)
THRESHOLD I (UA/CM^2)
CONDITION E (MV)
CONDITION T (S)
INIT DELAY (MV/S OR S)

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (MV)
VERTEX E (MV)
FINAL E (MV)SAMPLE PARAMETERS
AREA (CMS^2)
EQ WT (GM)
DENSITY (GM/CM^3)
CATHODIC TAFEL (MV)
ANODIC TAFEL (MV)

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

LEGEND

STATISTICAL MATRIX ON CDA 715
SD4=20; NO3=10; F=2; HCO3=85
CL=1000; T=95 C
PURGE W/1ATM CO2
DONE ON 273

11 APR 1991

Cyclic Polarization on CDA 715

Model Solution: CL=1000, NO₃=10, SO₄=20, F=2, HCO₃=85 95°C CO₂

STMX 58

Purpose: Same as STMX 48

The specimen, preparation, procedure, etc were as in STMX 48. Ref SCE #1 was used and checked as before, difference was less than 0.5 mV.

Test Solution Prep: Solution was prepared as in STMX 52. with the same lot # chemicals & solutions WJM

same lot # chemicals & solutions, except NaHCO₃ (new lot # 897789) and SO₄ stock sol'n (new # 019-97) Actual weights were 0.1326g NaHCO₃ and 1.16481g NaCl.


Spec. Dim: $\phi = 0.635 \text{ cm}$ $l = 1.902 \text{ cm}$ $A = 4.111 \text{ cm}^2$

- ① Specimen not pre-passivated; all surfaces polished to 600 grit
- ② Specimen held at open circuit for one hour before start.
- ③ E cor at start -246 mV vs SCE
- ④ E pt 10 min. before start +181 mV
- ⑤ Initial Temp, 95.0°C Final Temp, 95.0°C
- ⑥ Scan rate 0.17 mV/sec
- ⑦ Initial pH 5.12 @ 25°C Final pH 5.08 @ 25°C
- ⑧ Argon purge
- ⑨ Done on POR 273
- ⑩ Auto reverse @ 5000 $\mu\text{A/cm}^2$

Specimen had a reddish-brown flaky film. General corrosion evident beneath the film. Solution was water clear.

Stored on disk EC+C #4

Walter J. Macdonald
4/11/91

STMX 59
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (mV)
VERTEX E (mV)
FINAL E (mV)
SCAN RATE (mV/s)
THRESHOLD I (uA/cm²)
CONDITION E (mV)
CONDITION T (s)
INIT DELAY (mV/s OR s)

CYCLIC POLN
STMX 59
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA (cm²)
EQ WT (gm)
DENSITY (gm/cm³)
CATHODIC TAFEL (mV)
ANODIC TAFEL (mV)

4.356
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-498
4
20684.11
-470.1561
2.984389E-03
20684.11

LEGEND

STATISTICAL MATRIX ON INC 825
NO3=10; SO4=20; F=21; T=95 C
CL=1000; HCO3=1000
DE-AERATE W/ARGON
DONE ON PAR 173/276

12 APR 1991

Cyclic Polarization of Dac 825
Model Solution: $CL=1000$, $HCO_3=1000$, $NO_3=10$, $SO_4=20$, $F=2$ 95°C
STMX 59

Purpose: Same as STMX 55.

The test specimen, preparation, procedures, test cell, etc were as described in STMX 55. Ref SCE #4 was used and checked as before, difference was less than 0.5 mV.

Test Solution Prep: To 500 ml of 17 M.D. water in a 1-liter volumetric add 1.4359 g $NaHCO_3$ (Fisher lot # 897789) and 1.6487 g $NaCl$ (Fisher lot # 885407). Pipet 2.0 ml of F stock solution #013-107, 10.0 ml of NO_3 stock solution #019-63, and 20.0 ml of SO_4 stock solution #019-97, dilute to the mark.


Specimen Dimensions: $\phi=0.632$ cm $l=2.036$ cm $A=4.356$ cm²

- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start
- ③ E cor at start -498 mV vs SCE
- ④ E Pt 10 min before start -241 mV
- ⑤ Initial Temp. 93.0°C Final Temp. 94.0°C
- ⑥ Initial pH—not taken Final pH—not taken
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 173/276
- ⑩ Auto-reverse @ 5000 $\mu A/cm^2$

Specimen discolored + had many pits, especially evident when probed. Small amount of white attack. Solution murky w/ grayish-green gelatinous precipitate.

Stored on disk EDC #5

Walter J. MacKowski
4/15/91

STMX 60
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (mV)
VERTEX E (mV)
FINAL E (mV)
SCAN RATE (mV/s)
THRESHOLD I (μA/cm²)
CONDITION E (mV)
CONDITION T (s)
INIT DELAY (mV/s OR s)

CYCLIC POLN
STMX 60
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA (CM²)
EQ WT (GM)
DENSITY (GM/CM³)
CATHODIC TAFEL (mV)
ANODIC TAFEL (mV)

4.132
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-568
4
14569.22
-3775412
0
14569.22

LEGEND

STATISTICAL MATRIX ON INC 825
NO3=10; SO4=20; F=2; T=95 C
CL=1000; HCO3=1000
DE-AERATE W/ARGON
DONE ON PAR 273
RE-RUN OF CONDITION STMX 59

18 APR 1991

Cyclic Polarization of Inc 825
Model Solution: $Cl=1000$, $HCO_3=1000$, $NO_3=10$, $F=2$, $SO_4=20$ 95°C

STMX 60

Purpose: Same as STMX 55.

The test specimen, heat #, preparation, procedures, etc were as described in STMX 55. Ref SE #4 was used and checked as before, difference was less than 0.5 mV.

Test Solution Prep: To 500 ml of 17 M H_2O in a 1-liter volumetric add 1.6484 g NaCl and 1.4358 g $NaHCO_3$ (Fisher lot #'s 885407 and 897789), Pipet 20.0 ml of SO_4 stock, 2.0 ml of F stock, and 10.0 ml of NO_3 stock solutions, same lot #'s as p. 103. Dilute to the mark.

Specimen Dimensions: $\phi = 0.638$ cm $l = 1.902$ cm $A = 4.132$ cm²

- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start.
- ③ E corr at start -568 mV vs SCE
- ④ E Pt 10 min. before start -177 mV
- ⑤ Initial Temp. 95.0°C
- ⑥ Initial pH 8.55 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PDR 273.
- ⑩ Auto reverse @ 5000 $\mu A/cm^2$


Final Temp. 94.5°C

Final pH 9.91 @ 25°C

Specimen had brownish deposits and many pits. Moderate amount of crevice corrosion had occurred. Solution had a slight yellow tinge + some gelatinous precipitate.

Stored on disk EC-V-5.

Walter J. Nachowiak
4/18/91

STMX 61
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (mV)
VERTEX E (mV)
FINAL E (mV)
SCAN RATE (mV/s)
THRESHOLD I (uA/cm²)
CONDITION E (mV)
CONDITION T (s)
INIT DELAY (mV/s OR s)

CYCLIC POLN
STMX 61
0 VS E
100 VS E
100 VS E
-17
5000
PASS
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA (cm²)
EQ WT (gm)
DENSITY (gm/cm³)
CATHODIC TAFEL (mV)
ANODIC TAFEL (mV)

4.121
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-540
4
5338.51
-4149478
0
5338.51

LEGEND

STATISTICAL MATRIX ON INC 825
NO3=10; SO4=20; F=2; T=95 C
CL=1000; HCO3=2000
DE-AERATE W/ARGON
DONE ON PAR 273

22 APR 1991

Cyclic Polarization of Inc 825
Model Solution: CL=1000, HCO₃=2000, NO₃=10, F=2, SO₄=20 95°C

STMX 61

Purpose: Same as STMX 55.

The test specimen, heat #, preparation, procedures, etc were as described in STMX 55. Ref SCE #4 was used and checked as before, difference was less than 0.5 mV.

Test Solution Prep: Test solution was made as in STMX 60 using the same lot # chemicals and solutions, except 2.8708 g of NaHCO₃ were added. Actual NaCl weight was 1.6481 g.

Specimen Dim: $\phi = 0.637 \text{ cm}$ $l = 1.900 \text{ cm}$ $A = 4.121 \text{ cm}^2$


- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start.
- ③ E corr at start -540 mV vs SCE
- ④ E pt 10 min before start -212 mV.
- ⑤ Initial Temp. 95.2°C Final Temp. 95.0°C
- ⑥ Initial pH 8.55 @ 25°C Final pH 9.91 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Auto reverse @ 5000 $\mu\text{A/cm}^2$

Specimen had only a few pits & brownish deposits. These were at the bottom flat surface & around the upper edge near the TFE mounting gasket. This is where bubbles tend to cling. Small amount of crevice corrosion occurred. Solution remained water clear.

Stored on disk E6+C #5.

Walter J. Mocharhi
4/22/91

STMX 62
CYCLIC POLN



CYCLIC POLN

CYCLOC
STMX 62
O VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

RUN PARAMETERS

```

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

```

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

DATA SCALE

RECORG	
W/PT	4
DATA MAX	9656.706
DATA MIN	0
ABS MIN	0
ABS MAY	9656.706
	-637

LEGEND

STATISTICAL MATRIX ON 316L SS
NO3=10; SO4=20; F=2; T=95 C
CL=1000; HCO3=1000
DE-AERATE W/ARGON
DONE ON PAR 273

23 APR 1991

Cyclic Polarization of 316L SS
Model solution: $\text{Cl} = 1000$, $\text{HCO}_3 = 1000$, $\text{SO}_4 = 20$, $\text{F} = 2$, $\text{NO}_3 = 10$ 95°C

STMX 62

Purpose: Same as SVMX 17 (p.9)

The test specimen, heat #, preparation, procedure, etc were as described in SYMX 17. Ref SCE #4 was used and checked as before, difference was less than 0.5 mV.

Test solution prep: Test solution was as in S0MX 60 using same lot # chemicals and solutions. Actual salt weights were 1.6488g NaCl and 1.4358g NaHCO_3


Spec. dim: $\phi = 0.639 \text{ cm}$ $l = 1.842 \text{ cm}$ $A = 4.049 \text{ cm}^2$

- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start.
- ③ E_{scan} at start -638 mV vs SCE
- ④ E_{Pt} 10 min before start -170 mV
- ⑤ Initial Temp. 95.5°C Final Temp. 94.8°C
- ⑥ Initial pH $8.44 @ 25^\circ\text{C}$ Final pH $9.85 @ 25^\circ\text{C}$
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Above an PPR 273
- ⑩ Auto reverse @ $5000 \mu\text{A/cm}^2$

Specimen was discolored with many pits. Moderate amount of crevice corrosion. Solution was tinged yellow of gelatinous precipitate.

Stored on disk E0+C #5.

Walter J. Mackowski
4/23/91



RUN PARAMETERS
 TECHNIQUE
 ORIGINAL NAME
 INITIAL E (mV)
 VERTEX E (mV)
 FINAL E (mV)
 SCAN RATE (mV/s)
 THRESHOLD I (uA/cm^2)
 CONDITION E (mV)
 CONDITION T (s)
 INIT DELAY (mV/s OR s)

SAMPLE PARAMETERS
 AREA (cm^2)
 EQ WT (GM)
 DENSITY (GM/CM^3)
 CATHODIC TAFEL (mV)
 ANODIC TAFEL (mV)

DATA SCALE
 ECORR
 MV/PT
 DATA MAX
 DATA MIN
 ABS MIN
 ABS MAX

LEGEND
 STATISTICAL MATRIX ON 316L SS
 NO3=10; SO4=20; F=2; T=95 C
 CL=6; HCO3=1000
 DE-AERATE W/ARGON
 DONE ON PAR 273

26 APR 1991

Cyclic Polarization of 316L SS
 Model Solution: Cl^- , HCO_3^- , NO_3^- , F^- , SO_4^{2-} 95°C
 STMX 64 Cl^- 1000 uA/cm Cl^- 6, HCO_3^- 1000 uA/cm
 Purpose: Same as STMX 17.

The test specimen, heat #, preparation, etc were as described in STMX 17. Ref SCE #4 was used and checked as before, difference was less than 0.5 mV.

Test Solution Prep: To 500 ml of 17 M Ω water in a 1-liter volumetric flask add 1.4358 g of NaHCO_3 (lot # on p. 105). Pipet 10.0 ml of Cl^- stock, 2.0 ml of F^- stock, 10.0 ml of NO_3^- stock, and 20.0 ml of SO_4^{2-} stock solutions (#'s 013-107, 013-107, 019-63, 019-97 resp). Dilute to the mark.


Specimen Dim: $\phi = 0.635$ cm $l = 1.90$ cm $A = 4.109$ cm²

- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start
- ③ E_{com} at start -704 mV vs SCE
- ④ E_{PT} 10 min before start -175 mV
- ⑤ Initial Temp. 95.0°C Final Temp. 95.0°C
- ⑥ Initial pH 8.59 @ 25°C Final pH 10.02 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$

Specimen had no pits & retained its metallic luster. Solution remained water clear.

Stored on disk 10-6-#5.

Walter J. Macroski
 4/26/91



CYCLIC POLN

TECHNIQUE		CYCLIC PD
ORIGINAL NAME	STNX 65	
INITIAL E(MV)	0 VS E	
VERTEX E(MV)	100 VS E	
FINAL E(MV)	100 VS E	
SCAN RATE(MV/S)	.17	
THRESHOLD I(UA/CW*2)	5000	
CONDITION E(MV)	PASS	
CONDITION T(S)	PASS	
UNIT DELAY(MV/S OR S)	3600 S	

RUN PARAMETERS

SAMPLE PARAMETERS

AREA(CMS~2)	4.111
EQ WT(GM)	PASS
DENSITY(GM/CM^3)	PASS
CATHODIC TAFEL(MV)	PASS
ANODIC TAFEL(MV)	PASS
E	
ECORR	-569
MV/PT	4
DATA MAX	1785.454
DATA MIN	-7.540745E-02
ABS MIN	3.648747E-02
ABS MAX	1785.454

DATA SCALE

LEGEND

STATISTICAL MATRIX ON 304L SS
N03=10;S04=20;F=2;T=95 C
CL=6;HC03=85
DE-AERATE W/ARGON
DONE ON PAR 273

29 APR 1991

Cyclic Polarization of 304L SS
Model Solution: $Cl = 0, HCO_3 = 85, NO_3 = 10, F = 2, SO_4 = 20$ 95°C
STMX 65

Purpose: To obtain data of effects of various ion concentrations on 304L SS.

The specimen was cylindrical, fabricated at SwRI, from 304L SS heat # T0954. Preparation, procedures, cell, was as in STMX 17. Ref SCE #4 was used and checked as before, difference was less than 0.5 mV.

Test Solution Prep: To 500 ml of 12M H_2SO_4 water in a 1-liter volumetric add 0.1254 g NaHCO_3 (lot # Fisher 897789). Pipet 6.0 ml of Cl stock, 2.0 ml of F stock, 10.0 ml of NO_3 stock, and 30.0 ml of SO_4 stock solutions, same lot #'s as on p. 113. Dilute to the mark.


Spec. Dim: $\phi = 0.635 \text{ cm}$ $l = 1.902 \text{ cm}$ $A = 4.111 \text{ cm}^2$

- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen hld at open circuit for one hour before start
- ③ E_{com} at start -569 mV vs SCE
- ④ E_{Pt} 10 min. before start -266 mV
- ⑤ Initial Temp. 95.0°C Final Temp 95.0°C
- ⑥ Initial pH $8.35 @ 25^\circ\text{C}$ Final pH $10.04 @ 25^\circ\text{C}$
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Manual reverse @ $7300 \mu\text{A} / +1519 \text{ mV}$

Specimen had its 'metallic' luster & was pit free except one spot where bubbles tend to cling at top of specimen. One small spot of crevice corrosion. Solution remained water clear.

Stored on disk L2 & P#5

Walter J. Nachowski
4/29/91

STMX 66
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(μA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
STMX 66
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.114
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-681
4
2372.387
4.861449E-03
4.861449E-03
2372.387

LEGEND

STATISTICAL MATRIX ON 304L SS
N03=10; S04=20; F=2; T=95 C
CL=6; HCO3=85
DE-AERATE W/ARGON
DONE ON PAR 273
1ST REPETITION

30 APR 1991

Cyclic Polarization of 304L SS
Model Solution: Same as p.115
STMX 66

Purpose: Same as STMX 65 (1st replication run)

The test specimen, heat #, preparation, procedures, etc were as described in STMX 65. Ref SCE #4 was used and checked as before, difference was less than 0.5 mV.

Test Solution Prep: Solution was prepared as in STMX 65 using the same lot # chemicals and solutions. Actual salt weight was 0.1223 g NaHCO₃.

Specimen Dimensions: $\phi = 0.634$ cm $l = 1.907$ cm $A = 4.114$ cm²


- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start.
- ③ E scan at start -681 mV vs SCE
- ④ E Pt 10 min. before start -272 mV
- ⑤ Initial Temp. 95.4°C Final Temp. 95.0°C
- ⑥ Initial pH 8.50 @ 25°C Final pH 10.00 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Manual reverse @ 9600 μ A / +1487 mV

Specimen was free of pits, & discoloration. It retained its metallic luster. Solution remained water clear.

Stored on disk EP+P#5

Walter J. MacKowski
5/1/91

STMX 67
CYCLIC POLN



CYCLIC POLN

STMX 67
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

TECHNIQUE
ORIGINAL NAME
INITIAL E (MV)
VERTEX E (MV)
FINAL E (MV)
SCAN RATE (MV/S)
THRESHOLD I (UA/CM²)
CONDITION E (MV)
CONDITION T (S)
INIT DELAY (MV/S OR S)

SAMPLE PARAMETERS

AREA (CMS²)
EQ WT (GM)
DENSITY (GM/CM³)
CATHODIC TAFEL (MV)
ANODIC TAFEL (MV)

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

LEGEND

STATISTICAL MATRIX ON 304L SS
ND3=10; SD4=20; F=2; T=95 C
CL=6; HCO3=85
DE-AERATE W/ARGON
DONE ON PAR 273
2ND REPETITION

1 MAY 1991

Cyclic Polarization of 304L SS
Model Solution: Same as STMX 65

STMX 67

Purpose: Same as STMX 65 (2nd replication run)

The test specimen, heat #, preparation, procedures, etc were as described in STMX 65. Ref SCE #4 was used and checked as before, difference was less than 0.5 mV.

Test Solution Prep: Solution was prepared as in STMX 65 with same lot # chemicals and solutions. Actual salt weights were 0.1255 g NaHCO₃.


Specimen Dimensions: $\phi = 0.636 \text{ cm}$ $l = 1.905 \text{ cm}$ $A = 4.124 \text{ cm}^2$

- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start.
- ③ E scan at start -709 mV vs SCE
- ④ E Pt 10 min before start -185 mV
- ⑤ Initial Temp. 95.5°C Final Temp. 95.0°C
- ⑥ Initial pH 8.37 @ 25°C Final pH 10.04 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Manual reverse @ 6830 μA / +1507 mV

Specimen had one pit + two spots of discoloration at end near TFE mount. One spot of crevice corrosion. Solution remained water clear.

Stored on disk ECV-5.

Walter J. MacKowski
5/1/91

STMX 68
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (mV)
VERTEX E (mV)
FINAL E (mV)
SCAN RATE (mV/s)
THRESHOLD I (uA/cm²)
CONDITION E (mV)
CONDITION T (s)
INIT DELAY (mV/s OR s)

CYCLIC POLN
STMX 68
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA (cm²)
EQ WT (gm)
DENSITY (gm/cm³)
CATHODIC TAFEL (mV)
ANODIC TAFEL (mV)

4.122
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-618
4
5215.915
-.0727802
2.426007E-02
5215.915

LEGEND

STATISTICAL MATRIX ON 304L SS
NO3=10; NO4=20; F=2; T=95 C
CL=6; HCO3=1000
DE-AERATE W/ARGON
DONE ON PAR 273

2 MAY 1991

Cyclic Polarization of 304L SS
Model Solution: $\text{HCO}_3=1000$, $\text{CL}=6$, $\text{NO}_3=10$, $F=2$, $\text{SO}_4=20$ 95°C

STMX 68

Purpose: Same as STMX 65.

The test specimen, heat #, preparation, etc were as described in STMX 65. Ref SCE #4 was used and checked as before, difference was less than 0.5 mV.

Test Solution Prep: Solution was prepared as in STMX 65 with same lot # chemicals and solutions, except that 1.455 g of NaHCO_3 were added. *w/analytical*


Spec. Dim: $\phi = 0.636$ cm $l = 1.904$ cm $A = 4.122$ cm²

- ① Specimen not pre-passivated; all surfaces polished to 600 grit
- ② Specimen held at open circuit for one hour before start.
- ③ E scan at start -618 mV vs SCE
- ④ E Pt 10 min. before start -190 mV
- ⑤ Initial Temp. 95.4°C Final Temp. 95.5°C
- ⑥ Initial pH 8.54 @ 25°C Final pH 9.93 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$

Specimen had no pits & retained its metallic luster. Solution remained water clear

Stored on disk EPD #5

Walter J. Macchiaschi
5/5/91



RUN PARAMETERS

TECHNIQUE
G5 1-91
ORIGINAL NAME
O VS E
INITIAL E (MV)
1600 VS R
FINAL E (MV)
.17
SCAN RATE (MV/S)
PASS
CONDITION E (MV)
PASS
CONDITION T (S)
PASS
INIT DELAY (MV/S OR S)
PASS 3600 S

SAMPLE PARAMETERS

AREA (CMS^2)
3.398
EQ WT (GM)
PASS
DENSITY (GM/CM^3)
PASS
CATHODIC TAFEL (MV)
PASS
ANODIC TAFEL (MV)
PASS

DATA SCALE

ECORR
-510
MV/PT
2
DATA MAX
17510.3
DATA MIN
-602.7075
ABS MIN
1.247793
ABS MAX
17510.3

LEGEND

G5 STD RUN ON PAR 173/276
INSTRUMENT BACK FROM CAL LAB
IN H2SO4 AT 30 C
ARGON PURGE

3 MAY 1991

G5 1-91

Purpose: PAR 173 calibrated by cal lab - test to check function of instrument

Test was run in accordance with G5 procedure using ASTM supplied 430SS specimen.

Initial Temp. 31.0°C Final Temp. 30.0°C
E PT @ 55 minutes immersion -503 mV vs SCE
30 w/machmark

E cor @ 55 minutes immersion -518 mV " "


Spec. Dim $\phi = 0.931 \text{ cm}$ $l = 0.929 \text{ cm}$ $A = 3.398 \text{ cm}^2$

Stored on disk EPR #5

Walter J. Machowski
5/3/91

0 Storm interrupted right after start - restarted in

G61 91A
CYCLIC POLN



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
G61 91A
0 VS E
100 VS R
-100 VS E
.17
5000
PASS
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.122
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-449
4
11620.57
.0346919
.0346919
11620.57

LEGEND

G61 TEST ON 304L SS
RUN ON PAR 173/276
INSTRUMENT BACK FROM CAL LAB
ARGON PURGE

6 MAY 1991

G61 91A

Purpose: same as P5 on page 123

Test was run in accordance with G61 procedures. A cylindrical 304L SS (Lot# T0954) specimen was used.

Temperature was at 25°C for the whole test

E Pt @ 50 min. immersion +455 mV vs SCE

E cor at start -449 mV

Spec Dim $\phi = 0.636$ cm $l = 1.904$ cm $A = 4.122$ cm²

Standard disk E610-#5


Walter J MacKowski
5/6/91

Preparation of 600 ppm Cl Stock Solution
Purpose: For use in preparation of test solutions.

Weigh out 0.9875 g of NaCl (Fisher lot # 885407). Dissolve in 500 ml of 17 M Ω water in a 1-liter volumetric flask & dilute to the mark.

Labeled as 3N CNWRA 019-127.

Walter J. Mosley
5/23/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

POTENTIODYNAMIC
G5 2-91
O VS E
1600 VS R
.17
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

3.354
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-513
2
16785.93
-5.948122
2.534287E-02
16785.93

LEGEND

G5 STD RUN ON PAR 273
RUN AT END OF STMX SERIES
IN H2SO4 AT 30 C
ARGON PURGE

20 MAY 1991

G5 2-91

Purpose: G5 test is run after a series of tests. This one is for the end of the STMX series

Test was run in accordance with G5 procedure using ASTM supplied 430SS specimen.


Initial Temp. 30.5°C Final Temp. 30.0°C

E Pt 50 min. after immersion -201 mV
E can 55 " " " -514 mV

Spec. Dim. $\phi = 0.923 \text{ cm}$ $l = 0.926 \text{ cm}$ $A = 3.354 \text{ cm}^2$

Stored on disk ETOB #5.

Walter J. Macbourn
5/24/91



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	G61 91B
INITIAL E(MV)	0 VS E
VERTEX E(MV)	100 VS R
FINAL E(MV)	-100 VS E
SCAN RATE(MV/S)	.17
THRESHOLD I(UA/CM^2)	5000
CONDITION E(MV)	PASS
CONDITION T(S)	PASS
INIT DELAY(MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA(CMS^2)	4.122
EQ WT(GM)	PASS
DENSITY(GM/CM^3)	PASS
CATHODIC TAFEL(MV)	PASS
ANODIC TAFEL(MV)	PASS

DATA SCALE

ECORR	-607
MV/PT	4
DATA MAX	18219.31
DATA MIN	-.359049
ABS MIN	2.426007E-04
ABS MAX	18219.31

LEGEND

G61 TEST ON 304L SS
RUN ON PAR 273
END OF STMX SERIES
ARGON PURGE

29 MAY 1991

G61 91-B

Purpose: Same as G5 on page 129.

The test was run in accordance with G61 procedures. A cylindrical 304L SS (heat # T0954) specimen was used.

Temperature was 25°C for the entire test.


E Pt @ 50 min immersion +350 mV

E corr at start -607 mV

Spec. Dim $\phi = 0.914 \text{ cm}$ $l = 1.250 \text{ cm}$ $A = 4.245 \text{ cm}^2$

Stored on disk EC+G #5.

Walter J. Macdonald
5/24/91



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	CDA 1
INITIAL E (MV)	0 VS E
VERTEX E (MV)	100 VS E
FINAL E (MV)	100 VS E
SCAN RATE (MV/S)	.17
THRESHOLD I (UA/CM^2)	5000
CONDITION E (MV)	PASS
CONDITION T (S)	PASS
INIT DELAY (MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA (CMS^2)	4.106
EQ WT (GM)	PASS
DENSITY (GM/CM^3)	PASS
CATHODIC TAFEL (MV)	PASS
ANODIC TAFEL (MV)	PASS

DATA SCALE

ECORR	-249
MV/PT	4
DATA MAX	5504.14
DATA MIN	.0243546
ABS MIN	.0243546
ABS MAX	5504.14

LEGEND

CDA 715; RUN 1; TRIAL 6
DE-AERATE W/ARGON
HCO₃=8500; SO₄=1000; T=30
CL=6; NO₃=10; F=2

DONE ON PAR 273
25 JUNE 1991

Cyclic Polarization of CDA 715
Model Solution: CL=6, NO₃=10, F=2, HCO₃=8500, SO₄=1000 T=30

CDA 1 (Run #1 Trial #6)


Purpose: To collect data for evaluation of effects of various selected ionic species on the corrosion of CDA-102 and CDA-715 using a factorial experiment.

The test specimen was cylindrical CDA-715 (lot # 7037). Preparation, procedures, cell, etc were as in STMX 17 (p.9). Reference SCE #4 was used, and checked as before, difference was less than 1.0 mV.

Test Solution Prep: To 500 ml of 17 MR water in a 1-liter volumetric add 12.198 g of NaHCO₃ and 1.4792 g Na₂SO₄ (Fisher lot #'s 897789 and 901213). Pipet 10.0 ml of NO₃ stock, 2.0 ml of F stock, and 0.0 ml of Cl stock solutions, # 019-63, 013-107, and 019-127 resp. Dilute to the mark.

Spec Dim $\phi = 0.636$ cm $l = 1.896$ cm $A = 4.106$ cm²

- Spec not pre-passivated; all surfaces polished to 600 grit.
- Spec held at open circuit for one hour before start.
- E con at start -249 mV vs SCE
- E Pt 10 min before start -130 mV
- Initial Temp 31.0°C Final Temp 31.0°C
- Initial pH 8.34 Final Temp 9.25
- Scan rate 0.17 mV/sec
- Argon purge
- Done on PAR 273
- Auto reverse @ 5000 μ A/cm²




Stored on disk ECRB #5.

Specimen had dark coating w/ areas of light bluish-green corrosion product. Solution remained clear. Some shallow pits where corrosion product was observed.

On the ends, deep pits surrounded by spongy red deposit which is surrounded by green deposit (Basic CuCO₃?) was observed.

Walter J. MacKowski
6/25/91



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	CDA 2
INITIAL E(MV)	0 VS E
VERTEX E(MV)	100 VS E
FINAL E(MV)	100 VS E
SCAN RATE(MV/S)	.17
THRESHOLD I(UA/CM^2)	5000
CONDITION E(MV)	PASS
CONDITION T(S)	PASS
INIT DELAY(MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA(CMS^2)	4.123
EQ WT(GM)	PASS
DENSITY(GM/CM^3)	PASS
CATHODIC TAFEL(MV)	PASS
ANODIC TAFEL(MV)	PASS

DATA SCALE

ECORR	-342
MV/PT	4
DATA MAX	6621.392
DATA MIN	-2328402
ABS MIN	0
ABS MAX	6621.392

LEGEND

CDA RUN 2; TRIAL 11
DE-AERATE W/ARGON
HCO3=85; SO4=20; NO3=10; F=2
CL=1000; T=95

DONE ON PAR 273
27 JUNE 1991

Cyclic Polarization of CDA 715
Model Solution: CL=1000, SO4=20, NO3=10, F=2, HCO3=85 95°C
CDA 2 Run #2 Trial 11 approx. 11
(Purpose: Same as CDA 1.

The test specimen was as described in CDA 1.
Preparation, procedures, etc were as described in 500X17(p.9).
Ref SCE #4 was used, and checked as before, difference was less than 10 mV.

Test Solution Prep: To 500 ml of 17 MΩ water in a 1-liter volumetric add 0.1223 g of NaHCO3 (Fisher lot # 897789) and 1.6488 g of NaCl (Fisher lot # 885407). Pipet 20.0 ml of SO4 stock, 2.0 ml of F stock, and 10.0 ml of NO3 stock solutions (resp. #'s # 019-97, 013-107, 019-63). dilute to the mark.

Spec. Dim $\phi = 0.635 \text{ cm}$ $l = 1.908 \text{ cm}$ $A = 4.123 \text{ cm}^2$

- ① Spec. not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start.
- ③ E cor at start -338 mV vs SCE
- ④ E pt 10 min before start -110 mV
- ⑤ Initial Temp. 95.0°C Final Temp. 95.0°C
- ⑥ Initial pH 8.15 Final pH 9.78
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$

Specimen covered w/a reddish brown film. Solution had slight yellow tinge. General corrosion seemed to have occurred.

Stratman Disc E6+C #5

Walter J. Machowski
6/27/91


Preparation of SO_4 Stock Solution

Purpose: Stock solution used in preparation of test solutions

Weigh out 1.4788 g of Na_2SO_4 (Fisher # 901213) dissolve in 500 ml. of 12M HCl water in a 1-liter volumetric flask & dilute to the mark.

Label as SN CMCRA 019-137

Walter J. MacKowski
7/1/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (mV)
VERTEX E (mV)
FINAL E (mV)
SCAN RATE (mV/s)
THRESHOLD I (μA/cm²)
CONDITION E (mV)
CONDITION T (s)
INIT DELAY (mV/s OR s)

CYCLIC POLN
CDA 3
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 s

SAMPLE PARAMETERS

AREA (cm²)
EQ WT (gm)
DENSITY (gm/cm³)
CATHODIC TAFEL (mV)
ANODIC TAFEL (mV)

4.117
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-343
4
6703.911
9.958708E-03
9.958708E-03
6703.911

LEGEND

CDA 715; RUN 3; TRIAL 13
DE-AERATE W/ARGON
CL=6; F=2; NO3=10; HCO3=85
SO4=1000; T=95 C

DONE ON PAR 273
2 JULY 1991

Cyclic Polarization of CDA 715
Model. Solution: CL=6, NO₃=10, F=2, HCO₃=85, SO₄=1000 95°C
CDA 3 Run 3; Trial 13
Purpose: Same as CDA 1.

The test specimen, preparation, procedures, cell, etc were as in CDA 1. Ref SCE #4 was used and checked as before, difference was less than 1.0 mV.

Test Solution Prep: To 500 ml of 12 MR water in a 1-liter volumetric add 0.1218 g NaHCO₃ and 1.4791 g Na₂SO₄ (Fisher lot #'s 897789 and 901213 resp.). Pipet 10.0 ml of Cl stock, 10.0 ml of NO₃ stock, and 2.0 ml of F stock sol'n as CNARA #'s 019-127, 019-63 and 013-107, resp.). dilute to the mark.

Spec. Dim $\phi = 0.635$ cm $l = 1.905$ cm $A = 4.117$ cm²

- ① Specimen not pre-passivated; all surfaces polished to 600 grits
- ② Specimen held at open circuit for one hour before start.
- ③ E corr at start -343 mV vs SCE
- ④ E at 10 min before start → not taken
- ⑤ Initial Temp 95.0°C Final Temp 95.0°C
- ⑥ Initial pH 8.26 Final pH 9.99
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Auto reverse @ 5000 μA/cm²

Specimen not pitted but covered with a dark scale which easily flaked off. Solution remained clear.


Sample was immersed in 1M H₂O₂ for 2 min (approx) to remove scale. No pitting.

Stored on disk ECT#5

Re examination of sample on tie ends indicated shallow "pits" Not known if it is just another form of extreme general corrosion.

Walter J. MacKowski
7/2/91

- N.S.



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 4
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.111
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-291
4
5789.346
-1899.781
0
5789.346

LEGEND

CDA 715; RUN 4; TRIAL 7
DE-AERATE W/ARGON
HCO3=85; NO3=10; F=2
CL=1000; SO4=1000; T=30 C

DONE ON PAR 273
3 JULY 1991

Cyclic Polarization of CDA 715

Model Solution: CL=1000; SO4=1000; HCO3=85; NO3=10; F=2 30°C 141

CDA 4 Run 4 Trial 7

Purpose: Same as CDA 1.

The test specimen, preparation, procedure, cell, etc were as CDA 1. Ref SCE #4 was used and checked as before, difference was less than 1.0 mV.

Test Solution Prep: To 500ml of 17 M₂ water in a

1-liter volumetric add 0.1208 g NaHCO₃, 1.4793 g Na₂SO₄, and 1.6468 g NaCl (same lot's as p. 135 and p. 139). Pipet 2.0 ml of F stock and 10.0 ml of NO₃ stock solution (same #1's as p. 139). Dilute to the mark.

Spec. Dim: $\phi = 0.635 \text{ cm}$ $l = 1.912 \text{ cm}$ $A = 4.111 \text{ cm}^2$

- ① Specimen not pre-passivated; all surface polished to 600 grit.
- ② Specimen held at open circuit for one hour before start.
- ③ E con at start - 291 mV vs SCE
- ④ E Pt 10 min before start + 89 mV
- ⑤ Initial Temp 31.0°C Final Temp 30.5°C
- ⑥ Initial pH 8.05 Final pH 9.24
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Auto reverse @ 5000 $\mu\text{A/cm}^2$

Specimen had general corrosion and a scale that easily fell off. Solution had some yellowish gelatinous ppt & was moderately clear.


Stored on disk E-45

Sample reddish in

color

-118 10/9

Walter J. MacKowski
7/3/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 5
0 VS E
100 VS E
-100 VS E
.17
1000
PASS
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.1
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-261
4
1129.268
-1.3048781
1.804878E-02
1129.268

LEGEND

CDA 715; RUN 9; TRIAL 3
DE-AERATE W/ARGON
CL=1000; F=2; NO3=10; HCO3=85
SO4=20; T=30 C

DONE ON PAR 173/276
2 JULY 1991

Cyclic Polarization of CDA 715 CDA-5

Model Solution CL=1000 SO₄=20 HCO₃=85 NO₃=10 F=2 30°C
w/arg

Run 9 Trial 3

Purpose: Same as CDA 1

The test specimen, preparation, procedure, cell, etc were as CDA 1. Ref SCE #1 was used diff < 1.0 mV, with respect to SCE #3.

Test Solution Prep. To 500 mL of 17 mM water in a 1-liter volumetric add .1222 g NaHCO₃, 1.6567 g NaCl (same lot # as p 135 & p 139) Pipet 2.0 mL of F stock and 10.0 mL of NO₃ stock, and 20.0 mL SO₄ stock solution (same #'s as p 139) Dilute to mark.

Spec. Dim: $\phi = .636 \text{ cm}$ $l = 1.901 \text{ cm}$ $A =$


- ① Specimen not pre-passivated, polished w/ 600 grit.
- ② Held at open potential for 1 hr.
- ③ E con at start -261 mV vs SCE
- ④ E Pt 10 min before start +112 mV
- ⑤ Initial Temp: 32°C Final Temp: 31°C
- ⑥ Initial pH 8.49 Final pH: 9.18
- ⑦ Scan Rate 0.17 mV/sec
- ⑧ Argon purge 99.999%
- ⑨ Done on Par 173/276
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$

Specimen had general corrosion and a scale that easily flaked. Solution had yellowish tint and ppt.

Stored on disk EG 6 4

Sample mostly "white"
in color i.e. Nickel-like
- AS w/7

Thomas C Page
7/3/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 6
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.113
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-288
4
7075.128
-1361537
0
7075.128

LEGEND

CDA 715; RUN 5; TRIAL 4
DE-AERATE W/ARGON
SD4=20; NO3=10; F=2
CL=1000; HCO3=8500; T=30 C

DONE ON PAR 273
8 JULY 1991

Cyclic Polarization of CDA-715

Model Solution: CL=1000, HCO₃=8500, NO₃=10, SD4=20, F=2 30°C

CDA 6 Run 5; Trial 4

Purpose: Same as CDA 1.

The test specimen, preparation, procedures, cells, etc were as described in CDA 1. Ref SCE #4 was used and checked as before, difference was less than 10 mV.

Test Solution Prep: To 500 ml of 17 MR water in a 1-liter volumetric add 1.6464 g NaCl and 12.1963 g NaHCO₃ (same lot #'s as p. 135 + 139). Pipet 10.0 ml of NO₃ stock, 20.0 ml of SD4 stock and 2.0 ml of F stock solutions (same #'s as p. 135). dilute to the mark.

Spec. dim. $\phi = 0.635$ cm $l = 1.903$ cm $A = 4.113$ cm²

- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start
- ③ E can at start -288 mV vs SCE
- ④ E at 10 min before start +326 mV
- ⑤ Initial Temp. 29.6°C Final Temp. 30°C
- ⑥ Initial pH 8.52 Final pH 9.17
- ⑦ Scan rate 0.17 mV/sec
- ⑧ done on PAR 273
- ⑨ Argon purge
- ⑩ Auto reverse @ 5000 μ A/cm²

Specimen was covered w/ many areas of bluish-green corrosion deposits, under which areas of shallow pitting or localized attack had occurred. Solution remained clear.


classic Type I pitting: bluish-green outer deposit, reddish inner deposit, shallow pitting underneath.

Stored on dish EC&D #5.

Sample white in color

- NS

Walter J. MacKowski
7/8/91



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	CDA 7
INITIAL E(MV)	0 VS E
VERTEX E(MV)	100 VS E
FINAL E(MV)	-100 VS E
SCAN RATE(MV/S)	.17
THRESHOLD I(UA/CM^2)	1000
CONDITION E(MV)	PASS
CONDITION T(S)	PASS
INIT DELAY(MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA(CMS^2)	4.12
EQ WT(GM)	PASS
DENSITY(GM/CM^3)	PASS
CATHODIC TAFEL(MV)	PASS
ANODIC TAFEL(MV)	PASS

DATA SCALE

ECORR	-239
MV/PT	4
DATA MAX	1150.485
DATA MIN	.3398058
ABS MIN	.3398058
ABS MAX	1150.485

LEGEND

CDA 715; RUN 10; TRIAL 8
DE-AERATE W/ARGON
CL=1000; NO3=10; HCO3=8500
SO4=1000; T=30 C; F=2

DONE ON PAR 173/276
8 JULY 1991

Cyclic Polarization of CDA 715
Model Solution CL=1000 HCO₃=8500 NO₃=10 SO₄=1000 F=2 T=30C 147
CDA 7 Run 10 TRIAL 8
Purpose: Same as CDA 1

The test specimen, preparation, procedures, cell, etc. were described in CDA 1. Ref SCE #1 used. Checked diff ¹ mV vs SCE #3.

Test Solution Prep: To 500 mL of 17 mM H₂O in a 1-Liter volumetric add 1.6463g NaCl, 12.2006g NaHCO₃, 1.4796g Na₂SO₄ (Same lot #'s as p 135 & p 139) Pipet 10.0 mL NO₃ stock, 2.0 mL F⁻ stock (same #'s as p 135) dilute to mark.

Spec Dim: $\phi = .635 \text{ cm}$ $l = 1.905 \text{ cm}$ $A = 4.117 \text{ cm}^2$

- ① Specimens not pre-passivated; all surfaces polished to 600 grit.
- ② Specimens held at open circuit for one hour before start.
- ③ E_{con} at start -240 mV
- ④ E_{pt} 10 min before start +56 mV
- ⑤ Initial Temp 32°C Final T -31°C
- ⑥ Initial pH 8.25 Final pH 9.13
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Done on PAR 173/276
- ⑨ Argon purge 99.999%
- ⑩ Auto reverse @ 1000 $\mu\text{A}/\text{cm}^2$


Specimen holder leaked. Greenish corrosion scale from brass holder formed at teflon-sample junction. The specimen showed no corrosion. Was some discoloration near junction.

Stored on EG:G #4

Shallow pits on one part of Fe sample which were covered by greenish deposit. Sample was white in color.

- NS 10/7

James C Page
7/8/91



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	CDA 8
INITIAL E (MV)	0 VS E
VERTEX E (MV)	100 VS E
FINAL E (MV)	-100 VS E
SCAN RATE (MV/S)	.17
THRESHOLD I (UA/CM^2)	5000
CONDITION E (MV)	PASS
CONDITION T (S)	PASS
INIT DELAY (MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA (CMS^2)	4.115
EQ WT (GM)	PASS
DENSITY (GM/CM^3)	PASS
CATHODIC TAFEL (MV)	PASS
ANODIC TAFEL (MV)	PASS

DATA SCALE

ECORR	-425
MV/PT	4
DATA MAX	6342.649
DATA MIN	4.860267E-02
ABS MIN	4.860267E-02
ABS MAX	6342.649

LEGEND

CDA 715; RUN 6; TRIAL 16
DE-AERATE W/ARGON
NO3=10; F=2; T=95 C
CL=1000; SD4=1000; HCD3=8500

DONE ON PAR 273
9 JULY 1991

CDA 8 Run 6 Trial 16

Purpose: Same as CDA 1

The test specimen, procedure, preparation, etc were as described in CDA 1. Ref SCE #4 was used and checked as before, difference was

Test Solution Prep: To 500 ml of 17M Ω water in a 1-liter volumetric add 1.6468 g NaCl, 1.4789 g Na_2SO_4 and NaHCO_3 12.202 g (same lot #'s as p. 135 + 136). Pipet 2.0 ml of F stock and 10.0 ml of SO_4 stock solutions (same #'s as p. 135). Dilute to the mark.

Spec. Dim. $\phi = 0.635 \text{ cm}$ $l = 1.904 \text{ cm}$ $A = 4.115 \text{ cm}^2$


- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start.
- ③ E scan at start -425 mV vs SCE
- ④ E Pt 10 min before start. -450 mV
- ⑤ Initial Temp 94.5°C Final Temp 95.0°C
- ⑥ Initial pH 8.38 Final pH 10.08
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$

Specimen slightly darkened, but no corrosion occurred. Solution remained water clear.

Stand on EAP # 5.

Specimen "white" in
obs. - N 10/7

Walter J. Machowski
7/9/91

CDA 7R
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 7R
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.115
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-259
4
9866.343
-4218.712
.090887
9866.343

LEGEND

CDA 715; RUN 10; TRIAL 8
DE-AERATE W/ARGON
CL=1000; NO3=10; HCO3=8500
SO4=1000; T=30 C; F=2

RERUN OF CDA 7

DONE ON PAR 173/276
9 JULY 1991

Cyclic Polarization of CDA 715
Model Solution CL=1000 HCO₃=8500 NO₃=10 SO₄=1000 F=2 T=30C 151
CDA 7R Run 10 Trial 8 Rerun

Purpose: Same as CDA 1

The test specimen, preparation, procedures, cell, etc. were described in CDA 1. Ref SCE #1 used. Checked and diff < 1mV vs SCE #3.

Test Solution Preparation: To 800ml of 17m/2 H₂O in a 1-L volumetric add 1.647g NaCl, 12.2063g NaHCO₃, 1.4782g Na₂SO₄ (Same lot #'s as p135 & p139) Pipet 10.0mL NO₃ stock, 2.0mL F⁻ stock (same #'s as p135) dilute to mark.

Specimen Dimensions: $\phi = .635\text{cm}$ $L = 1.904\text{cm}$ $A = 4.115\text{cm}^2$

- ① Specimen not pre-passivated; all surfaces polished to 600grit.
- ② Specimen held at open circuit for one hour before start.
- ③ E con at start -139
- ④ E pt 10 min before start
- ⑤ Initial Temp 31°C Final 30°C
- ⑥ Initial pH 8.52 Final pH 9.42
- ⑦ Scan Rate 0.17 mV/sec
- ⑧ Done on PAR 173/276
- ⑨ Argon purge 99.999%
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$


Large number of deep local corrosion pits.
Greenish precipitate corrosion product covering pits.
Red deposit inside pits.

Saved EG 6 #4

Sample white in color

-NS
10/7

Thomas C Page
7/9/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 10
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.107
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-229
4
1275.87
2.678354E-03
2.678354E-03
1275.87

LEGEND

CDA 715; RUN 7; TRIAL 1
DE-AERATE W/ARGON
CL=6; NO3=10; SO4=20
F=2; HCO3=85; T=30 C

DONE ON PAR 273
10 JULY 1991

Cyclic polarization of CDA-715
Model Solution: $\text{Cl} = 6, \text{NO}_3 = 10, \text{SO}_4 = 20, \text{F} = 2, \text{HCO}_3 = 85, 30^\circ\text{C}$
CDA 10 Run 7 Trial 1
Purpose: Same as CDA 1.

The test specimen, preparation, procedures, etc were as described in CDA 1. Ref SCE #4 was used and checked as before, difference was less than 1.0 mV.

Test Solution Prep: To 500 ml of 17 M Ω water in a 1-liter volumetric add 0.1209 g of NaHCO_3 (same lot # as p.135). Pipet 10.0 of Cl, 20.0 ml of SO_4 , 2.0 ml of F and 10.0 ml of NO_3 stock solutions (same #1s as p.133 + p.135). Dilute to the mark.

Spec. Dim: $\phi = 0.635 \text{ cm}$ $l = 1.900 \text{ cm}$ $A = 4.107 \text{ cm}^2$

- ① Specimen not pre-passivated; all surfaces polished to 600 grit
- ② Specimen held at open circuit for one hour before start
- ③ E cor at start -229 mV vs SCE
- ④ F Pt 10 min before start +85 mV
- ⑤ Initial Temp. 30.0°C Final Temp. 31.0°C
- ⑥ Initial pH @ 25 8.04 Final pH @ 25 9.46
- ⑦ scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Manual reverse @ 5100 μA / +1035 mV.


Specimen not pitted but had brown staining. Solution remained relatively clear.

Stored on disk ECPD #5

Brown film formed in local areas flaked off easily. No pitting.

- All 10/7

Walter J. Mochnowski
7/10/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 9
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
PASS
600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.111
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-350
4
5619.071
-498.1756
.2724398
5619.071

LEGEND

CDA 715; RUN 11; TRIAL 14
DE-AERATE W/ARGON
CL=6; NO₃=10; HCO₃=8500
SO₄=1000; F=2; T=95 C

DONE ON PAR 173/276
10 JULY 1991

Cycle 13 largen of CDA-715
Model Solution CL=6 NO₃=10 SO₄=1000 F=2 HCO₃=8500 95°C 155
CDA 9 Run 11 Trial 14
Purpose: Same as CDA 1

The test specimens, preparation, procedures, etc. were described in CDA 1. Ref SE #1 was used difference < 1.0 mV.

Test Solution Prep: To 500 mL of 17 M/L water in a 1-L volumetric flask. ADD 12.2082 g NaHCO₃ (same lot # as p 135). ADD 1.4762 g Na₂SO₄ (same lot # as p 139). Pipet 10.0 mL CL, 2.0 mL of F, and 10.0 mL NO₃ stock solutions (same #s as p. 139 & p 135). Dilute.

Spec Dim: $\phi = .635 \text{ cm}$ $l = 1.902 \text{ cm}$ $A = \text{cm}^2$

- ① Specimen not prepassivated; all surfaces polished to 600 grit
- ② Specimen held at open circuit potential for 1 hr before start
- ③ E_{con} at start $\approx -340 \text{ mV}$
- ④ E_{pt} 10 min before start -194 mV
- ⑤ Initial Temp 94°C final 93°C
- ⑥ Initial pH 8.43 final pH — not taken
- ⑦ Scan Rate 0.17 mV/sec
- ⑧ Purge w/ Argon 99.999%
- ⑨ Done on Par 173/276
- ⑩ Cnt reverse at 5000 $\mu\text{A}/\text{cm}^2$

Specimen furnished brown color no pitting. Test Solution remained clear.

Test done 7/10/91

There was one area in the center that had shallow corrosion and green deposit

- N.S.

Thomas C Page
7/16/91

Cyclic Polarization of CDA-715

Model Solution: $\text{Cl} = 6$, $\text{NO}_3 = 10$, $\text{SO}_4 = 20$, $\text{F} = 2$, $\text{HCO}_3 = 85$ 30°C

CDA 10 Run 7 Trial 1


Purpose: Same as CDA 1.

Test specimen, preparation, cell, etc were as in CDA 1. Ref SCE #4 was used and checked, difference $< 1.0 \text{ mV}$.

Test Solution Prep:

experiment already described on p. 153

WJ Macdonald
7/17/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 11
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.098
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-427
4
5685.7
-3.904343E-02
2.440215E-02
5685.7

LEGEND

CDA 715; RUN 8; TRIAL 10
DE-AERATE W/ARGON
CL=6; NO3=10; SO4=20; F=2
HCO3=8500; T=95 C

DONE ON PAR 273
11 JULY 1991

Cyclic Polarization of CDA-115

Model Solution: CL=6, SO₄=20, NO₃=10, F=2, HCO₃=8500 95°C

CDA 11 Run 8; Trial 10

Purpose: Same as CDA 7.

The test specimen, preparation, procedures, etc were as described in CDA 7. Ref SCE #4 was used and checked as before, difference was less than 1.0 mV.

Test Solution Prep: To 500 ml of 17 MΩ water in a 1-liter volumetric add 12.1994 g NaHCO₃ (same lot # as p. 135). Pipet 10.0 ml of Cl stock, 20.0 ml of SO₄ stock, 2.0 ml of F stock and 10.0 ml of NO₃ stock solutions (same #s as p. 135 + p. 139. dilute to the mark.

Spec. dim: $\phi = 0.636 \text{ cm}$ $l = 1.892 \text{ cm}$ $A = 4.098 \text{ cm}^2$


- ① Spec not pre-passivated; all surfaces polished to 600 grit.
- ② Spec held at open circuit for one hour before start.
- ③ E con at start, -427 mV vs SCE
- ④ E Pt 10 min before start -400 mV.
- ⑤ Initial Temp. 194.5°C Final Temp. 95.0°C
- ⑥ Initial pH 8.42 @ 25°C Final pH 10.16 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$

Specimen not pitted, but covered with dark brownish stains over 80% of surface. Solution remained clear.

Specimen appeared uncorroded.
Metallic sheen intact.

Stored on disk ECPD #5.

Walter J. MacKowski
7/17/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 12
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3500 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.104
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-232
4
5214.425
4.459064E-02
4.459064E-02
5214.425

LEGEND

CDA 715; TRIAL 5; RUN 12
DE-AERATE W/ARGON
CL=6; NO3=10; HCO3=85
SO4=1000; F=2; T=30 C

DONE ON PAR 173/276
11 JULY 1991

Cyclic Polarization of CDA 113
Model Solution CL=6, F=2, NO3=10, HCO3=85, SO4=1000 30°C 161

CDA 12 Run 12 TRIAL 5
Purpose: Same as CDA 1

The test specimen, preparation, procedures, etc. were described in CDA1. Ref SCE #1 was used Pot. diff < 1.0 mV with SCE #3.

Test Solution Prep: To 500 mL of 17 M/L H₂O in a 1-L volumetric flask. ADD .122 g NaHCO₃ and 1.4780 g Na₂SO₄ (same lot #'s as p135 & p139) pipet 10.0 mL Ce, 2.0 mL F, 10.0 mL NO₃ (stock same as p135 & p139) Dilute to the mark.

Spec. Param: $\phi = .634 \text{ cm} = 1.902 \text{ cm}$ $A = 4.104 \text{ cm}^2$

- ① Specimen not pre-passivated; all surfaces polished to 600 grit
- ② Specimen held at open-circuit potential for 1 hour prior to start
- ③ E_{con} at start -232 mV
- ④ Initial Temp 30°C Final Temp 32°C
- ⑤ Initial pH 8.54 Initial pH 9.24
- ⑥ Scan Rate 0.17 mV/sec
- ⑦ Purge with Argon 99.999%
- ⑧ Done on Par 173/276
- ⑨ Auto reverse at 5000 mV/cm²

Test Solution remained clear. The sample had flakey copper colored ppt. Sample is tarnished copper color.


Test Done 7/11/91

EG # 4

Uniform corrosion

18/7

Thomas C. Page
7/16/91

CDA 13
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 13
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.1
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-299
4
5097.561
8.536585E-02
8.536585E-02
5097.561

LEGEND

CDA 715; TRIAL 9; RUN 15
DE-AERATE W/ARGON
CL=6; NO3=10; HCO3=85
SO4=20; F=2; T=95 C

DONE ON PAR 173/276
12 JULY 1991

Cyclic Polarization of CDA 715
Model Solution: CL=6, SO4=20, NO3=10, HCO3=85, F=2 T=95°C 163

CDA 13 Trial 9 Run 13

Purpose: Same as CDA 1

The test specimen, preparation, procedures, etc. were described in CDA 1. Ref SCE #1 was used potential against SCE #3 < 1 mV

Test Solution Prep.: To 500 mL of 17 mM H₂O in a 1-L volumetric flask add .1224 g NaHCO₃ (same lot # as p135) pipet 10.0 mL CL, 10.0 mL NO₃, 2.0 mL F, 20 mL SO₄ (same stock as p135 & p139) Dilute to mark.

Spec. Diam: $\phi = .634 \text{ cm} = (.900 \text{ cm}) A = 4.10 \text{ cm}^2$


- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit potential for 1 hr before test start.
- ③ Econ at start -310 mV
- ④ E Pt at 10 min prior -305 mV
- ⑤ Initial pH 8.50 Final pH 9.78
- ⑥ Initial Temp 95°C Final Temp 93°C
- ⑦ Scan Rate 0.17 mV/sec
- ⑧ Purge with Argon 99.999%
- ⑨ Done on Par 173/276
- ⑩ Cuts reverse at 5000 mA/cm²

General Selective Corrosion of Nickel
leaving flakey copper film and copper colored tarnished underneath. Solution is turbid appears "dirty"

Done 7/12/91

E.G. #4

James C. Hays
7/16/91



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	CDA 14
INITIAL E (MV)	0 VS E
VERTEX E (MV)	100 VS E
FINAL E (MV)	-100 VS E
SCAN RATE (MV/S)	.17
THRESHOLD I (UA/CM^2)	5000
CONDITION E (MV)	PASS
CONDITION T (S)	PASS
INIT DELAY (MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA (CMS^2)	4.098
EQ WT (GM)	PASS
DENSITY (GM/CM^3)	PASS
CATHODIC TAFEL (MV)	PASS
ANODIC TAFEL (MV)	PASS

DATA SCALE

ECORR	-230
MV/PT	4
DATA MAX	5392.875
DATA MIN	-8.150317
ABS MIN	.3440703
ABS MAX	5392.875

LEGEND

CDA 715; TRIAL 2; RUN 14
DE-AERATE W/ARGON
CL=6; NO3=10; HCO3=8500
SO4=20; F=2; T=30 C

DONE ON PAR 173/276
15 JULY 1991

Cyclic voltammetry of CDA 115
Model Sol'n: HCO₃=8500; CL=6; SO₄=20; NO₃=10; F=2 T=30°C
CDA 14 Trial 2 Run 14
Purpose: Same as CDA 1

165

7/22/91
30°C TCP

The test specimen, preparation, procedures, etc. were described in CDA 1. SEE #1 was used.
Potential of SEE #1 vs SEE #3 < 1.0 mV

Test Sol'n Prep: 500 mL of 17 M H₂O in a 1-L volumetric flask add 12.200 g NaHCO₃ (same lot # as p 135) pipet 10.0 mL CL, 20.0 mL SO₄, 10.0 mL NO₃, 2.0 mL F (same stock as p 135 & p 139) Dilute to mark.

Spec. Dim: $\phi = .633 \text{ cm}$ $l = 1.9025 \text{ cm}$ $A = 4.098 \text{ cm}^2$

- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit potential for 1 hr prior to start.
- ③ Ecorr at start - 235 mV
- ④ Ept at 10 min prior 75 mV
- ⑤ Initial Temp 32°C Final Temp 30°C
- ⑥ Initial pH 8.59 Final pH 9.08
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Purge with Argon 99.999%
- ⑨ Done on PAR 173/276
- ⑩ Auto reverse at 5000 uA/cm²


No apparent corrosion. Sample was tarnished. Solution remained clear.

Done 7/15/91

EGG #4

Specimen exhibited metallic sheen. But there were longitudinal, river-like marks on parts of the sample. Related to residual stress pattern? - NS 10/7/91

Thomas C Page
7/16/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (mV)
VERTEX E (mV)
FINAL E (mV)
SCAN RATE (mV/s)
THRESHOLD I (UA/CM²)
CONDITION E (mV)
CONDITION T (s)
INIT DELAY (mV/s OR s)

CYCLIC POLN
CDA 15
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 s

SAMPLE PARAMETERS

AREA (CM²)
EQ WT (GM)
DENSITY (GM/CM³)
CATHODIC TAFEL (mV)
ANODIC TAFEL (mV)

4.088
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-365
4
6090.999
-5.009785
.5797457
6090.999

LEGEND

CDA 715; RUN 15; TRIAL 12
DE-AERATE W/ ARGON
CL=1000; NO₃=10; HCO₃=8500
SO₄=20; F=2; T=95 C

DONE ON PAR 173/276
16 JULY 1991

Cyclic Polarization of CDA 715 ¹⁰⁰⁰ 7/22/91
Model Sol'n = HCO₃-8500; CL=10; SO₄=20; NO₃=10; F=2 T=95°C
CDA 15 Trial 12; Run 15
Purpose: Same as CDA 1

This test specimen, preparation, procedures, etc. were described in CDA 1. SCE #1 was used and was checked vs SCE #3; diff < 1.0 mV

Test Sol'n Prep: To 500 mL of 17 mL H₂O in a 1-L Vol. flask add 12.7030 g NaHCO₃; 1.6453 g NaCl (same lot #10 as p 135 & p 139) pipet 10.0 mL HNO₃, 20 mL SO₄, 2.0 mL F (same stock as p 135 & p 139) Dilute to mark.

Spec. Dim: $\Phi = .632 \text{ cm}$ $l = 1.901 \text{ cm}$ $A = 4.088 \text{ cm}^2$

- ① Specimen not pre-passivated; all surfaces polished to 600 grit
- ② Specimen held at open circuit potential for 1 hr prior to start
- ③ Econ start -365 mV vs SCE
- ④ Ept 10 min prior to start -254 mV
- ⑤ Unifed J 93°C Final 94°C
- ⑥ Unifed pH 8.4/ Final 9.87
- ⑦ Scan Rate 0.17 mV/sec
- ⑧ Purge w/ Argon 99.999%
- ⑨ Done on Par 173/276
- ⑩ Auto Reverse at 5000 mA/cm²


Test Solution was clear. Sample was tarnished.

Test Stored on EG & G #4

Test Performed 7/16/91

10/7

Thomas Chage
7/22/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 16
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.1
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-293
4
7170.732
-3.507317
.1926829
7170.732

LEGEND

CDA 715; TRIAL 15; RUN 16
DE-AERATE W/ARGON
CL=1000; NO3=10; HCO3=85
SO4=1000; F=2; T=95 C

DONE ON PAR 173/276
17 JULY 1991

Cyclic Polarization of CDA 715

Model Sol'n: $\text{HCO}_3^- = 85$; $\text{Cl}^- = 1000$; $\text{SO}_4 = 1000$; $\text{NO}_3 = 10$; $F=2$; $T=95^\circ\text{C}$ 169

CDA 16

Purpose: Same as CDA 1

The test specimen, preparation, procedures, etc. were described in CDA #1. SCE #1 was used. Checked vs SCE #3 diff $< 1.0 \text{ mV}$

Test Sol'n Prep: To 500 mL of 17 M H_2O in a 1-L volumetric flask add .1227g NaHCO_3 , 1.4770g Na_2SO_4 , 1.6452g NaCl (Same lot #'s as p135 & 139) Pipet 10.0 mL NO_3 ; 2.0 mL F (Same stock as p135 & p139) Dilute to mark.

Spec. Dim: $\phi = .6335 \text{ cm} = 1.9015 \text{ cm}^2 = 4.10 \text{ cm}^2$

- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit potential for 1 hr before test.
- ③ $E_{\text{con start}} = -293 \text{ mV}$
- ④ $E_{\text{pt}} 10 \text{ min before start} = -125 \text{ mV}$
- ⑤ Initial T 94°C Final 95°C
- ⑥ Initial pH (9.20) Final 10.02
- ⑦ Scan Rate 0.17 mV/sec
- ⑧ Purge w/Argon 99.999%
- ⑨ Done on Par 173/276
- ⑩ Auto Reverse at 5000 uA/cm^2

Too high. Possible measurement/recording error.

Copper-colored test solution. Copper flake covering. Sample underneath pinkish color. Sample holder leaked. Test redo as CDA 16R (p181)


Test Stored on EG&G #4

Test Done on 7/17/91

See comments on p.181

10/7/91

James C. Page
7/22/91

CDA 17
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(μA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 17
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.108
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-212
4
5258.033
-87.87732
5.355404E-03
5258.033

LEGEND

CDA 102; RUN 1; TRIAL 6
DE-AERATE W/ARGON
CL=6; F=2; NO3=10
HCO3=8500; SO4=1000; T=30 C

DONE ON PAR 273
16 JULY 1991

Cyclic Polarization of CDA-102

Model Solution: $CL=6$, $SO_4=1000$, $HCO_3=8500$, $F=2$, $NO_3=10$ 30°C 171

CDA 17 Run 1 Trial 6

Purpose: Same as CDA 7.

The test specimen was CDA-102 from heat no. 6681. All other procedures, preparation, etc were as in CDA 7. Ref. SCE #4 was used and checked as before, difference was less than 1.0mV.

Test Solution: Prep: To 500ml of 17MR water in a 1-liter volumetric add 12.1894 g of $NaHCO_3$ and 1.4786 g of HCl (same lot #'s as p. 139). Pipet 10.0 ml of Cl stock, 10.0 ml of NO_3 stock, and 2.0 ml of F stock solutions (same lot #'s as p. 139). Dilute to the mark.

Spec. Dim: $\phi = 0.636$ cm $l = 1.897$ cm $A = 4.108$ cm²


- ① Spec not pre-passivated; all surfaces polished to 600 grit
- ② Spec held at open circuit for one hour before start.
- ③ E cor at start -212 mV vs SCE.
- ④ E Pt 10 min. before start -235 mV.
- ⑤ Initial Temp. 30.0°C Final Temp. 32.0°C
- ⑥ Initial pH 8.45 Final pH 9.25
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon Purge
- ⑨ Done on PAR 273
- ⑩ Auto reverse @ 5000 $\mu A/cm^2$

Specimen was darkened & had about 50-60% bluish-green corrosion product, under which shallow local attack had occurred. Solution was clear, but had a very, very, slight bluish tinge.

Stored on dish E6+G #5.

red corrosion product under green deposit. 7/17/91

Walter J. MacKinnon
7/17/91



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	CDA 18
INITIAL E(MV)	0 VS E
VERTEX E(MV)	100 VS E
FINAL E(MV)	100 VS E
SCAN RATE(MV/S)	.17
THRESHOLD I(μA/CM²)	5000
CONDITION E(MV)	PASS
CONDITION T(S)	PASS
INIT DELAY(MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA(CMS²)	4.118
EQ WT(GM)	PASS
DENSITY(GM/CM³)	PASS
CATHODIC TAFEL(MV)	PASS
ANODIC TAFEL(MV)	PASS

DATA SCALE

ECORR	-345
MV/PT	4
DATA MAX	5536.668
DATA MIN	-1.629432
ABS MIN	8.013599E-02
ABS MAX	5536.668

LEGEND

CDA 102; RUN 2; TRIAL 11
DE-AERATE W/ARGON
HCO₃=85; SO₄=20; NO₃=10; F=2
CL=1000; T=95

DONE ON PAR 273
17 JULY 1991

Cyclic Polarization of CDA-102

Model Solution: CL=1000, F=2, NO₃=10, SO₄=20, HCO₃=85 95°C

CDA 18 Run 2 Trial 11

Purpose: Same as CDA 1.

The test specimen, preparation, procedures, cell, etc were as described in CDA 17. Ref SCE #4 was used and checked as before, difference was less than 1.0 mV.

Test Solution prep: To 500 ml of 17MΩ water in a 1-liter volumetric add 0.1335 g NaHCO₃ and 1.6468 g NaCl (same lot #1s as p.135). Pipet 20.0 ml of SO₄ stock, 2.0 ml of F stock and 10.0 ml of NO₃ stock solution (same #1s as p.135). Dilute to the mark.

Spec. Dim: $\phi = 0.636 \text{ cm}$ $l = 1.902 \text{ cm}$ $A = 4.118 \text{ cm}^2$

- ① Spec not pre-passivated; all surfaces polished to 600 grit.
- ② Spec held at open circuit for one hour before start
- ③ E can at start, -345 mV vs SCE
- ④ E PT 10 min before start -165 mV
- ⑤ Initial Temp. 95.0°C Final Temp. 95.0°C
- ⑥ Initial pH 9.08 Final pH 9.96
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$


Specimen covered w/a reddish-brown film which readily flaked off. Solution was yellowish

Stored on dish EOC #5

Uniform corrosion.

10/7/91

Walter J. Mackenzie
7/17/91



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	CDA 19
INITIAL E (MV)	0 VS E
VERTEX E (MV)	100 VS E
FINAL E (MV)	-100 VS E
SCAN RATE (MV/S)	.17
THRESHOLD I (UA/CM ²)	5000
CONDITION E (MV)	PASS
CONDITION T (S)	PASS
INIT DELAY (MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA (CMS ²)	4.102
EQ WT (GM)	PASS
DENSITY (GM/CM ³)	PASS
CATHODIC TAFEL (MV)	PASS
ANODIC TAFEL (MV)	PASS

DATA SCALE

ECORR	-355
MV/PT	4
DATA MAX	5216.967
DATA MIN	.1121404
ABS MIN	.1121404
ABS MAX	5216.967

LEGEND

CDA 102; RUN 3; TRIAL 13
DE-AERATE W/ARGON
CL=6; F=2; NO3=10; HCO3=85
SO4=1000; T=95 C

DONE ON PAR 273
18 JULY 1991

Cyclic Polarization of CDA-102
Model Solution; CL=6, F=2, NO₃=10, HCO₃=85, SO₄=1000 95°C
CDA 19 Run 3 Trial 13
Purpose: Same as CDA 7.

W. J. MacKowski
The test ~~solute~~ specimen, preparation, procedures, etc were as in CDA 17. Ref SCE #4 was used and checked as before, but the difference was less than 1.0 mV.

Test Solution Prep: To 500 ml of 17MR of 1-liter volumetric add 0.1531 g of NaHCO₃ and 1.4789 g of Na₂SO₄ (same lot #'s as p. 139). Pipet 10.0 ml of Cl stock, 10.0 ml of NO₃ stock, and 2.0 ml of F stock solution (lot #'s same as p. 139) dilute to the mark.

Spec. Dim: $\phi = 0.634$ cm $l = 1.901$ cm $A = 4.102$ cm²


- ① Spec not pre-passivated; all surfaces polished to 600 grit
- ② Spec held at open circuit for one hour before start
- ③ E corr at start -355 mV vs SCE
- ④ E Pt 10 min before start -75 mV
- ⑤ Initial Temp. 95.3°C Final Temp. 95.0°C
- ⑥ Initial pH 8.28 Final pH 10.22
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Auto reverse @ 5000 μ A/cm²

Specimen covered w/a dark deposit. Solution had a brownish tinge. Specimen holder had leaked, test should be re-run.

Stored on disk EDA #5

W. J. MacKowski
10/1/91

W. J. MacKowski
7/18/91



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	CDA 20
INITIAL E(MV)	0 VS E
VERTEX E(MV)	100 VS E
FINAL E(MV)	-100 VS E
SCAN RATE(MV/S)	.17
THRESHOLD I(UA/CM^2)	1000
CONDITION E(MV)	PASS
CONDITION T(S)	PASS
INIT DELAY(MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA(CMS^2)	4.111
EQ WT(GM)	PASS
DENSITY(GM/CM^3)	PASS
CATHODIC TAFEL(MV)	PASS
ANODIC TAFEL(MV)	PASS

DATA SCALE

ECORR	-231
MV/PT	4
DATA MAX	1172.464
DATA MIN	-72.48844
ABS MIN	1.289224E-02
ABS MAX	1172.464

LEGEND

CDA 102; TRIAL 3; RUN 9
DE-AERATE W/ARGON
CL=1000; F=2; NO3=10; HCO3=85
SO4=20; T=30 C

DONE ON PAR 173/276
19 JULY 1991

Cyclic Polarization CDA 102

Model Sol'n: $\text{HCO}_3 = 85$; $\text{Cl} = 1000$, $\text{SO}_4 = 20$, $\text{NO}_3 = 10$, $F = 2$ $T = 30^\circ\text{C}$ 177

CDA 20

Purpose: Same as CDA 1

The test specimen, preparation, procedures, etc were as in CDA 17. Ref SCE #1 was used. Checked against SCE #4 diff 1.4 mV.

Test Sol'n Prep: To 500 mL of 17 M H_2O in a 1-L volumetric flask add .1220g NaHCO_3 , 1.6462g NaCl (same lot # as p135 & p139) pipet 20.0 mL SO_4 , 10.0 mL NO_3 , 2.0 mL F (same stock as p135 & p139) Dilute to mark.

Spec. Dim: $\phi = .635\text{cm}$ $l = 1.902\text{cm}$ $A = 4.111\text{cm}^2$

- ① Specimen not pre-passivated; all surfaces polished to 600grit
- ② Specimen held at open circuit potential for 1-hr before test.
- ③ E corr at start -231 mV
- ④ E pt at 10 min prior -15 mV
- ⑤ Initial Temp 30°C Final 32°C
- ⑥ Initial pH 8.18 Final 8.96
- ⑦ Scan Rate 0.17 mV/sec
- ⑧ Purge w/Argon 99.999%
- ⑨ Done on PAR 173/276
- ⑩ Auto reverse at 5000 $\mu\text{A}/\text{cm}^2$


Clear test solution. Tarnish film on sample. Does not wipe-off.

Test Stored on EGEG #4
Test Done 7/19/91

Tarnish was ~~got~~ bronze colored.

15/7/91

Thomas Page
7/22/91

CDA 21
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (mV)
VERTEX E (mV)
FINAL E (mV)
SCAN RATE (mV/s)
THRESHOLD I (μA/cm²)
CONDITION E (mV)
CONDITION T (s)
INIT DELAY (mV/s OR s)

CYCLIC POLN
CDA 21
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 s

SAMPLE PARAMETERS

AREA (cm²)
EQ WT (gm)
DENSITY (gm/cm³)
CATHODIC TAFEL (mV)
ANODIC TAFEL (mV)

4.1
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-245
4
5365.854
-1482.927
7.317073E-03
5365.854

LEGEND

CDA 102; RUN 4; TRIAL 7
DE-AERATE W/ARGON
HCO₃=85; NO₃=10; F=2
CL=1000; SD4=1000; T=30 C

DONE ON PAR 273
19 JULY 1991

Cyclic Polarization on CDA-102

Model Solution: CL=1000, SD4=1000, F=2, NO₃=10, HCO₃=85 30°C

CDA 21 Run 4 Trial 7

Purpose: Same as CDA 1

The test specimen, preparation, procedures, etc were as described in CDA 17. Ref SCE#4 was used and checked as before, difference was less than 1.5 mV.

Test Solution Prep: To 500 ml of 17 MΩ water in a 1-liter volumetric add 0.1208 g NaHCO₃, 1.479 g Na₂SO₄ and 1.646 g NaCl (same lot #1s as p.135 and p.139). Pipet 10.0 ml of NO₃ stock and 2.0 ml of F stock solution (same lot #1s as p.135). Dilute to the mark.

Spec Dim: $\phi = 0.634 \text{ cm}$ $l = 1.8998 \text{ cm}$ $A = 4.100 \text{ cm}^2$


- ① Spec not pre-passivated; all surface polished to 600 grit.
- ② Spec held at open circuit for one hour before start.
- ③ E scan at start -245 mV vs SCE
- ④ E pt 10 min before start +30 mV
- ⑤ Initial Temp. 29.5°C Final Temp. 31.0°C
- ⑥ Initial pH 8.01 Final pH 9.21
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 573
- ⑩ Auto reverse @ 5000 μA/cm²

Specimen had a dark, flaky scale & general corrosion underneath. Solution had a slight greenish tint.

Stored on disk EG #5

10/7/91

Walter J. MacLachlan
7/19/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(μA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 16R
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.093
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-330
4
5765.942
-5.003665
8.600049E-02
5765.942

LEGEND

CDA 715; TRIAL 15; RUN 16
DE-AERATE W/ARGON
CL=1000; NO3=10; HCO3=85
SO4=1000; F=2; T=95 C

DONE ON PAR 173/276
18 JULY 1991

Cyclic Polarization of CDA 715

Model Sol'n: $\text{HCO}_3^- = 85$; $\text{Cl}^- = 1000$, $\text{SO}_4 = 1000$, $\text{NO}_3 = 10$, $F = 2$ $T = 95^\circ\text{C}$ 181

CDA 16R

Purpose same as CDA 1

The test specimen preparation, procedures, etc., were described in CDA 1. SCE #1 was checked vs SCE #4 diff 1.4 mV.

Test Solution Prep: To 500ml of 17M/2 H_2O in a 1-L volumetric flask add .1229g NaHCO_3 ; 1.6470g NaCl ; 1.4785g Na_2SO_4 (Same lot # as p135 & p139) Pipet 10.0mL NO_3^- , 2.0 mL F^- (Same Stock as p135 & p139) Dilute to mark.

Spec. Dim: $\phi = .632\text{cm}$ $L = 1.9035\text{cm}$ $A =$

- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit potential for 1 hr before test.
- ③ E con start -331 mV
- ④ E pt 10 min prior to start -74 mV
- ⑤ Initial Temp 95°C Final 95°C
- ⑥ Initial pH 8.23 Final 9.68
- ⑦ Scan Rate 0.17 mV/sec
- ⑧ Purge w/Argon 99.999%
- ⑨ Done on PAR 173/276
- ⑩ Auto reverse at 5000 $\mu\text{A}/\text{cm}^2$

Orangeish - Copper-colored test solution.
Sample copper flake covering film. Sample underneath is pinkish color.


Test stored on EG&G #4
Test done on 7/18/91

Patches of red film.

Over the red film, areas of green deposit. No localized corrosion

10/7/91

Thomas C Page
7/22/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 22
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.117
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-214
4
6703.911
-1457372
0
6703.911

LEGEND

CDA 102; RUN 5; TRIAL 4
DE-AERATE W/ARGON
SO4=20; NO3=10; F=2
CL=1000; HCO3=8500; T=30 C

DONE ON PAR 273
22 JULY 1991

Cyclic Polarization of CDA-102

Model Solution: CL=1000, HCO₃=8500, SO₄=20, NO₃=10, F=2 30°C 183

CDA 22 Run 5 Trial 4

Purpose: Same as CDA 1

The test specimen, preparation, procedures, etc was as described in CDA 17. Ref SCE #4 was used and checked as before, difference was less than 1.5 mV.

Test Solution Prep: To 500 ml of 17 M.R. water in a 1-liter volumetric add 12.1893g of NaHCO₃ and 1.6457g of NaCl (same lot #/s as p.135). Pipet 20.0ml of SO₄ stock, 10.0ml of NO₃ stock and 2.0 ml of F stock solutions (same #/s as p.135). Dilute to the mark.

Spec. Dim: $\phi = 0.635$ cm $l = 1.905$ cm $A = 4.117$ cm²

- ① Spec held at open circuit for one hour before start
- ② Spec not pre-passivated, all surfaces polished to 600 grit.
- ③ E corr at start -214
- ④ E pt 10 min before start - not taken
- ⑤ Initial Temp. 29.0°C Final Temp. 32.0°C
- ⑥ Initial pH 8.39 Final pH 9.22
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Auto reverse c 5000 μ A/cm²


Specimen covered w/ small spots of blue-green corrosion product. Solution remained clear.

Stored on disk EDA #5

Red deposit under tie
green deposit. shallow, localized
attacks under rebar.

Walter J. MacKowski
7/22/91

10/7/91



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	CDA 23
INITIAL E (MV)	0 VS E
VERTEX E (MV)	100 VS E
FINAL E (MV)	-100 VS E
SCAN RATE (MV/S)	.17
THRESHOLD I (UA/CM^2)	1000
CONDITION E (MV)	PASS
CONDITION T (S)	PASS
INIT DELAY (MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA (CMS^2)	4.095
EQ WT (GM)	PASS
DENSITY (GM/CM^3)	PASS
CATHODIC TAFEL (MV)	PASS
ANODIC TAFEL (MV)	PASS

DATA SCALE

ECORR	-201
MV/PT	4
DATA MAX	1418.803
DATA MIN	-5.001221
ABS MIN	3.687424E-02
ABS MAX	1418.803

LEGEND

CDA 102; TRIAL 8; RUN 10
DE-AERATE W/ARGON
CL=1000; NO3=10; HCO3=8500
SO4=1000; T=30 C; F=2

DONE ON PAR 173/276
22 JULY 1991

The cyclic polarization of CDA 102

Model Sol'n: 8500 HCO₃, 1000 CL, 1000 SO₄, 10 NO₃, 2 F, 30°C

CDA 23

Purpose: Same as CDA 1

The test specimen, preparation, procedures, etc. were described in CDA 17. Ref SCE #1 was used and checked as before, difference < 1.0 mV

Test Solution Prep: To 500 mL of 17 M/L H₂O in a 1-L volumetric flask, add 1.6465g NaCl, 1.4795g H₂SO₄, 12.1994g NaHCO₃ (Same lot #'s as p135 & p139) pipet 10.0 mL NO₃, 2.0 mL F (Same stock as p135 & p139) Dilute to mark.

Specimen: $\phi = .6325\text{cm}$ $l = 1.9025\text{cm}$ $A = 4.095\text{cm}^2$

- ① Spec not pre-passivated, all surfaces polished to 600 grit
- ② Specimen held at open circuit potential for 1-hr before test
- ③ E_{corr} at start -202 mV
- ④ E_{pt} @ 10 min before -128 mV
- ⑤ Initial Temp 29°C Final 31°C
- ⑥ Initial pH 8.46 Final 9.09
- ⑦ Scan Rate 0.17 mV/sec
- ⑧ Argon Purge 99.999%
- ⑨ Done on Par 173/276
- ⑩ Auto reverse at 5000 uA/cm²


Specimen tarnished film with several local attacks. Green precipitate covers these spots with corroded spots beneath. Attack also at junction of sample & holder (green also). Clear solution.

Saved on EB&G #4

Attack not as extensive as in previous sample, CDA 22.

10/7/91

Harrold
7/23/91

CDA 24
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	CDA 24
INITIAL E(MV)	0 VS E
VERTEX E(MV)	100 VS E
FINAL E(MV)	-100 VS E
SCAN RATE(MV/S)	.17
THRESHOLD I(UA/CM^2)	5000
CONDITION E(MV)	PASS
CONDITION T(S)	PASS
INIT DELAY(MV/S OR S)	3400 S

SAMPLE PARAMETERS

AREA(CMS^2)	4.102
EQ WT(GM)	PASS
DENSITY(GM/CM^3)	PASS
CATHODIC TAFEL(MV)	PASS
ANODIC TAFEL(MV)	PASS

DATA SCALE

ECORR	-284
MV/PT	4
DATA MAX	5777.669
DATA MIN	-.1487079
ABS MIN	.1487079
ABS MAX	5777.669

LEGEND

CDA 102; TRIAL 14; RUN 11
DE-AERATE W/ARGON
CL=6; NO3=10; HCO3=8500
SO4=1000; F=2; T=95 C

DONE ON PAR 173/276
23 JULY 1991

Cyclic Polarization of CDA 102

Model Sol'n: $\text{HCO}_3 = 8500$, $\text{CL} = 6$, $\text{SO}_4 = 1000$, $\text{NO}_3 = 10$, $F = 2$, $T = 95^\circ\text{C}$ 187CDA24 Trial 8 RUN 12 Run 11 Trial 14 at 95°C
Purpose: Same as CDA 1

The test specimen, preparation, procedures, etc. were described in CDA 17. Ref SCE #1 was used and checked against SCE #3, diff < 1.0 mV

Test Solution Prep: To 500 mL of 17 M H_2O in a 1-L volumetric flask, add 12.2020 g NaHCO_3 , 1.4793 g Na_2SO_4 (same lot #'s as p135 & p139) pipet 10.0 mL NO_3 , 10.0 mL CL , 2.0 mL F (same stock as p135 & p139) dilute to mark.

Specimen Dimension: $\phi = .6327\text{cm}$, $l = 1.9055\text{cm}$, $A = 4.102\text{cm}^2$

- ① Specimen not pre-passivated, all surfaces polished to 600 grit.
- ② Specimen held at open circuit potential for 1-h before test
- ③ E_{corr} at start -303 mV
- ④ E_{pt} @ 10 min before -176 mV
- ⑤ Initial Temp 93°C Final 94°C
- ⑥ Initial pH 8.51 Final 9.78
- ⑦ Scan Rate 0.17 mV/sec
- ⑧ Argon purge 99.999%
- ⑨ Done on PAR 173/276
- ⑩ Auto Reverse at 5000 mA/cm²


Thick black film that does not rub off.
Clean test solution.

Save all E6 & G #4

The black film is thick & opaque.

10/2/91

Thomas C Page
7/31/91



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	CDA 25
INITIAL E (MV)	0 VS E
VERTEX E (MV)	100 VS E
FINAL E (MV)	-100 VS E
SCAN RATE (MV/S)	.17
THRESHOLD I (UA/CM²)	5000
CONDITION E (MV)	PASS
CONDITION T (S)	PASS
INIT DELAY (MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA (CMS²)	4.107
EQ WT (GM)	PASS
DENSITY (GM/CM³)	PASS
CATHODIC TAFEL (MV)	PASS
ANODIC TAFEL (MV)	PASS

DATA SCALE

ECORR	-143
MV/PT	4
DATA MAX	5137.57
DATA MIN	-498.6608
ABS MIN	8.522036E-03
ABS MAX	5137.57

LEGEND

CDA 102; TRIAL 5; RUN 12
DE-AERATE W/ARGON
CL=6; NO3=10; HCO3=85
SO4=1000; F=2; T=30 C

DONE ON PAR 173/276
25 JULY 1991

Cyclic Voltammogram of CDA 102
Model Sol'n: $\text{HCO}_3^- = 85$, $\text{CL} = 6$, $\text{SO}_4 = 1000$, $\text{NO}_3 = 10$, $F = 2$, $T = 30^\circ\text{C}$ 189
CDA 25 TRIAL 5 RUN 12
Purpose: Same as CDA 1

The test specimen, preparation, procedures, etc, were described in CDA 17. Ref SCE #3 was used, checked against SCE #1. Diff $< 1.0 \text{ mV}$

Test Solution Prep: To 500 mL of 17 M/L H_2O in a 1-L volumetric flask, add .1221g NaHCO_3 , 1.4787g Na_2SO_4 (same lot #'s as p 135 & p 139) pipet 10.0 mL CL, 10.0 mL NO_3 , 2.0 mL F (same stock as p 135 & p 139) Dilute to mark.

Specimen Dimension: $\phi = .6335 \text{ cm}$, $l = 1.905 \text{ cm}$, $A = 4.107 \text{ cm}^2$

- ① Specimen not pre-passivated, all surfaces polished to 600 grit
- ② Specimen held at open-circuit potential for 1-h before test
- ③ E_{corr} at start -143 mV vs SCE
- ④ Ept 10 min before start - not taken
- ⑤ Initial Temp 30°C Final 31°C
- ⑥ Initial pH 8.64 Final 9.24
- ⑦ Scan Rate 0.17 mV/sec
- ⑧ Argon Purge 99.999%
- ⑨ Done on PAR 173/276
- ⑩ Auto reverse at 5000 mA/cm^2

Specimen had brown flakey film.
Comes off very easily. Clear test solution.

Saved on EG & G #4

Thomas Chage
7/31/91


Preparation of F Stock Solution

Purpose: Stock solution used in preparation of test solutions

Weigh out 2.2100g of NaF (Fisher lot # B96405) Dissolve in 500 mL of 17 mM water in a 1-liter volumetric flask and dilute to mark.

Label as SN CNWRA 019-191.

James C. Page
7/31/91

CDA 26
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (MV)
VERTEX E (MV)
FINAL E (MV)
SCAN RATE (MV/S)
THRESHOLD I (UA/CM²)
CONDITION E (MV)
CONDITION T (S)
INIT DELAY (MV/S OR S)

CYCLIC POLN
CDA 26
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA (CMS²)
EQ WT (GM)
DENSITY (GM/CM³)
CATHODIC TAFEL (MV)
ANODIC TAFEL (MV)

4.088
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-279
4
5283.758
-50.09785
.611546
5283.758

LEGEND

CDA 715
DE-AERATE W/ARGON
CL=1000; NO3=10; HCO3=8500
SO4=1000; F=2; T=60 C

DONE ON PAR 173/276
1 AUG 1991

The Cyclic Polarization of CDA 715
Model Sol'n: 8500 ppm HCO₃; CL=1000, SO₄=1000, F=2, NO₃=10 T=60°C

CDA 26

Purpose: Same as CDA 1

The test specimen preparation, procedures, etc., were described in CDA 1700. Ref SCE #1 was used. Checked against SCE #3 diff 2.10 mV.

Test Solution Prep: To 1-L of 17 M/L H₂O in a 2-L volumetric flask, add 24.400 g NaHCO₃, 3.2924 g NaCl, 2.9591 g Na₂SO₄ (Same lot # as p135 & p139) pipet 10.0 mL NO₃ and 2.0 mL F (Same stock # as p135 & p139) Dilute to mark. 1-L of this solution for CDA 26 & CDA 270a.

Specimen Dimension: $\phi = .6323 \text{ cm}$ $l = 1.900 \text{ cm}$ $A = 4.088 \text{ cm}^2$

- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open-circuit potential for 1-h before test
- ③ E con at start -280 mV vs SCE
- ④ E pt 10 min before -158 mV
- ⑤ Initial Temp 60°C Final 59°C
- ⑥ Initial pH 8.49 Final pH 9.48
- ⑦ Scan Rate 0.17 mV/sec
- ⑧ Argon Purity 99.999%
- ⑨ Done on Par 173/276
- ⑩ Auto Reverse at 5000 uA/cm²


Few local corrosion pits covered by green precipitate on sample.
Test solution is clear

Save on EG & G #4

Sample white in color in the uncorroded areas.

10/7/91

James C. Fog
Aug 2 1991

CDA 27
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 27
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.0966
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-266
4
7591.661
-1.269345
.2196944
7591.661

LEGEND

CDA 715
DE-AERATE W/ARGON
NO3=10; F=2; T=40 C
CL=1000; SD4=1000; HCO3=8500

DONE ON PAR 273
1 AUG 1991

Cyclical Polarization of CDA 715
Model Sol'n: $\text{HCO}_3 = 8500$, $\text{Cl} = 1000$, $\text{SO}_4 = 1000$, $\text{NO}_3 = 10$, $F=2$ $T=40^\circ\text{C}$ 195
CDA 27

Purpose Same as CDA 1

The test specimen, preparation, procedures, etc., were described in CDA 17th. Ref SCE #1 was used. Checked against SCE #3 difference $< 1.0 \text{ mV}$

Test Solution Prep: See CDA 26 p.193

Specimen Dimension: $\phi = .6335 \text{ cm}$ $L = 1.900 \text{ cm}$ $A = 4.0966 \text{ cm}^2$

- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open-circuit potential for 1-h before test.
- ③ Econ at Start -268 mV vs SCE
- ④ Ept 10 min before +402 mV
- ⑤ Initial Temp 40°C Final 40°C
- ⑥ Initial pH 8.49 Final 9.33
- ⑦ Scan Rate 0.17 mV/sec
- ⑧ Argon Purity 99.999%
- ⑨ Done on Par 273
- ⑩ Auto reverse at 5000 $\mu\text{A}/\text{cm}^2$


Specimen has quite a lot of pits covered by green precipitate (local) esp near end. Test solution has slight green tint.

Save on E6 & E #5

Sample white in color in the uncorroded areas.

10/7/91

Thomas Page
8/2/91

CDA 28
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (mV)
VERTEX E (mV)
FINAL E (mV)
SCAN RATE (mV/s)
THRESHOLD I (UA/CM²)
CONDITION E (mV)
CONDITION T (s)
INIT DELAY (mV/s OR s)

CYCLIC POLN
CDA 28
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 s

SAMPLE PARAMETERS

AREA (CM²)
EQ WT (GM)
DENSITY (GM/CM³)
CATHODIC TAFEL (mV)
ANODIC TAFEL (mV)

4.0807
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-274
4
5072.659
-50.18747
.2867155
5072.659

LEGEND

CDA 102; TRIAL 9; RUN 15
DE-AERATE W/ARGON
CL=6; NO3=10; HCO3=85
SO4=20; F=2; T=95 C

DONE ON PAR 173/276
2 AUG 1991

Cyclical Polarization of CDA 102

Model Sol'n: HCO₃ = 85; CL = 6; SO₄ = 20; NO₃ = 10; F = 2. T = 95°C

CDA 28 J 9 R 13

Purpose: Same as COA 1

The test specimen preparation, procedures, etc, were described in COA 17. Ref SCE #1 was used checked against SCE #3 diff < 1.0 mV

Test Solution Prep: To 500 mL of 17 mM H₂O add a 1-L volumetric flask add 0.1224g NaHCO₃ (same lot # as p 135) pipet 10.0 mL CL, 20.0 mL SO₄, 10.0 mL NO₃, 2.0 mL F (same stock as p 135 & p 139) Dilute to mark.

Specimen Dimension: $\phi = .6315 \text{ cm}$ $l = 1.899 \text{ cm}$ $A = 4.0807 \text{ cm}^2$ TCA

- ① Specimen not pre-passivated, all surfaces polished to 600 grit
- ② Specimen held at open-circuit potential for 1-h before start
- ③ E_{corr} at start -274 mV vs SCE
- ④ E_{pt} at 10 min before - not taken
- ⑤ Initial Temp 94°C Final 95.0°C
- ⑥ Initial pH not taken Final 10.27
- ⑦ Scan Rate 0.17 mV/sec
- ⑧ Argon purge 99.999%
- ⑨ Done on Par 173/276
- ⑩ Auto reverse at 5000 uA/cm²

Specimen holder leaked badly. Specimen had a dark powdery film. Solution was brownish. Test should be re-run.

Stored on disk E-C #4.

Dark green film/deposit on sample. No visible local attack.

10/7/91

Thomas C Page
8/2/91


Preparation of NO_3 Stock Solution 1000 ppm

Purpose: Stock solution used in preparation of test solutions.

Weigh out 1.3793 g of NaNO_3 (Fisher lot # 897183), dissolve in 500 ml of 17 M Ω water in a 1-liter volumetric flask. Dilute to the mark.

Label as SN CWA 019-199.

Walter J. MacLowski
8/5/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 28R
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.31
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-286
4
3508.121
-475.174
.2853828
3508.121

LEGEND

CDA 102; TRIAL 9; RUN 15
DE-AERATE W/ARGON
CL=6; NO3=10; HCO3=85
SO4=20; F=2; T=95 C
TEST IS RE-RUN DUE TO LEAK

DONE ON PAR 173/276
6 AUG 1991

Cyclic Polarization of CDA-102
Model Solution: Same as CDA 28

CDA 28R

Purpose: Same as CDA I. This run due to leak in CDA 28.

The test specimen, preparation, procedures, etc. were as described in CDA 17. Ref SCE #1 was used and checked as before, difference was less than 1.0 mV.

Test Solution Prep: To 500 ml of 17M52 water in a 1-liter volumetric add 0.1230 g of NaHCO₃ (same lot as p.135).

disregard original
Pipet 10.0 ml of Cl₂, 20.0 ml of SO₄, 10.0 ml of NO₃, and 2.0 ml of F stock solutions (lot #1's 019-127, 019-199, 019-794, and

rewrite
Pipet 10.0 ml of Cl₂, 20.0 ml of SO₄, 10.0 ml of NO₃, and 2.0 ml of F stock solutions # 019-127, 019-137, 019-199, and 019-191 respectively, dilute to the mark.

Spec. Dim: $\phi = 0.640 \text{ cm}$ $l = 1.907 \text{ cm}$ $A = 4.156 \text{ cm}^2$


- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour prior to start
- ③ E con at start -288 mV vs SCE
- ④ E Pt 10 min before start -127 mV
- ⑤ Initial Temp. 94.3°C Final Temp. 95.8°C
- ⑥ Initial pH 8.02 @ 25°C Final pH 10.28 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 173/276
- ⑩ Experiment accidentally aborted - data saved: no reverse scan was obtained; will re-run the test

Specimen covered with a dark blackish-green powdery film. Solution had a slight greenish tint.

Stored on disk EPR #4

very shallow local attack
under green deposit. 10/7/91

Walter J. Machowski
8/6/91

CDA 29
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	CDA 29
INITIAL E (MV)	0 VS E
VERTEX E (MV)	100 VS E
FINAL E (MV)	-100 VS E
SCAN RATE (MV/S)	.17
THRESHOLD I (UA/CM^2)	5000
CONDITION E (MV)	PASS
CONDITION T (S)	PASS
INIT DELAY (MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA (CMS^2)	4.156
EQ WT (GM)	PASS
DENSITY (GM/CM^3)	PASS
CATHODIC TAFEL (MV)	PASS
ANODIC TAFEL (MV)	PASS

DATA SCALE

ECORR	-331
MV/PT	4
DATA MAX	5606.352
DATA MIN	7.218479E-02
ABS MIN	7.218479E-02
ABS MAX	5606.352

LEGEND

CDA 715
DE-AERATE W/ARGON
NO3=10; F=2; T=80 C
CL=1000; SD4=1000; HCD3=8500

DONE ON PAR 273
6 AUG 1991

Cyclic Polarization of CDA-715

Model Solution: 8500 = HCO₃; CL=1000, SD4=1000, F=2, NO₃=10 80°C 203

CDA 29

Purpose: Same as CDA 1.

The test specimen, procedures, preparation, etc were as described in CDA 1. Ref SCE #4 was used and checked as before, difference was less than 1.0 mV

Test Solution Prep: To 500 ml of 17MΩ water in a 1-L volumetric add 12.2101 g of NaHCO₃, 1.6467 g of NaCl, and 1.4781 g Na₂SO₄ (Fisher lot #s 897789, 885407, + 901213 resp.) Pipet 10.0 ml of NO₃ and 2.0 ml of F stock solutions (#019-199 and 019-191 resp.) dilute to the mark.

Spec. Dim: $\Phi = 0.636$ cm $l = 1.998$ cm $A = 4.310$ cm²


- ① Specimen not pre-passivated; all surface polished to 600 grit
- ② Specimen held at open circuit for one hour prior to start
- ③ E scan at start -332 mV vs SCE
- ④ E Pt 10 min before start +90 mV
- ⑤ Initial Temp. 81.6°C Final Temp. 80.0°C
- ⑥ Initial pH 8.34 @ 25°C Final pH 9.51 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Auto-reverse @ 5000 μ A/cm²

Specimen had small amount of greenish corrosion product at mounted end + at edge of lower end. Specimen somewhat darkened w/ some areas of shallow localized corrosion appearing. Solution remained clear.

Stored on disk 20 + 0 #5.

10/7/91

Walter J. MacKowski
8/6/91

CDA 29
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	CDA 29
INITIAL E (mV)	0 VS E
VERTEX E (mV)	100 VS E
FINAL E (mV)	-100 VS E
SCAN RATE (mV/s)	.17
THRESHOLD I (μA/cm²)	5000
CONDITION E (mV)	PASS
CONDITION T (s)	PASS
INIT DELAY (mV/s OR s)	3600 s

SAMPLE PARAMETERS

AREA (cm²)	4.156
EQ WT (GM)	PASS
DENSITY (GM/cm³)	PASS
CATHODIC TAFEL (mV)	PASS
ANODIC TAFEL (mV)	PASS

DATA SCALE

ECORR	-331
MV/PT	4
DATA MAX	5606.352
DATA MIN	7.218479E-02
ABS MIN	7.218479E-02
ABS MAX	5606.352

LEGEND

CDA 715
DE-AERATE W/ARGON
N03=10; F=2; T=80 C
CL=1000; S04=1000; HCO3=8500

DONE ON PAR 273
6 AUG 1991

Cyclic Polarization of CDA-715

Model Solution: 8500 = HCO₃; CL=1000, S04=1000, F=2, N03=10 80°C 203

CDA 29

Purpose: Same as CDA 1.

The test specimen, procedures, preparation, etc were as described in CDA 1. Ref SCE #4 was used and checked as before, difference was less than 1.0 mV

Test Solution Prep: To 500 ml of 17MΩ water in a 1-L volumetric add 12.2101 g of NaHCO₃, 1.6467 g of NaCl, and 1.4781 g Na₂SO₄ (Fisher lot #'s 897789, 885407, + 901213 resp.) Pipet 10.0 ml of NO₃ and 2.0 ml of F stock solutions (#019-199 and 019-191 resp.) dilute to the mark.

Spec. Dim: $\Phi = 0.636$ cm $l = 1.998$ cm $A = 4.310$ cm²


- ① Specimen not pre-passivated; all surface polished to 600 grit
- ② Specimen held at open circuit for one hour prior to start
- ③ E scan at start -332 mV vs SCE
- ④ E Pt 10 min before start +90 mV
- ⑤ Initial Temp. 81.0°C Final Temp. 80.0°C
- ⑥ Initial pH 8.34 @ 25°C Final pH 9.51 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Auto-reverse @ 5000 μA/cm²

Specimen had small amount of greenish corrosion product at mounted end + at edge of lower end. Specimen somewhat darkened w/ some areas of shallow localized corrosion appearing. Solution remained clear.

Stored on disk 203 + 205.

10/7/91

Walter J. Mackowski
8/6/91

CDAR28R
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDAR28R
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.162
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-288
4
4404.132
.2090341
.2090341
4404.132

LEGEND

CDA 102; TRIAL 9; RUN 15
DE-AERATE W/ARGON
CL=6; NO3=10; HCO3=85
SO4=20; F=2; T=95 C
THIS IS 2ND RE-RUN OF THIS TEST

DONE ON PAR 173/276
7 AUG 1991

Cyclic Polarization of CDA-102
Model Solution: Same as CDA 28R

CDAR28R

Purpose: Same as CDA 1. This re-run due to accidental shut off on CDA 28R.

The test specimen, etc were as in CDA 28R.
Ref SCE #4 was used and checked, difference less than 1.0mV.
Test Solution Prep: Same as CDA 28R using same lot #'s for chemicals and stock solutions. Actual weight of NaHCO₃ added was 0.1223g.

Spec. Dim: $\phi = 0.642 \text{ cm}$ $l = 1.903 \text{ cm}$ $A = 4.162 \text{ cm}^2$


- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before starting.
- ③ E corr at start -290 mV vs SCE
- ④ E Pt 10 min. before start -47mV
- ⑤ Initial Temp. 96.8°C Final Temp. 94.8°C
- ⑥ Initial pH 8.20 @ 25°C Final pH 10.37 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 173/276
- ⑩ Manual rev @ 17880uA / +1157mV

Specimen covered w/a dark flaky scale which easily came off. Some areas appeared red-brown when the outside scale was wiped off. Solution had a dirty brown color.

Stored on disk E6+C #4

10/7/91

Walter J. MacKowski
8/7/91



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	CDA 30
INITIAL E(MV)	0 VS E
VERTEX E(MV)	100 VS E
FINAL E(MV)	-100 VS E
SCAN RATE(MV/S)	.17
THRESHOLD I(UA/CM^2)	5000
CONDITION E(MV)	PASS
CONDITION T(S)	PASS
INIT DELAY(MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA(CMS^2)	4.119
EQ WT(GM)	PASS
DENSITY(GM/CM^3)	PASS
CATHODIC TAFEL(MV)	PASS
ANODIC TAFEL(MV)	PASS

DATA SCALE

ECORR	-221
MV/PT	4
DATA MAX	5122.603
DATA MIN	1.165331E-02
ABS MIN	1.165331E-02
ABS MAX	5122.603

LEGEND

CDA 102; RUN 14; TRIAL 2
DE-AERATE W/ARGON
CL=6; NO3=10; HCO3=8500
SO4=20; F=2; T=30 C

DONE ON PAR 173/276
8 AUG 1991

Cyclic Polarization of CDA 102

Model Solution: $\text{HCO}_3^- = 8500$, $\text{Cl}^- = 6$, $\text{SO}_4^{2-} = 20$, $\text{NO}_3^- = 10$, $F = 2$ 30°C

CDA 30 Run 14; Trial 2

Purpose: Same as CDA 1.

The test specimen, procedures, preparation, etc were as described in CDA 17. Ref SCE #4 was used and checked vs another, difference was less than 1.0 mV.

Test Solution Prep: To 500 ml of 17MR water in a 1-L volumetric add 12.1898 g of NaHCO_3 (Fisher lot #897789). Pipet 0.0 ml of Cl^- , 20.0 ml of SO_4^{2-} , 10.0 ml of NO_3^- , and 2.0 ml of F stock solutions (same #1s as p. 201). Dilute to the mark.

Spec. Dim: $\phi = 0.635 \text{ cm}$ $l = 1.906 \text{ cm}$ $A = 4.119 \text{ cm}^2$


- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start.
- ③ E scan at start
- ④ E Pt 10 min before start +10 mV
- ⑤ Initial Temp. 29.2°C Final Temp. 30.0°C
- ⑥ Initial pH 8.41 @ 25°C Final pH 9.28 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 173/276
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$

Specimen was very dark all over with a few areas of greenish-bluish localized corrosion product. Some localized attack may have occurred in some spots under this greenish corrosion product. Solution remained clear.

Stored on dish EC#4

10/7/91

Dale J. MacKowski
8/8/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 31
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.194
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-406
4
5937.053
.1168336
.1168336
5937.053

LEGEND

CDA 102; RUN 15; TRIAL 12
DE-AERATE W/ARGON
CL=1000; NO3=10; HCO3=8500
SO4=20; F=2; T=95 C

DONE ON PAR 173/276
9 AUG 1991

Cyclic Polarization of CDA-102

Model Solution: $\text{HCO}_3^- = 8500$, $\text{CL} = 1000$, $\text{SO}_4 = 20$, $\text{NO}_3 = 10$, $F = 2$ 95°C

CDA 31 Run 15 Trial 12

Purpose: Same as CDA 1.

Test specimen, preparation, procedures, etc were as in CDA 17. Ref SCE #4 was used, and checked as before, difference was less than 1.0 mV.

Test Solution Prep: To 500 ml of 17 MΩ water in a 1-L volumetric add 12.1983 g of NaHCO_3 and 1.6468 g of NaCl (same lots as p.203) Pipet 20.0 ml of SO_4 , 10.0 ml of NO_3 and 2.0 ml of F stock solutions (Lot #s 019-137, 019-199 + 019-191 resp.). Dilute to the mark.

Spec. dim: $\phi = 0.638 \text{ cm}$ $l = 1.908 \text{ cm}$ $A = 4.144 \text{ cm}^2$


- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start.
- ③ E scan at start
- ④ E Pt 10 min before start -208 mV
- ⑤ Initial Temp. 95.5°C Final Temp. 95.5°C
- ⑥ Initial pH 8.36 @ 25°C Final pH 9.86 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 173/276
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$

Specimen covered w/a black, moderately adherent film.
Solution remained clear.

Stored on dish E.C. & C. #4

10/7/91

Walter J. MacKowski
8/9/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 32
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.12
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-348
4
5582.524
-4.970874
.1337379
5582.524

LEGEND

CDA 102; RUN 16; TRIAL 15
DE-AERATE W/ARGON
CL=1000; NO3=10; HCO3=85
SO4=1000; F=2; T=95 C

DONE ON PAR 173/276
14 AUG 1991

Cyclic Voltammogram of CDA-102

Model Solution: CL=1000, SO4=1000, NO3=10, F=2, HCO3=85 95°C

CDA 32 Run 16 Trial 15

Purpose: Same as CDA 2.

The test specimen, preparation, procedures, etc were as described in CDA 17. Ref SCE #4 was used and checked as before, difference was less than 1.0 mV.

Test Solution Prep: To 500 ml of 17M R water in a 1-L rd-untitle add 0.1219 g NaHCO3, 1.6458 g of NaCl and 1.4790 g of Na2SO4 (Fisher lot #1's 897289, 885407, and 901213 resp). Pipet 10.0 ml of NO3 and 2.0 ml of F stock solutions (CWA #1's 019-179 and 019-191 resp.) Dilute to the mark.

Spec. dim: $\phi = 0.636 \text{ cm}$ $l = 1.903 \text{ cm}$ $A = 4.120 \text{ cm}^2$

- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start.
- ③ E cor at start -349 mV vs SCE
- ④ E pt 10 min before start -224 mV
- ⑤ Initial Temp. 95.5°C Final Temp. 95.0°C
- ⑥ Injld pH 8.13 @ 25°C Final pH 10.35 @ 25°C
- ⑦ scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 173/276
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$

Specimen covered w/a reddish-brown flaky scale which easily came off. General corrosion occurred + grains of the metal were easily visible. Solution was a bright yellow.

Stored on disk 6700 #4

10/7/91

Walter J. MacKowski
8/14/91

10/10/91

Av. init. pH: 8.35

std. dev.: 0.16

Av. Final pH(30c): 9.24

std. dev.: 0.13

Av. Final pH(95c): 9.95

std. dev.: 0.15

A - Active


Ap - Active-Passive

Alloy	Run No.	Trial No	HC03	Cl	S04	H03	T	Ecorr	Ebreak	Exp	Comments
CDA 715	7	1	85	6	20	10	30	-229	56	56	Uniform corrosion, brown film A/P?
	14	2	8500	6	20	10	30	-230	831	799	No pitting, Ni-color
	9	3	85	1000	20	10	30	-261	NA	NA	Uniform corrosion, Ni color A
	5	4	8500	1000	20	10	30	-280	845	13	Pits, green deposit, Ni-color
	12	5	85	6	1000	10	30	-232	NA	NA	Uniform corrosion, flaky red film A
	1	6	8500	6	1000	10	30	-249	820	56	Deep Pits, green deposits
	4	7	85	1000	1000	10	30	-283	NA	NA	Uniform corrosion, red film A
	10	8	8500	1000	1000	10	30	-259	506	26	Deep pits, green deposit, Ni-color
	10	8	8500	1000	1000	10	30	-237	678	54	Shallow pits, green deposit, Ni-color
	13	9	85	6	20	10	95	-299	198	-18	Uniform corrosion, Red film A/P
	8	10	8500	6	20	10	95	-427	602	530	No pitting, dark brown stain
	2	11	85	1000	20	10	95	-338	-29	-242	Uniform corrosion, red film A/P
	15	12	8500	1000	20	10	95	-365	628	552	No pitting
	3	13	85	6	1000	10	95	-343	74	-162	A few shallow pits A/P
	11	14	8500	6	1000	10	95	-350	611	551	Shallow pits at crevice
	16	15	85	1000	1000	10	95	-293	-24	-241	Uniform corrosion, Red film A/P
	6	16	8500	1000	1000	10	95	-425	612	525	No pits, Ni-color

This page blank

N. Guid has

Walter J MacQuinn
10/22/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 33
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.113
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-404
4
5737.904
.2917579
.2917579
5737.904

LEGEND

CDA 102; RUN 6; TRIAL 16
DE-AERATE W/ARGON
NO3=10; F=2; T=95 C
CL=1000; SO4=1000; HCO3=8500

DONE ON PAR 273
22 OCT 1991

Cyclic Polarization of CDA-102
Model Solution: CL=1000; SO₄=1000; HCO₃=8500; NO₃=10; F=2 95°C
CDA 33 Run 6; Trial 16
Purpose: Same as CDA 2 (p.133)

The test specimen, preparation, procedures, etc were as described in CDA 17 (p.171). Ref SCE #1 was used and checked as before, difference was less than 1.0 mV.

Test Solution Prep: To 500 ml of 17 M/2 water in a 1-L volumetric add 12.1739g NaHCO₃, 1.6460g NaCl and 1.4789g Na₂SO₄ (Fisher lot #'s 897789, 885407, & 901213 resp). Pipet 10.0 ml of NO₃ stock and 2.0 ml of F stock solution (#019-199 and #019-191 resp.). Dilute to the mark.

Spec. Dim: $\phi = 0.633$ cm $l = 1.910$ cm $A = 4.113$ cm²


- ① Specimen not pre-passivated; all surfaces polished to 600 grit.
- ② Specimen held at open circuit for one hour before start
- ③ E cor at start -405 mV vs SCE
- ④ E Pt 10 min before start -194 mV
- ⑤ Initial Temp. 95.5°C Final Temp. 94.0°C
- ⑥ Initial pH 8.29 @ 25°C Final pH 9.65 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Auto reverse @ 5000 μ A/cm²

Specimen covered w/p black, dull uniform film which was moderately adherent. Test solution remained water clear.

Stored on disk ECR #5.

12/16/91

Walter J. MacKowski
10/22/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (MV)
VERTEX E (MV)
FINAL E (MV)
SCAN RATE (MV/S)
THRESHOLD I (UA/CM²)
CONDITION E (MV)
CONDITION T (S)
INIT DELAY (MV/S OR S)

CYCLIC POLN
CDA 34
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA (CMS²)
EQ WT (GM)
DENSITY (GM/CM³)
CATHODIC TAFEL (MV)
ANODIC TAFEL (MV)

4.106
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-245
4
1444.228
1.169021E-02
1.169021E-02
1444.228

LEGEND

CDA 102; RUN 7; TRIAL 1
DE-AERATE W/ARGON
CL=6; NO3=10; SO4=20
F=2; HCO3=85; T=30 C

DONE ON PAR 273
23 OCT 1991

Cyclic Polarization of CDA-102
Model Solution: CL=6, SO₄=20, NO₃=10, F=2, HCO₃=85 30°C

CDA 34 Run 7; Trial 1

Purpose: Same as CDA 1 (p.153)

The test specimen, preparation, procedures, etc were as described in CDA 17 (p.171). Ref SCE #4 was used and checked as before, difference was less than 1.0 mV.

Test Solution Prep: To 500 ml of 17 MΩ water in a 1-L volumetric add 0.1226 g of NaHCO₃ (same lot # as p.215). Pipet 10.0 ml of CL stock, 20.0 ml of SO₄ stock, 10.0 ml of NO₃ stock, and 5.0 ml of F stock solutions (lot #'s 019-127, 019-132, 019-199, + 019-190 resp.) dilute to the mark.


Spec. dim: $\phi = 0.634$ cm $l = 1.903$ cm $A = 4.106$ cm²

- ① Specimen not pre-passivated; all surfaces polished to 600 grit
- ② Specimen held at open circuit for one hour before start
- ③ E cor at start -246 mV vs SCE
- ④ E Pt 10 min. before start -170 mV
- ⑤ Initial Temp. 30.0°C Final Temp. 31.0°C
- ⑥ Initial pH 8.16 @ 25°C Final pH 9.67 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Manual reverse @ 5930 μ A / +1311 mV

Specimen covered w/a dark brownish film which flaked off very easily. General corrosion was evident, and grains could be discerned on the specimen. Solution had a slight bluish tinge, mostly due to a flabby bluish precipitate (small amount).

Stored andish ECTA #5

Walter J. Mochowicki
10/23/91

CDA 35
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 35
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.095
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-231
4
5470.086
.3250305
.3250305
5470.086

LEGEND

CDA 102; RUN 8; TRIAL 10
DE-AERATE W/ARGON
CL=6; NO3=10; SO4=20; F=2
HCO3=8500; T=95 C

DONE ON PAR 273
24 OCT 1991

Cyclic Polarization of CDA-102
Model Solution: HCO₃ = 8500; CL=6, SO₄=20, NO₃=10, F=2 95°C

CDA 35 Run 8; Trial 10

Purpose: Same as CDA 2 (p. 133).

The test specimen, preparation, procedures, etc were as described in CDA 17 (p. 121). Ref SCE #1 was used and checked as before, difference was less than 1.0 mV.

Test Solution Prep: To 500 ml of 17 M₂ water in a 1-L volumetric add 12.1978 g NaHCO₃ (same lot # as p. 215). Pipet 10.0 ml of Cl₂, 20.0 ml of SO₄, 10.0 ml of NO₃ and 2.0 ml of F stock solutions (same lot #'s as p. 217). Dilute to the mark.

Spec Area: $\phi = 0.635 \text{ cm}$ $l = 1.894 \text{ cm}$ $A = 4.095 \text{ cm}^2$


- ① Specimen not pre-passivated; all surfaces polished to 600 grit
- ② Specimen held at open circuit for one hour before start
- ③ E scan at start -231 mV vs SCE
- ④ E Pt 10 min. before start -197 mV
- ⑤ Initial Temp. 95.0°C Final Temp. 94.3°C
- ⑥ Initial pH 8.35 @ 25°C Final pH 9.69 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$

Specimen covered w/a black, dull, uniform film which was modestly adherent. Test solution remained water clear.

Stored on disk E6+C #5.

nl

Walter J. Mockowski
10/24/91



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (MV)
VERTEX E (MV)
FINAL E (MV)
SCAN RATE (MV/S)
THRESHOLD I (UA/CM²)
CONDITION E (MV)
CONDITION T (S)
INIT DELAY (MV/S OR S)

CYCLIC POLN
CDA 36
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA (CMS²)
EQ WT (GM)
DENSITY (GM/CM³)
CATHODIC TAFEL (MV)
ANODIC TAFEL (MV)

4.07
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-287
4
5159.705
-408.3538
5.651106E-02
5159.705

LEGEND

CDA 715; EFFECT OF BICARBONATE
DE-AERATE W/ARGON
HCO3=122; CL=1000; SO4=1000
NO3=10; F=2
60 C

DONE ON PAR 273
25 OCT 1991

Cyclic Polarization of CDA-715

Model Solution: HCO₃ = 122; CL=1000; SO₄=1000; NO₃=10; F=2 60°C

CDA 36

Purpose: To evaluate the effect of bicarbonate on the pitting of CDA-715.

CDA-715 (Lot # 7037) was used. Specimen preparation, procedures, etc were as described in CDA 2 (p. 133). Ref SCE #1 was used and checked as before, difference was less than 1.0 mV.

Test Solution Prep: To 500 ml of 17 M-2 water in a 1-L volumetric add 0.1691 g of NaHCO₃ (Same lot # as p. 215). Add 1.4881 g of Na₂SO₄ and 1.6468 g NaCl (lot #'s on p. 215). Pipet 10.0 ml of NO₃ and 2.0 ml of F stock solutions (lot #'s on p. 215). dilute to the mark.


Spec. Dim: $\phi = 0.632$ cm $l = 1.896$ cm $A = 4.070$ cm²

- ① Specimen not pre-passivated; all surfaces polished to 600 grit
- ② Specimen held at open circuit for one hour before start
- ③ E corr at start -287 mV vs SCE
- ④ E PT 10 min before start -2 mV.
- ⑤ Initial Temp. 61.0°C Final Temp. 61.0°C
- ⑥ Initial pH 8.05 @ 25°C Final pH 9.18 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Auto reverse @ 5000 μ A/cm²

Specimen covered w/a copper colored film which easily flaked off. Solution was clear with some orange precipitate. No localized attack observed.

Start on disk EG+A #5.

Walter J. Mackowski
10/25/91

CDA 37
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(μA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 37
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.098
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-293
4
5710.103
-1059.053
.2098585
5710.103

LEGEND

CDA 715; EFFECT OF BICARBONATE
DE-AERATE W/ARGON
HCO3=1000; CL=1000; SO4=1000
NO3=10; F=2
60 C

DONE ON PAR 273
28 OCT 1991

Cyclic Polarization of CDA-715

Model Solution: Same as p.221 except 1000ppm HCO₃ 60°C 223

CDA 37

Purpose: Same as CDA 36 (p. 221)

The test specimen, preparation, procedures, cell, etc were as described in CDA 1 (p. 133). Ref SCE #1 was used and checked as before, difference was less than 1.0 mV.

Test Solution Prep: Prepared as on p.221 from same chemical + solution lot #'s. Actual salt weights were 1.3880 g NaHCO₃; 1.4789 g Na₂SO₄ and 1.6472 g of NaCl.


Spec. Dim: $\phi = 0.636$ cm $l = 1.892$ cm $A = 4.098$ cm²

- ① Specimen not pre-passivated; all surface polished to 600 grit.
- ② Specimen held at open circuit for one hour before start.
- ③ E corr at start -293 mV vs SCE.
- ④ E Pt 10 min before start +50 mV.
- ⑤ Initial Temp. 60.5°C Final Temp. 59.0°C
- ⑥ Initial pH 8.37 @ 25°C Final pH 9.09 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Auto reverse @ 5000 μA/cm²

Specimen covered in part of reddish-brown film on top of which was some bluish-green film. Film was easily removed. Solution remained clear. No pitting or localized attack observed.

Stored on dish ECT# 5.

Walter J. MacKowski
10/28/91



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	CDA 38
INITIAL E(MV)	0 VS E
VERTEX E(MV)	100 VS E
FINAL E(MV)	100 VS E
SCAN RATE(MV/S)	.17
THRESHOLD I(UA/CM^2)	5000
CONDITION E(MV)	PASS
CONDITION T(S)	PASS
INIT DELAY(MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA(CMS^2)	4.103
EQ WT(GM)	PASS
DENSITY(GM/CM^3)	PASS
CATHODIC TAFEL(MV)	PASS
ANODIC TAFEL(MV)	PASS

DATA SCALE

ECORR	-305
MV/PT	4
DATA MAX	7019.254
DATA MIN	-338.7765
ABS MIN	2.437241E-02
ABS MAX	7019.254

LEGEND

CDA 715; EFFECT OF BICARBONATE
DE-AERATE W/ARGON
HCO3=2000; CL=1000; SO4=1000
NO3=10; F=2
60 C

DONE ON PAR 273
29 OCT 1991

Cyclic Polarization of CDA-115
Model solution: Same as p.221 except 2000 ppm HCO₃ 60°C 225
CDA 38
Purpose: Same as CDA 36 (p.221)

The test specimen, preparation, procedures, etc were as described in CDA 7 (p.133). Ref SCE #1 was used and checked as before, difference was less than 1.0mV.

Test solution Prep: Prepared as on p.221 from same chemical + solution lot #'s. Actual salt weights used were 2.7792g NaHCO₃; 1.4790g Na₂SO₄; + 1.6461g of NaCl.


Spec. Dim: $\phi = 0.635$ cm $l = 1.898$ g cm $A = 4.103$ cm²

- 1 Specimen not pre-passivated; all surfaces polished to 600 grit
- 2 Specimens held at open circuit for one hour before start
- 3 E corr at start -305 mV vs SCE
- 4 E Pt 10 min before start +51 mV
- 5 Initial Temp. 66.0°C Final Temp 60.0°C
- 6 Initial pH 8.39 @ 25°C Final pH 9.28 @ 55°C
- 7 Scan rate 0.17 mV/sec
- 8 Argon purge
- 9 Done on PAR 273
- 10 Auto reverse @ 5000 μ A/cm²

Specimen had copper colored scale on it.
Solution was clear. Some shallow pits and/or localized attack was evident.

Stored on dish E.C.A. #5

Walter Phacharski
10/29/91

CDA 39
CYCLIC POLN

RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM^2)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CDA 39
0 VS E
100 VS E
100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS^2)
EQ WT(GM)
DENSITY(GM/CM^3)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.095
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-305
4
6691.087
-959.707
3.614164E-02
6691.087

LEGEND

CDA 715; EFFECT OF BICARBONATE
DE-AERATE W/ARGON
HCO3=4000; CL=1000; SO4=1000
NO3=10; F=2
60 C

DONE ON PAR 273
30 OCT 1991

Cyclic Voltammetry of CDA-715
Model Solution: Same as p. 221 except 4000ppm HCO₃ 60°C 227
CDA 39

Purpose: Same as CDA 36 (p. 221).

The test specimen, preparation, procedures, cell, etc were as described in CDA 2 (p. 133). Ref SCE #1 was used and checked as before, difference was less than 1 mV.

Test Solution Prep. Prepared as on p. 221 from same chemical and solution lot #'s. Actual salt weights used were 5.5555 g NaHCO₃; 1.4790 g Na₂SO₄; and 1.6459 g NaCl.


Spec. Dim: $\phi = 0.635$ cm $l = 1.894$ cm $A = 4.095$ cm²

- ① Specimen not pre-passivated; all surfaces polished to 600 grit
- ② Specimen held at open circuit for one hour before start
- ③ E scan at start -305 mV vs SCE
- ④ E Pt 10 min before start +62 mV
- ⑤ Initial Temp. 60.0°C Final Temp. 60.0°C
- ⑥ Initial pH 8.34 @ 25°C Final pH 9.23 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273
- ⑩ Auto reverse @ 5000 μ A/cm²

Specimen had ~50% area of copper colored scale w/ some bluish green product on top of that. Pitting was evident in the "silver" colored part of the specimen. Solution was clear.

Stored on desk E676 #5

Walter J. Mockuschi
10/30/91



RUN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	CDA 40
INITIAL E (MV)	0 VS E
VERTEX E (MV)	100 VS E
FINAL E (MV)	100 VS E
SCAN RATE (MV/S)	.17
THRESHOLD I (UA/CM^2)	5000
CONDITION E (MV)	PASS
CONDITION T (S)	PASS
INIT DELAY (MV/S OR S)	3600 S

SAMPLE PARAMETERS

AREA (CMS^2)	4.096
EQ WT (GM)	PASS
DENSITY (GM/CM^3)	PASS
CATHODIC TAFEL (MV)	PASS
ANODIC TAFEL (MV)	PASS

DATA SCALE

ECORR	-313
MV/PT	4
DATA MAX	6567.382
DATA MIN	-3.662109E-02
ABS MIN	0
ABS MAX	6567.382

LEGEND

CDA 715; EFFECT OF BICARBONATE
DE-AERATE W/ARGON
HCO3=6000; SO4=1000; CL=1000
NO3=10; F=2
60 C

DONE ON PAR 273
31 OCT 1991

Cyclic Polymerization of CDA-715
Model solution: same as p.221 except 6000ppm HCO₃ 60°C 229
CDA 40

Purpose: Same as CDA 36 (p.221).

The test specimen, procedure, preparation, etc. were as described in CDA 2 (p.133). Ref SCE#1 was used and checked as before, difference was less than 10 mV.

Test solution prep: Prepared as on p.221 from the same chemical and solution lot #'s. Actual salt weights used were 8.3334 g NaHCO₃; 1.4792 g Na₂SO₄; + 1.6470 g NaCl.

Spec. Dim: $\phi = 0.634 \text{ cm}$ $l = 1.898 \text{ cm}$ $A = 4.096 \text{ cm}^2$

- ① Specimen not pre-passivated; all surfaces polished to 600 grit
- ② Specimen held at open circuit for one hour before start
- ③ E can at start
- ④ E Pt 10 min before start -50 mV
- ⑤ Initial Temp. 61.0°C Final Temp. 60.5°C
- ⑥ Initial pH 8.33 @ 25°C Final pH 9.25 @ 25°C
- ⑦ Scan rate 0.17 mV/sec
- ⑧ Argon purge
- ⑨ Done on PAR 273.
- ⑩ Auto reverse @ 5000 $\mu\text{A/cm}^2$

Specimen was slightly darkened w/ greenish globules of corrosion spotted over the surface. No pits were evident. Solution remained clear.

Stored on disk ECL #5

Shallow areas of attack
under green corrosion
product.

Walter J. Mocharsh
10/31/91

Preparation of SO_4 Stock Solution

Purpose: Stock solution used in preparation of test solutions.

Weigh out 1.4787 g of Na_2SO_4 (Fisher lot # 901213). Dissolve in 500 ml of 17M R water in a 1-L volumetric flask + dilute to the mark.

Label as SO_4 CNARA 019-231

Walter J. Macdonald
11/1/91

Room temperature test

Purpose: To determine what cause the increase in pH over time in the test solutions.

Solution Prep: A solution containing: 8500 ppm HCO_3^- ; 1000 ppm Cl^- ; 1000 ppm SO_4^{2-} ; 10 ppm NO_3^- and 2 ppm F was prepared by the following:

In a 2-L volumetric add 1 liter 17 M Ω water add 24.1793 g NaHCO_3 , 3.2928 g NaCl , and 2.9577 g of Na_2SO_4 (same lot #'s as p. 231). Pipet 20.0 ml of NO_3^- and 2.0 ml of F stock solutions (lot # 019-199 + 019-190 resp.). Dilute to mark.

Method: Approx. 900 ml of this solution was placed in each of two polypropylene bottles which were loosely covered w/ Kimwipes to keep out dust. The solutions were held at 25°C in a shaker bath which oscillated @ 30 rpm. pH readings in triplicate were taken at periodic intervals.

initial pH	8.18, 8.20, 8.22 (all pH's @ 25°C)	
+ 7 day	8.32, 8.32, 8.32 (bottle 1)	8.58, 8.58, 8.58 (bottle 2)
+ 3 1/2 "	8.75, 8.74, 8.74 (")	8.80, 8.80, 8.80 (")
+ 5 "	8.81, 8.81, 8.81 (")	8.88, 8.88, 8.88 (")
+ 7 "	8.85, 8.85, 8.85 (")	8.92, 8.91, 8.91 (")
+ 9 1/2 "	8.93, 8.94, 8.94 (")	8.97, 8.98, 8.98 (")
+ 20 "	8.97, 8.97, 8.97 (")	9.16, 9.16, 9.16 (")

A second solution w/ 85 ppm HCO_3^- was prepared by: to 500 ml of 17 M Ω in a 1-L volumetric add 0.1224 g NaHCO_3 (same lot # as p. 231). Pipet 10.0 ml Cl^- , 20.0 ml SO_4^{2-} , 10.0 ml NO_3^- and 2.0 ml of F stock solutions (lot #'s as p. 217). Dilute to mark.

Place about 900 ml. in a polypropylene bottles as noted above and place in same shaker bath.

	all pH's @ 25°C		
initial pH	8.08	8.10	8.08
+ 1 day	8.38	8.48	8.32
+ 3 "	8.75	8.81	8.78

water J. H. H. H.
11/1/91

+ 4 1/2 days	8.82	8.85	8.82	{don't checked cal. + buffers
+ 10 days	8.39	8.27	8.27	
+ 20 days	8.32	8.29	8.30	

A third solution, containing only 8500 ppm HCO_3 was prepared by weighing 12.1994 g of NaHCO_3 (lot # on p. 221) into a 1-L volumetric w/ 500 ml of 17M Na_2CO_3 water and diluting to volume. About 900 ml were placed in a polypropylene bottle and placed in the same shaker bath as the other two solutions.

initial pH 8.13 @ 25°C
+ 1 day 8.50

+ 3 days	8.77	8.77	8.78
+ 7 days	8.95	8.94	8.94
+ 13 "	9.09	9.08	9.08

pH Change in Solutions

95°C Temperature Test

Purpose: Same as on p. 233.

Solution Prep: To 500 ml of 17M Na_2CO_3 water in a 1-L volumetric add 12.2018 g NaHCO_3 , 1.6169 g NaCl , + 1.4788 g Na_2SO_4 (same lot #s as p. 221). Pipet 10.0 ml HNO_3 and 2.0 ml of F stock solutions (stock #s on p. 233). Dilute to mark.

Method: Put about 900 ml of the solution in the 5-port corrosion flask that has been in use. Attach condenser + close all other ports and heat to 95°C. Remove about 30 ml at certain time intervals into a 4oz glass bottle and stopper tightly. Cool under stream of cold water + when cool, measure pH. Replace into test flask after pH measurement.

Readings as flask heated up:

	pH
40°C after 15 min	8.13
73°C " 30 "	8.46
94°C " 45 "	8.53
95°C " 55 "	8.58

Readings at 95°C (NOTE: pH was measured at RT after solution attained 95°C)

	pH
after 15 min	8.64
" 30 "	8.70
" 45 "	8.71
" 1 hr	8.73
" 2 "	8.81
" 4 "	8.84

After 4 hrs, started Ar purge: 15 min. after purge start, pH was 9.21
after 30 min of purging pH was 9.35
discontinued the test.

Walter J. Macchiusi
11/1/91

pH Change in Solutions

95°C Test

Purpose: Same as p. 233.Solution Prep: Same as on p. 235 w/ same chemical & solution but # 1's. Actual salt weights were 12.1987g NaHCO_3 , 1.6462g NaCl and 1.4788g Na_2SO_4 .Method: Same as on p. 233. This test will be allowed to run for 24 hours.

Initial pH 8.20 @ 25°C Final pH 8.89 @ 25°C

The total dissolved CO_2 was determined using ASTM D513: Method A "Gas Sensing Electrode Test Method". The Orion 750A pH/ISE was used w/ a Orion CO_2 gas sensing electrode. The CO_2 value was then converted to bicarbonate.

The sample was diluted 200:1 w/ 17MR water.

as mixed $\text{CO}_2 = 33.6 \text{ mg/L}$ 9316 ppm HCO_3 after 24 hrs. $\text{CO}_2 = 32.4 \text{ " "}$ 8989 ppm HCO_3

Walter J. Macdonald
11/13/91

Assay of CO_2 in Bicarbonate Test Solutions:Purpose: To try to correlate pH change with changes in bicarbonate concentration.

The solutions described on pp. 233, 234 & 235 were analyzed for CO_2 concentration using ASTM D513 as described on p. 236.

Solution	CO_2 (mg/L)	HCO_3 (ppm)
85 ppm HCO_3 (initial)	65.7	91
" " (final)	82.1	113
two aliquots of same mixture { 8500 ppm HCO_3 (initial)	289 (20:1 dil)	8013
" " (final)	269 (" ")	7458
{ 8500 ppm HCO_3 (initial)	296 (20:1 dil)	8207
" " (final)	269 (" ")	7348
* 8500 HCO_3 ; 24 hr, N_2 (initial)	288 (20:1)	7985
" " (final)	185 (20:1)	5129
8500 HCO_3 ; 24 hr, no purge (init)	32.4 (200:1)	8873
" " (final)	25.7 (200:1)	7126
8500 HCO_3 only (init)	33.6 (200:1)	9316
" " (final)	26.1 (200:1)	7237

* this solution measured "fresh" all others measured 2-4 weeks after preparation.

Walter J. Macdonald
11/26/91

COTST.1

Purpose: To monitor current in high H_2O_2 solution with polarized copper alloy with addition of various reactive ions.

Spec Prep: A cylindrical specimen was wet polished in 220 & finally 600 grit paper. It was cleaned in soapy water in an ultrasonic bath, rinsed w/ DI water, rinsed w/ acetone and dried in hot air. The 5 neck corrosion cell described on p. 9 was used for the test.

Solution Prep: An 8500 H_2O_2 , 6 cc; 10 NO_3 ; 20 SO_4 ; and 2 ppm F solution was prepared. Two liters were made in a 2-L volumetric by adding 24.4 g of NaHCO_3 (Fisher lot # 897581) to 1-L of 17 M- Ω water.

Pipet 20.0 ml of Cl_2 , 40.0 ml of SO_4 , 20.0 ml of NO_3 and 4.0 ml of F stock solutions (# 019-127, 019-231, 019-199 and ~~019-127~~ 019-121 resp.) dilute to mark w/ H_2O .

Procedure: Purge one hour w/ H_2 . Immerse specimen & hold at OCV for one hour. Polarize at +500 mV and after one hour add Cl^- to make - up 1000 ppm (use 900 ml of test solution, then add 100 ml of 10,000 ppm Cl^-). Using multi channel p-stat + Stramberg Tree WB, record current density, voltage & time - see p. 240. Run at room temperature.

Specimen was a dark grey color.

Stored on disk COPDAT 7.

Note: The data acquisition program

Workbench PC was used and

the logic sequence for the COTST series

was stored under CDA1.HBB.

N. Snickas

Walter J. MacLachlan

12/13/91

Outputs:

< None >

Name:

AO:3 Analog Output

Card Type:

STI ACAO-12

Channel Number:

3

Range:

+/- 5 Volts

Resolution:

0.024%

Inputs:

CA22 set potential

Outputs:

< None >

Name:

AO:4 Analog Output

Card Type:

STI ACAO-12

Channel Number:

4

Range:

+/- 5 Volts

Resolution:

0.024%

Inputs:

CA26 set potential

Outputs:

< None >

3 solutions
 of

not polished
 & was
 both, rinsed
 in hot air
 on p. 9 was

50%; and
 others were
 24.4% of
 water.
 of NO₂ and
 019-231,
 date to make

specimen +
 500 ml and
 100 ppm (use
 100 ppm Cl⁻)
 see WB,
 see p. 240).

Note:

He
 was

N. Snickel

12/13/91

Macharski

Film Formation on CDA-715 (A. 7037)

X Axis Label:
Y Axis Min:
Y Axis Max:
Inputs:
CA1 c.d. ch.1
Outputs:
< None >

< None >
1.0e-07
0.001

Name:
Chart Color:
X Axis Label:
X Axis Min:
X Axis Max:
Y Axis Label:
Y Axis Min:
Y Axis Max:
Inputs:
CA4 c. d. ch. 2
Outputs:
< None >

CH2 c. d. ch.2
White
Hours
0.0
36.0
< None >
1.0e-07
0.001

Name:
Chart Color:
X Axis Label:
X Axis Min:
X Axis Max:
Y Axis Label:
Y Axis Min:
Y Axis Max:
Inputs:
CA20 c. d. ch. 3
Outputs:
< None >

CH5 c. d. ch3
White
Hours
0.0
36.0
< None >
1.0e-07
0.001

Name:
Chart Color:
X Axis Label:
X Axis Min:
X Axis Max:
Y Axis Label:
Y Axis Min:
Y Axis Max:
Inputs:
CA23 c. d. ch. 4
Outputs:
< None >

CH6 c. d. ch. 4
White
Hours
0.0
36.0
< None >
1.0e-07
0.001

Type: Analog Output

Name:
Card Type:
Channel Number:
Range:
Resolution:
Inputs:
CA3 set potential
Outputs:
< None >

AO:1 Analog Output
STI ACAO-12
1
+/- 5 Volts
0.024%

Name:
Card Type:
Channel Number:
Range:
Resolution:
Inputs:
CA6 set potential

AO:2 Analog Output
STI ACAO-12
2
+/- 5 Volts
0.024%

Note:

12

was

N. Snicker

3 solution
of

et polished
+ was
both, mixed
d in hot air
p. 9 was

say; and
then were
4.4 g of
water.

NO₂ and
19-23/
ute to make

specimen +
20 ml and
0 ppm (use
10 ppm CO₂)
e WB,
see p. 240.

charush

12/13/91

AXIS LABEL:
< None >

Name:
Log Status:
Sample Rate:
Gate:

LO4 COPTST10.DAT
< disabled >
15.0 Minutes
< None >

Data Format:
Heading:
File Path:
File Name:
Date Stamp:
Time Stamp:

CONSTANT POTENTIAL DATA, CH.4
C:\WB
COPTST10.DAT
enabled
enabled

Inputs:
T14 Timer
Outputs:
< None >

CA23 c. d. ch. 4

CA24 invert

Type: Meter

Name:
Output Type:
Units:
Integer:
Decimal:
Inputs:
CA2 invert
Outputs:
< None >

MT1 Meter
Fixed Point
< None >
6
3

Name:
Output Type:
Units:
Integer:
Decimal:
Inputs:
CA5 invert
Outputs:
< None >

MT2 Meter
Fixed Point
< None >
6
3

Name:
Output Type:
Units:
Integer:
Decimal:
Inputs:
CA21 invert
Outputs:
< None >

MT7 Meter
Fixed Point
< None >
6
3

Name:
Output Type:
Units:
Integer:
Decimal:
Inputs:
CA24 invert
Outputs:
< None >

MT8 Meter
Fixed Point
< None >
6
3

Type: Chart

Name:
Chart Color:
X Axis Label:
X Axis Min:
X Axis Max:

CH1 c.d.ch.1
White
Hours
0.0
36.0

Note:

was

N. Snicker

12/13/91

3 solution
of

it polished
+ was
both, mixed
d in hot air
p. 9 was

say; and
there were
14.4 g of
water.
NO₂ and
19-23%,
late to make

recimen +
20 ml and
2 ppm (one
20 ppm Cl⁻)
+ WB,
see p. 240).

charush

Inputs:
 "a" constant: -1.0
 "b" constant: 0.0
 "c" constant: 0.0

Inputs:
 AI:16 measured pot

Outputs:
 MT8 Meter LO4 COPTST10.DAT

Name: CA26 set potential
 Function: aX + bY
 X input: PL6 Pulse
 Y input: 0.0
 "a" constant: 0.5
 "b" constant: 0.0
 "c" constant: 0.0

Inputs:
 PL6 Pulse
 Outputs:
 AO:4 Analog Output

Type: Log

Name: LO1 Log
 Log Status: < disabled >
 Sample Rate: 5.0 Minutes
 Gate: < None >
 Data Format:
 Heading: CONSTANT POTENTIAL DATA, CH.3
 File Path: < None >
 File Name: < None >
 Date Stamp: enabled
 Time Stamp: enabled
 Inputs:
 TI1 Timer CA1 c.d. ch.1 CA2 invert
 Outputs:
 < None >

Name: LO2 Log
 Log Status: < disabled >
 Sample Rate: 5.0 Minutes
 Gate: < None >
 Data Format:
 Heading: CONSTANT POTENTIAL DATA, CH.3
 File Path: < None >
 File Name: < None >
 Date Stamp: enabled
 Time Stamp: enabled
 Inputs:
 TI2 Timer CA4 c. d. ch. 2 CA5 invert
 Outputs:
 < None >

Name: LO3 COPTST9.DAT
 Log Status: < disabled >
 Sample Rate: 15.0 Minutes
 Gate: < None >
 Data Format:
 Heading: CONSTANT POTENTIAL DATA, CH.3
 File Path: C:\WB
 File Name: COPTST9.DAT
 Date Stamp: enabled
 Time Stamp: enabled
 Inputs:
 TI3 Timer CA20 c. d. ch. 3 CA21 invert
 Outputs:

Note:

He
 was

N. Snicker

12/13/91

solution
 of

it polished
 + was
 bath, rinsed
 d in hot air
 p. 9 was

say; and
 time were
 4.4 g of
 water.
 NO₂ and
 219-23/
 into to make

recimen +
 20 ml and
 2 ppm (use
 20 ppm CO₂)
 e WB,
 ce p.240).

charush

Film Formation on COA-715 (A. 7037)

Outputs:

MT2 Meter

LO2 Log

Name:

CA6 set potential

Function:

aX + bY

X input:

PL2 Pulse

Y input:

0.0

"a" constant:

0.5

"b" constant:

0.0

"c" constant:

0.0

Inputs:

PL2 Pulse

Outputs:

AO:2 Analog Output

Name:

CA20 c. d. ch. 3

Function:

aX / bY

X input:

AI:5 current ch. 3

Y input:

4.12

"a" constant:

-1.0

"b" constant:

10.0

"c" constant:

0.0

Inputs:

AI:5 current ch. 3

Outputs:

CH5 c. d. ch3

LO3 COPTST9.DAT

Name:

CA21 invert

Function:

aX + bY

X input:

AI:15 measured pot

Y input:

0.0

"a" constant:

-1.0

"b" constant:

0.0

"c" constant:

0.0

Inputs:

AI:15 measured pot

Outputs:

MT7 Meter

LO3 COPTST9.DAT

Name:

CA22 set potential

Function:

aX + bY

X input:

PL5 Pulse

Y input:

0.0

"a" constant:

0.5

"b" constant:

0.0

"c" constant:

0.0

Inputs:

PL5 Pulse

Outputs:

AO:3 Analog Output

Name:

CA23 c. d. ch. 4

Function:

aX / bY

X input:

AI:7 current ch. 4

Y input:

4.11

"a" constant:

-1.0

"b" constant:

10.0

"c" constant:

0.0

Inputs:

AI:7 current ch. 4

Outputs:

CH6 c. d. ch. 4

LO4 COPTST10.DAT

Name:

CA24 invert

Function:

aX + bY

X input:

AI:16 measured pot

solution
of

it polished
+ was
boiled, mixed
d in hot air
p. 9 was

say; and
there were
14.4 g of
water.

NO₂ and
219-231,
into to mark.

recimen +
20 ml and
0 ppm (one
10 ppm CO₂)
a WB,
see p. 240).

Note:

He
was

charush

N. Snicker

12/13/91

Start value:

LOW

Reset on exit

enabled

Inputs:

< None >

Outputs:

TI4 Timer

CA26 set potential

Type: Calculation

Name:

CA1 c.d. ch.1

Function:

aX / bY

X input:

AI:1 current ch. 1

Y input:

4.12

"a" constant:

-1.0

"b" constant:

10.0

"c" constant:

0.0

Inputs:

AI:1 current ch. 1

Outputs:

CH1 c.d. ch.1

LO1 Log

Name:

CA2 invert

Function:

aX + bY

X input:

AI:13 measured pot

Y input:

0.0

"a" constant:

-1.0

"b" constant:

0.0

"c" constant:

0.0

Inputs:

AI:13 measured pot

Outputs:

MT1 Meter

LO1 Log

Name:

CA3 set potential

Function:

aX + bY

X input:

PL1 Pulse

Y input:

0.0

"a" constant:

0.5

"b" constant:

0.0

"c" constant:

0.0

Inputs:

PL1 Pulse

Outputs:

AO:1 Analog Output

Name:

CA4 c. d. ch. 2

Function:

aX / bY

X input:

AI:3 current ch. 2

Y input:

4.12

"a" constant:

-1.0

"b" constant:

10.0

"c" constant:

0.0

Inputs:

AI:3 current ch. 2

Outputs:

CH2 c. d. ch.2

LO2 Log

Name:

CA5 invert

Function:

aX + bY

X input:

AI:14 measured pot

Y input:

0.0

"a" constant:

-1.0

"b" constant:

0.0

"c" constant:

0.0

Inputs:

AI:14 measured pot

Note:

He

was

N. Smith

12/13/91

solution
ofet polished
+ was
both, rinsed
d in hot air
p. 9 wassay; and
there were
14.4 g of
water.
NO₂ and
19-23%,
into to make
recimen +
20 ml and
2 ppm (use
20 ppm Cl⁻)
+ WB,
see p. 240).

charushin

Inputs:

< None >

Outputs:

CA24 invert

Type: Timer

Name:

TI1 Timer

Inputs:

PL1 Pulse

Outputs:

LO1 Log

Name:

TI2 Timer

Inputs:

PL2 Pulse

Outputs:

LO2 Log

Name:

TI3 Timer

Inputs:

PL5 Pulse

Outputs:

LO3 COPTST9.DAT

Name:

TI4 Timer

Inputs:

PL6 Pulse

Outputs:

LO4 COPTST10.DAT

Type: Pulse

Name:

PL1 Pulse

High Duration:

496.0 Hours

Low Duration:

0.1 Seconds

Start Value:

Low

Reset on exit

enabled

Inputs:

< None >

Outputs:

TI1 Timer

CA3 set potential

Name:

PL2 Pulse

High Duration:

496.0 Hours

Low Duration:

0.1 Seconds

Start Value:

Low

Reset on exit

enabled

Inputs:

< None >

Outputs:

TI2 Timer

CA6 set potential

Name:

PL5 Pulse

High Duration:

496.0 Hours

Low Duration:

0.1 Seconds

Start Value:

Low

Reset on exit

enabled

Inputs:

< None >

Outputs:

TI3 Timer

CA22 set potential

Name:

PL6 Pulse

High Duration:

496.0 Hours

Low Duration:

0.1 Seconds

Note:

He
was

N. Snickles

12/13/91

solution
be ofit polished
+ was
both, unsold
d in hot air
p. 9 wassay; and
the were
14.4 g of
water.NO₂ and
19-23/
into to markrecimen +
00 mV and
0 ppm (was
10 ppm Cl⁻)
e WB,
see p. 240).

clarush

Fast Mode: < disabled >

Inputs:

< None >

Outputs:

CA20 c. d. ch. 3

Name:

Card Type:

Channel Number:

Range:

Resolution:

Output Type:

Sample rate:

Fast Mode:

Inputs:

< None >

Outputs:

CA23 c. d. ch. 4

Name:

Card Type:

Channel Number:

Range:

Resolution:

Output Type:

Sample rate:

Fast Mode:

Inputs:

< None >

Outputs:

CA2 invert

Name:

Card Type:

Channel Number:

Range:

Resolution:

Output Type:

Sample rate:

Fast Mode:

Inputs:

< None >

Outputs:

CA5 invert

Name:

Card Type:

Channel Number:

Range:

Resolution:

Output Type:

Sample rate:

Fast Mode:

Inputs:

< None >

Outputs:

CA21 invert

Name:

Card Type:

Channel Number:

Range:

Resolution:

Output Type:

Sample rate:

Fast Mode:

AI:7 current ch. 4

STI ACPC-16

7

Auto V

Lo Noise (17ms)

Voltage

10.0 Hertz

< disabled >

AI:13 measured pot

STI ACPC-16

13

Auto V

Lo Noise (17ms)

Voltage

10.0 Hertz

< disabled >

AI:14 measured pot

STI ACPC-16

14

Auto V

Lo Noise (17ms)

Voltage

10.0 Hertz

< disabled >

AI:15 measured pot

STI ACPC-16

15

Auto V

Lo Noise (17ms)

Voltage

10.0 Hertz

< disabled >

AI:16 measured pot

STI ACPC-16

16

Auto V

Lo Noise (17ms)

Voltage

10.0 Hertz

< disabled >

solution
ofet polished
+ was
boiled, rinsed
d in hot air
p. 9 wassay; and
there were
4.4 g of
water.NO₂ and
219-23/
into to makerecimen +
20 ml and
2 ppm (one
20 ppm Cl⁻)
e WB,
see p. 240).

Note:

He

was

N. Snickes

12/13/91

charushin

Worksheet Name: CDA1.WBB
 Hardware list:
 Name AIs AOs DIOs CTs DIIs DOs
 STI ACPC-16 16 0 16 0 0 0
 STI ACAO-12 0 6 8 0 0 0
 Maximum icons: 464
 Grid size: 16
 Snap to grid: < disabled >
 Report Unsynch: < disabled >
 Fast Mode: enabled
 Fast Mode Samples: 1000
 Fast Mode Rate: 1.0 KiloHertz
 Com ports: 2

Port: COM 1
 Comment: Mouse connected

Port: COM 2
 Baud rate: 9600
 Data bits: 8
 Stop bits: 1
 Duplex: Half
 Parity: None
 XonXoff: < disabled >
 Echo wait: < disabled >
 Line delay: < disabled >

IEEE: < disabled >

Type: Analog Input

Name: AI:1 current ch. 1
 Card Type: STI ACPC-16
 Channel Number: 1
 Range: Auto V
 Resolution: Lo Noise (17ms)
 Output Type: Voltage
 Sample rate: 10.0 Hertz
 Fast Mode: < disabled >
 Inputs:
 < None >

Outputs:
 CA1 c.d. ch.1

Name: AI:3 current ch. 2
 Card Type: STI ACPC-16
 Channel Number: 3
 Range: Auto V
 Resolution: Lo Noise (17ms)
 Output Type: Voltage
 Sample rate: 10.0 Hertz
 Fast Mode: < disabled >
 Inputs:
 < None >

Outputs:
 CA4 c. d. ch. 2

Name: AI:5 current ch. 3
 Card Type: STI ACPC-16
 Channel Number: 5
 Range: Auto V
 Resolution: Lo Noise (17ms)
 Output Type: Voltage
 Sample rate: 10.0 Hertz

Note:

He
 was

N. Snicker

12/13/91


solution
 of

et polished
 + was
 bath, rinsed
 in hot air
 p. 9 was

say; and
 there were
 4.4 g of
 water.
 NO₂ and
 19-23/
 into to make

recimen +
 20 ml and
 2 ppm (use
 10 ppm CO)
 e WB,
 ee p. 240).

charush



there

shed

mixed
hot air
was

and
were
of
and
3/4,
mark

en +
and
(use
CDA)
B,
240).

Note:

He

was

N. Snickler

12/13/91

charush

COPTST.2

Prep: Same as p.238

Test run the same as on p.238, except this one at 95°C.

Same solution was used as in COPTST 2.

Specimen had a thin gold-brown film.

Stored on disk COPDAT 1.

Walter Machowski
12/13/91

COPTEST 3 and COPTEST 4

Purpose: Same as COPTEST 2 (p. 238)

Cylindrical specimens were prepared as described on p. 238. The same 5-neck flasks were used. Test temperature for both tests was 95°C .

Solution Two liters were prepared as described on p. 238 from same lot no chemicals & solutions.

After holding at open circuit for one hour, polarize at $+500\text{ mV}$ vs SCE for one hour. To COTEST 3 add 1.3304g of Na_2SO_4 (lot #) in 30ml of water to bring to about 1000 ppm SO_4 . To COTEST 4 add 100 ml of 10,000 ppm Cl to bring to 1000 ppm Cl. Monitor current.

Note: Due to an error in setting of logging format, no useful current data was obtained.

COTEST 3: Specimen dark & covered w/ bluish green film (moderately thick)

COTEST 4: Specimen covered w/ a thin reddish-brown film.

Stored on disk COPDAT 2.

Walter J. Macintosh
12/18/91

COPTEST 5

Purpose: Same as COPTEST 1.

Specimen, preparation, cells were as described on p. 238.

Two liters of solution were prepared as on p. 238 from same lot # chemicals and solutions.

- ① de-aerate one hour before immersion
- ② Hold at open circuit one hour
- ③ Polarize at +500 mV vs SCE for one hour
- ④ Add 1.3304 g Na_2SO_4 (same lot # as p. 241) to bring cell conc. to 1000 ppm SO_4
- ⑤ Monitor current
- ⑥ Test run at R.T.

Specimen covered w/ thick bluish-green film.

Stored on dish COPDAT I.

Walter J. MacKowski
12/26/91

COPTEST 6

Purpose: Same as COPTEST 1.

Specimen, preparation, cells were as described on p. 238.

Same solution as COPTEST 5 was used.

- ① de-aerate one hour before immersion
- ② Hold at open circuit one hour
- ③ Polarize at +500 mV vs SCE for one hour
- ④ Add 100 ml of 10,000 ppm Cl sol'n to bring cell conc. to 1000 ppm Cl
- ⑤ Monitor current
- ⑥ Test run at R.T.

Specimen covered w/ a thick bluish green film.
Stored on dish COPDAT I.

Walter J. MacKowski
12/26/91 12/26

COPTEST 7

Purpose: Same as COPTEST 1.

Specimen preparation, solutions, etc were as described on p. 238.

Two liters of solution was prepared as described on p. 238 from the same lot # chemicals and solutions.

- ① De-aerate one hour before immersion
- ② Hold at open circuit one hour
- ③ Polarize at +500 mV vs SCE for one hour
- ④ Add 4.3304 g Na_2SO_4 (same lot # as p. 241) to bring cell conc to 1000 ppm SO_4 .
- ⑤ Monitor current
- ⑥ Test run at 95°C

Specimen was a dark red-brown color.

Stored on dish COPDAT 1.

Walter J. Machowski
12/27/91

COPTEST 8

Purpose: Same as COPTEST 1.

Specimen preparation, etc were as described on p. 238.

Same solution as COPTEST 7 was used.

- ① De-aerate one hour before immersion
- ② Hold at open circuit one hour
- ③ Polarize at +500 mV vs SCE for one hour
- ④ Add 100 ml of 10,000 ppm Cl solution
- ⑤ Monitor current
- ⑥ Test run at 95°C

Specimen was a dark gray-blue color.

Stored on dish COPDAT 1.

Walter J. Machowski
12/27/91

COPTEST 9

Purpose: Same as COPTEST 1

Specimen preparation, procedures, test cell, etc. were as described on p. 238.

Two liters of test solution were prepared as described on p. 238 from the same lot # chemicals and solutions.

- ① de-aerate one hour before immersion
- ② Hold at open circuit one hour
- ③ Polarize at +500 mV vs SCE for one hour.
- ④ Monitor current
- ⑤ Test run at 30°C.

Specimen had a greyish metallic film.

Stored on dish COPDAT 1.

Walter J. MacKowski
1/2/92

COPTEST 10

Purpose: Same as COPTEST 1

Specimen prep, procedures, test cell, etc. were as described on p. 238.

Used same solution as COPTEST 9.

- ① de-aerate one hour before immersion
- ② Hold at open circuit one hour
- ③ Polarize at +500 mV vs SCE for one hour.
- ④ Monitor current.
- ⑤ Test run at 30°C.

Specimen had a thin greenish film.

Stored on dish COPDAT 1.

Walter J. MacKowski
1/2/92

Cu T3

Purpose:

The test specimen, procedures, preparation, etc were as described on p. 171. Run was made on PAR 173/276.

A 0.075M borax + 0.15M boric acid solution was prepared by adding to 1500 ml of 17M Ω water in a 2-L volumetric the following: 57.1949g borax and 18.5492g boric acid (Fisher lot #'s 914886 and 916567A resp.). Stir until dissolved and dilute to volume.

- ① Specimen polished to 600 grit
- ② Held at OCV for one hour
- ③ E can at start -178mV vs SCE
- ④ Temp. room temp ($\sim 25^\circ\text{C}$)
- ⑤ Initial pH 8.60 Final pH 8.67
- ⑥ Scan rate 0.167mV/sec
- ⑦ Range w/argon (99.999%)
- ⑧ Done on PAR 173/276
- ⑨ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$

Test solution remained clear; specimen appeared the same before + after the test.

Stored on ECF # 45

257
see page 269

Walter J. Macdonald
3/23/92

Cu T4

Purpose:

Test specimen, procedures, preparation, etc were as described on p. 171. Run was made on PAR 273.

A 0.075M borax + 0.15M boric acid solution + 6ppm Cl^- + 20ppm SO_4^{2-} + 10ppm NO_3^- + 2ppm F was made by:

To 1500 ml of 17M Ω water in a 2-L volumetric add 57.1946g borax and 18.5501g boric acid (Fisher lot #'s 914886 and 916567A resp.). Pipet 20.0 ml of Cl^- stock, 40.0 ml of SO_4^{2-} stock, 20.0 ml of NO_3^- stock and 4.0 ml of F stock solutions (019-127, 025-91, 025-66 and 019-191 resp.). Stir until dissolved and dilute to volume.

- ① Specimen polished to 600 grit.
- ② Held at OCV for one hour
- ③ E can at start -225mV vs SCE
- ④ Temp: room temp ($\sim 25^\circ\text{C}$)
- ⑤ Initial pH 8.60 Final pH 8.70
- ⑥ Scan rate 0.167mV/sec
- ⑦ Range w/argon (99.999%)
- ⑧ Done on PAR 273
- ⑨ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$

Test solution remained clear. Specimen appeared unchanged.

Stored on ECF # 5.

258
see page 269

Walter J. Macdonald
3/23/92

Pm Cu T5

Purpose:

Test specimen, preparation, procedure were as on p. 133.

Used same solution as Cu T3.

- ① Specimen polished to 600 grit
- ② Held at OCV one hour
- ③ E com at start -145 mV vs SCE
- ④ Temp: room temp ($\sim 25^\circ\text{C}$)
- ⑤ Initial pH 8.60 Final pH 8.66
- ⑥ Scan rate 0.167 mV/sec
- ⑦ Purge w/Argon (99.999%)
- ⑧ Done on PAR 173/276
- ⑨ Auto reverse at $5000\text{ }\mu\text{A/cm}^2$

Solution remained clear. Specimen appeared unchanged.

Stored on EG+C # ~~4~~⁵ 4/9/92

See page 259

Walter J. MacKowski
3/23/92

Cu T6

Purpose:

Test specimen, preparation, procedure, etc were as on p. 133.

Used same solution as Cu T4.

- ① Specimen polished to 600 grit.
- ② Held at OCV one hour.
- ③ E com at start -236 mV vs SCE .
- ④ Temp: room temp ($\sim 25^\circ\text{C}$)
- ⑤ Initial pH 8.60 Final pH 8.67
- ⑥ Scan rate 0.167 mV/sec
- ⑦ Purge w/Argon (99.999%)
- ⑧ Done on PAR 273
- ⑨ Auto reverse at $5000\text{ }\mu\text{A/cm}^2$

Solution remained clear. Specimen appeared unchanged.

Stored on EG+C # ~~5~~⁴ 4/9/92

See page 260

Walter J. MacKowski
3/23/92

Cu T7

Purpose:

The test specimen, procedures, preparation, etc were as on p. 153, 171 w/Markowski 3/24/92

Solution: 2-Liter was prepared from the same lot # chemicals and solutions as described on p. 249. To one liter of this was added 0.122 g of NaNO_3 (Fisher lot # 897789).

- ① Specimen polished to 600 grit
- ② Held at OCV for one hour
- ③ E com at start -173 mV vs SCE
- ④ Temp. room temp ($\sim 25^\circ\text{C}$)
- ⑤ Initial pH 8.66 Final pH 8.68
- ⑥ scan rate 0.167 mV/sec
- ⑦ Purge w/Argon (99.999%)
- ⑧ Done on PAR 173/276
- ⑨ Auto reverse @ $5000 \mu\text{A/cm}^2$

Solution remained clear + specimen appeared unchanged.

Stored on EG+C #4, ⁵ ~~1~~ 3/25/92

See page 261

Walter J. Markowski
3/24/92

Cu T8

Purpose:

The test specimen, procedures, preparation were as on p. 171.

Solution: Used one liter of "base" solution on p. 252 and to this was add 0.0139 g NaHCO_3 (same lot # p. 252)

- ① Specimen polished to 600 grit
- ② Held at OCV for one hour
- ③ E com at start -204 mV vs SCE
- ④ Temp: room temp ($\sim 25^\circ\text{C}$)
- ⑤ Initial pH 8.67 Final pH 8.68
- ⑥ scan rate 0.167 mV/sec
- ⑦ Purge w/Argon (99.999%)
- ⑧ Done on PAR 273
- ⑨ Auto reverse @ $5000 \mu\text{A/cm}^2$

Solution remained clear + specimen appeared unchanged.

Stored on EG+C #4, ⁵ ~~1~~ 3/25/92 w/Markowski

See page 262

Walter J. Markowski
3/24/92

Cu T9
Purpose:

The test specimen was the same one from Cu T8 → repolished. Procedures, etc were as on p. 171

Solution: One liter prepared by adding 28.5977g of borax and 9.274g, boric acid to 700 ml of 17M water. Add 1.2221g of NaHCO_3 (same lot #12 as p. 252). Pipet 10.0 ml of Cl_2 , 10.0 ml of H_2O_2 , 20.0 ml of SO_4 and 2.0 ml of F stock solution (same lot #12 as p. 249). Dilute to mark.

- ① Specimen polished to 600 grit.
- ② Held at OCV for one hour
- ③ E can at start -174mV vs SCE
- ④ Room temp ($\sim 25^\circ\text{C}$)
- ⑤ Initial pH 8.66 Final pH 8.67
- ⑥ Scan rate 0.167 mV/sec
- ⑦ Purge w/Argon (99.999%)
- ⑧ Done on PAR 273
- ⑨ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$

Solution remained clear and specimen appeared unchanged.

Stored on EC+C #5

See page 263

Walter J. Moehrkens
 3/25/92

Cu T10
Purpose:

The test specimen from Cu T9 was repolished and used for this test. Preparation, procedures, etc were as on p. 171.

Solution: Two liters of solution were prepared as on p. 249 from the same lot # chemicals + solutions. One liter of this solution was measured out and to this 2.442g of NaHCO_3 was added to give approx 1700ppm HCO_3^- .

- ① Specimen polished to 600 grit.
- ② Held at OCV for one hour.
- ③ E can at start -194mV vs SCE
- ④ Room temp ($\sim 25^\circ\text{C}$)
- ⑤ Initial pH 8.64 Final pH 8.71
- ⑥ Scan rate 0.167 mV/sec
- ⑦ Purge w/Argon (99.999%)
- ⑧ Done on PAR 173/276
- ⑨ Auto reverse @ 5000 $\mu\text{A}/\text{cm}^2$

Solution remained clear + specimen appeared unchanged.

Stored on EC+C #4.

See page 264

Walter J. Moehrkens
 3/26/92

Cu T11
Purpose:

Used same specimen as Cu T7 (repolished).
 Procedures, preparation etc were as on p. 171.

Solution: To 500 ml of 17 M R water in a 1-L volumetric
 add 1.6468 g NaCl and 0.1225 g NaHCO₃ 99.99%
 3/27/92

(same lot #15 as p. 254). Pipet 10.0 ml of H₂O₂ stock, 20.0 ml
 of SA stock and 2.0 ml of F stock solution (same lot #15
 as p. 249). Dilute to the mark.


- ① R dish to 600 gpt.
- ② Cleanse + hold at OCV for one hour
- ③ E can at start -135 mV vs SCE
- ④ Room temp (~25°C)
- ⑤ Initial pH 8.31 Final pH 9.13
- ⑥ Scan rate 0.167 mV/sec
- ⑦ Purge w/argon (99.999%)
- ⑧ Done on Pan 173/276
- ⑨ Auto reverse @ 5000 $\mu A/cm^2$

Solution had blue ppt and specimen had
 a flaky brownish film. Grains visible
 when flaky scale was off.

Stored in EG+C #4

see page 265.

Walter J. Neumann
 3/27/92



UN PARAMETERS

TECHNIQUE	ORIGINAL NAME	VALUE	UNIT
CYCLIC POLN	CU T3	0	VS E
	INITIAL E (mV)	100	VS E
	VERTEX E (mV)	-100	VS E
	FINAL E (mV)	17	
	SCAN RATE (mV/s)	5000	
	THRESHOLD I (μA/cm²)	PASS	
	CONDITION E (mV)	PASS	
	CONDITION T (s)	PASS	
	INIT DELAY (mV/s OR S)	3600	S

AMPLE PARAMETERS

PARAMETER	VALUE
AREA (CM²)	4.17
EQ WT (GM)	PASS
DENSITY (GM/CM³)	PASS
CATHODIC TAFEL (mV)	PASS
ANODIC TAFEL (mV)	PASS


ATA SCALE

PARAMETER	VALUE
ECORR	-178
MV/PT	4
DATA MAX	5371.703
DATA MIN	1.558753E-02
ABS MIN	1.558753E-02
ABS MAX	5371.703

EGEND

TEST ON CDA-102 AT 25 C
 0.075M BORAX+0.15M BORIC ACID
 CL=6; SOT=20; NDS=10; f=2
 PH 8.6
 PURGE W/ARGON

N. Snidman 3/27/92



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CU T4
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.126
PASS
PASS
PASS
PASS

DATA SCALE


ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-225
4
5210.858
-6.519632E-02
0
5210.858

LEGEND

TST ON CDA-102 AT 25 C
0.075M BORAX+0.15M BORIC ACID
NO OTHER ANIONS
PH 8.6
PURGE W/ARGON

added.



JN PARAMETERS

TECHNIQUE	CYCLIC POLN
ORIGINAL NAME	CU T5
INITIAL E(MV)	0 VS E
VERTEX E(MV)	100 VS E
FINAL E(MV)	-100 VS E
SCAN RATE(MV/S)	.17
THRESHOLD I(UA/CM ²)	5000
CONDITION E(MV)	PASS
CONDITION T(S)	PASS
INIT DELAY(MV/S OR S)	3600 S

AMPLE PARAMETERS

AREA(CMS ²)	4.192
EQ WT(GM)	PASS
DENSITY(GM/CM ³)	PASS
CATHODIC TAFEL(MV)	PASS
ANODIC TAFEL(MV)	PASS

ATA SCALE

ECORR	-145
MV/PT	4
DATA MAX	5319.657
DATA MIN	2.266221E-02
ABS MIN	2.266221E-02
ABS MAX	5319.657

EGEND


TEST ON CDA 715 AT 25 C
0.075M BORAX+0.15M BORIC ACID
CL=6; S04=20; NO3=10; F=2
PH 8.6
PURGE W/ARGON

N. Swickel

3/27/92

N. Swickel

3/27/92



UN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (MV)
VERTEX E (MV)
FINAL E (MV)
SCAN RATE (MV/S)
THRESHOLD I (UA/CM²)
CONDITION E (MV)
CONDITION T (S)
INIT DELAY (MV/S OR S)

CYCLIC POLN
CU T6
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

AMPLE PARAMETERS

AREA (CMS²)
EQ WT (GM)
DENSITY (GM/CM³)
CATHODIC TAFEL (MV)
ANODIC TAFEL (MV)

4.166
PASS
PASS
PASS
PASS

ATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX


-236
4
5328.853
-5.352857E-02
0
5328.853

EGEND

TEST ON CDA 715 AT 25 C
0.075M BORAX+0.15M BORIC ACID
NO OTHER ANIONS
PH 8.6
PURGE W/ARGON

Sample
as Cu₂S

N. Sridhar 3/27/92



N PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E (MV)
VERTEX E (MV)
FINAL E (MV)
SCAN RATE (MV/S)
THRESHOLD I (UA/CM²)
CONDITION E (MV)
CONDITION T (S)
INIT DELAY (MV/S OR S)

CYCLIC POLN
CU T7
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

AMPLE PARAMETERS

AREA (CMS²)
EQ WT (GM)
DENSITY (GM/CM³)
CATHODIC TAFEL (MV)
ANODIC TAFEL (MV)

4.076
PASS
PASS
PASS
PASS

TA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX


-173
4
5201.177
-50.24533
1.447497E-02
5201.177

GEND

TEST ON CDA 102 AT 25 C
0.075M BORAX+0.15M BORIC ACID
CL-6; SO4-20; NO3-10; F-2
85 PPM HCO3
PURGE W/ARGON

24 MAR 1992

N. Sridhar
3/27/92



UN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CU T8
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

AMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.144
PASS
PASS
PASS
PASS

ATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX


-204
4
5357.143
-.2244208
6.756756E-03
5357.143

EGEND

TEST ON CDA 102 AT 25 C
0.075M BORAX+0.15M BORIC ACID
CL-6; NO3-10; SO4-20; F-2
10 PPM HCO3
PURGE W/ARGON

24 MAR 1992

N. Sridhar
3/27/92



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(UA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CU T9
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.154
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX


-174
4
5223.881
0
0
5223.881

LEGEND

TEST ON CDA 102 AT 25 C
0.075M BORAX+0.15M BORIC ACID
CL-6; SO4-20; NO3-10; F-2
850 PPM HCO3
PURGE W/ARGON

25 MAR 1992

N. Sridhar
3/27/92



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(μA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CU T10
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.006
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX


-194
4
5292.062
.0214678
.0214678
5292.062

LEGEND

TEST ON CDA 102 AT 25 C
0.075M BORAX+0.15M BORIC ACID
CL-6; NO3-10; SO4-20; F-2
1700 PPM HCO3
PURGE W/ARGON

26 MAR 1992

N. Sridhar
3/27/92



RUN PARAMETERS

TECHNIQUE
ORIGINAL NAME
INITIAL E(MV)
VERTEX E(MV)
FINAL E(MV)
SCAN RATE(MV/S)
THRESHOLD I(μA/CM²)
CONDITION E(MV)
CONDITION T(S)
INIT DELAY(MV/S OR S)

CYCLIC POLN
CU T11
0 VS E
100 VS E
-100 VS E
.17
5000
PASS
PASS
3600 S

SAMPLE PARAMETERS

AREA(CMS²)
EQ WT(GM)
DENSITY(GM/CM³)
CATHODIC TAFEL(MV)
ANODIC TAFEL(MV)

4.026
PASS
PASS
PASS
PASS

DATA SCALE

ECORR
MV/PT
DATA MAX
DATA MIN
ABS MIN
ABS MAX

-135
4
5861.897
-2.116244
9.190263E-03
5861.897

LEGEND

TEST ON CDA 102 AT 25 C
J-13 MODEL SOLUTION
CL-6; SO4-20; NO3-10; F-2
85 PPM HCO3
PURGE W/ARGON

27 MAR 1992

ADDITIONAL INFORMATION FOR SCIENTIFIC NOTEBOOK #: 019

Document Date:	11/21/1990
Availability:	Southwest Research Institute® Center for Nuclear Waste Regulatory Analyses 6220 Culebra Road San Antonio, Texas 78228
Contact:	Southwest Research Institute® Center for Nuclear Waste Regulatory Analyses 6220 Culebra Road San Antonio, TX 78228-5166 Attn.: Director of Administration 210.522.5054
Data Sensitivity:	☒ "Non-Sensitive" ☐ Sensitive ☐ "Non-Sensitive - Copyright" ☐ Sensitive - Copyright
Date Generated:	1992 through 1999
Operating System: (including version number)	DOS
Application Used: (including version number)	EG&G 342C
Media Type: (CDs, 3 1/2, 5 1/4 disks, etc.)	3-3 1/2 disks, 1 CD
File Types: (.exe, .bat, .zip, etc.)	dat, binary
Remarks: (computer runs, etc.)	CD contains: Project data files.